



BURNSIDE

**Whitevale TFPM Development
Functional Servicing and
Stormwater Management Report**

Seaton TFPM Inc.



BURNSIDE

**Whitevale TFPM Development
Functional Servicing and Stormwater
Management Report**

Seaton TFPM Inc.

**R.J. Burnside & Associates Limited
1465 Pickering Parkway Suite 200
Pickering ON L1V 7G7 CANADA**

**March 2023
300043770.0000**



Distribution List

No. of Hard Copies	PDF	Email	Organization Name
0	Yes	Yes	City of Pickering
0	Yes	Yes	Region of Durham
0	Yes	Yes	TRCA


Record of Revisions

Revision	Date	Description
-	March 8, 2023	Initial Submission

R.J. Burnside & Associates Limited

Report Prepared By: 
 Melissa Haw, E.I.T.
 Stormwater Management, Land Development
 MH:tm

Report Prepared By: 
 Heather Simpson, C.E.T., B.A., M.A.
 Designer, Land Development
 HS:tm

Report Reviewed By: 
 Jody Smith, P.Eng.
 Water Resources Engineer
 JS:tm


Report Reviewed By: 
 Sam Webb, P.Eng.
 Project Engineer, Land Development
 SW:tm



Table of Contents

1.0	Introduction	1
1.1	Purpose and Scope	1
1.2	Study Area	5
2.0	Summary of MESPA Recommendations and Design Criteria.....	8
2.1	Natural Heritage System (NHS).....	9
2.1.1	Water Augmentation.....	11
2.1.2	Fencing Requirements Adjacent to the NHS.....	11
2.1.3	Archaeological Site.....	11
2.2	MESPA Endangered Species Act Considerations	12
2.2.1	Redside Dace.....	12
2.2.2	Bobolink and Eastern Meadowlark.....	13
2.2.3	Butternut.....	14
2.3	Stormwater Management.....	14
2.3.1	Stormwater Management Facilities	14
2.3.2	Low Impact Development Measures	15
2.3.3	Areas of Special Interest	15
2.3.4	Features with Reduced Buffers	15
3.0	Existing Conditions.....	15
3.1	Hydrology / Hydraulics	15
3.2	Channel Morphology and Streambank Erosion	16
3.3	Geotechnical Conditions	18
3.4	Hydrogeological Conditions	18
3.5	Feature Based Water Balance	20
3.6	Species at Risk Considerations	22
3.6.1	Redside Dace.....	22
3.6.2	Bobolink and Eastern Meadowlark.....	22
3.6.3	Barn Swallow.....	23
3.6.4	Chimney Swift	23
3.6.5	Butternut.....	23
3.6.6	Bats	25
4.0	Municipal Servicing, Grading, and Erosion and Sediment Control.....	26
4.1	Grading	26
4.2	Grading Outside Site Limits	30
4.3	Proposed Storm Drainage	33
4.3.1	Minor Storm Drainage	33
4.3.2	Major Storm Drainage	33
4.3.3	Roof Drain Collector System.....	33
5.0	Wastewater Servicing	37
5.1	Wastewater Design Criteria	37

5.2	External Wastewater Servicing	37
5.3	Internal Wastewater Sewer Design.....	37
6.0	Water Distribution	38
6.1	Water Distribution Design Criteria.....	38
6.2	External Water Servicing and Pressure Zones	38
6.3	Internal Water Servicing.....	39
7.0	Construction Considerations	39
7.1	Construction Below the Groundwater Table	39
7.1.1	Dewatering Requirements.....	40
7.1.2	Environmentally Sensitive Areas.....	40
7.2	Erosion, Sediment, and Topsoil Control Strategy	41
7.3	Utility Requirements	42
8.0	Transportation	43
8.1	ROW Cross Sections	43
8.2	Noise Attenuation.....	43
9.0	Stormwater Management Strategy	44
9.1	Design Parameters / Terms of Reference.....	44
9.1.1	Storm Sewer Design and Modelling	45
9.2	Impervious Ground Cover	46
9.3	Uncontrolled Rear Lots to NHS.....	49
9.4	Stormwater Management Facility Details (SWMF 43)	49
9.4.1	Stormwater Management Facility 43 (SWMF)	53
10.0	Low Impact Development (LID) Measures	55
10.1	LID Measures for Feature-Based Water Balance	56
10.1.1	Outlet to U8	59
10.1.2	Outlet to G9.....	61
10.2	LID Measures for Water Quality.....	61
10.2.1	LID Measures for Recharge and Runoff Volume Reductions	61
10.2.2	LID Measures for ROWs	62
10.2.3	Recharge / Runoff LID Strategies	62
11.0	Conclusions and Recommendations	66

Tables

Table 1.1:	Summary of Whitevale TFFM Development Proposed Land Use	6
Table 2.1:	Summary of MESPA Recommendations Relevant to Whitevale TFFM Development.....	8
Table 3.1:	Comparison of MESPA and Updated Feature Drainage Areas	20
Table 9.1:	Percent Impervious Cover Based on Land Use	46
Table 9.2:	Summary of SWMF Target Release Rates	49
Table 9.3:	Summary of SWMF 43 Storage / Release Rates.....	54
Table 9.4:	Summary Table for SWMF 43 Design.....	55

Table 10.1: U8: Existing Conditions Percent Variability from Average Runoff Volumes	57
Table 10.2: U8: Proposed Conditions Percent Change in Runoff Volume from Existing Average Runoff.....	57
Table 10.3: G9: Existing Conditions Percent Variability from Average Runoff Volumes	57
Table 10.4: G9: Proposed Conditions Percent Change in Runoff Volume from Existing Average Runoff.....	57
Table 10.5: Drainage Area for Feature Augmentation	58
Table 10.6: Volume Retention Requirements	62
Table 10.7: Details of Proposed SWMF Effluent Fed-Centralized Infiltration Galleries ..	63

Figures

Figure 1-1: Key Plan	2
Figure 1-2: Neighbourhood 19 Ownership Plan.....	3
Figure 1-3: Subwatershed Areas	7
Figure 2-1: Natural Heritage Features	10
Figure 3-1: Pre-Development Storm Drainage Area Plan.....	17
Figure 3-2: NHS Feature Water Augmentation Drainage Areas	21
Figure 4-1: Grading Plan.....	28
Figure 4-2: 100-Year Capture	29
Figure 4-3: Infrastructure and Grading within Provincial NHS Tablelands	31
Figure 4-4: NHS Buffer Enhancement Plan	32
Figure 4-5: Preliminary Servicing Plan.....	34
Figure 4-6: Overland Drainage Conveyance.....	35
Figure 4-7: Diversion Swale Drainage Area	36
Figure 9-1: Roof Area Calculation (Typical House).....	47
Figure 9-2: Roof and Impervious Area Calculation	48
Figure 9-3: SWMF 43 Drainage Area.....	50
Figure 9-4: SWMF 43 Plan.....	51
Figure 9-5: SWMF 43 Sections	52
Figure 10-1: Water Augmentation Plan to Feature G9 and U8	60
Figure 10-2: Centralized LID Facility IG 43	64
Figure 10-3: Infiltration Gallery IG-43 Details.....	65

Appendices (provided digitally)

Appendix A Archaeological Study

Appendix B Geotechnical Reports

Appendix C Hydrogeological Assessment

Appendix D Feature Based Water Balance

Appendix E Environmental Input

Appendix F Diversion Swale

Appendix G Overland Conveyance

Appendix H Stormwater Management Calculations

Appendix I Recharge Volume and LID Sizing Calculations

Commonly-Used Acronym Glossary

MESP	Master Environmental Servicing Plan
MESPA	Master Environmental Servicing Plan Amendment
NHS	Natural Heritage System
NFSSR	Neighbourhood Functional Servicing and Stormwater Report
SAR	Species at Risk
ESA	Endangered Species Act
TRCA	Toronto Region Conservation Authority
MNRF	Ministry of Natural Resources and Forestry
MECP	Ministry of the Environment, Conservation and Parks
CAF	Comprehensive Aquatic Framework
SWMF	Stormwater Management Facility

Disclaimer

Other than by the addressee, copying or distribution of this document, in whole or in part, is not permitted without the express written consent of R.J. Burnside & Associates Limited.

In the preparation of the various instruments of service contained herein, R.J. Burnside & Associates Limited was required to use and rely upon various sources of information (including but not limited to: reports, data, drawings, observations) produced by parties other than, R.J. Burnside & Associates Limited. For its part, R.J. Burnside & Associates Limited has proceeded based on the belief that the third party/parties in question produced this documentation using accepted industry standards and best practices and that all information was therefore accurate, correct and free of errors at the time of consultation. As such, the comments, recommendations and materials presented in this instrument of service reflect our best judgment in light of the information available at the time of preparation. R.J. Burnside & Associates Limited, its employees, affiliates and subcontractors accept no liability for inaccuracies or errors in the instruments of service provided to the client, arising from deficiencies in the aforementioned third party materials and documents.

R.J. Burnside & Associates Limited makes no warranties, either express or implied, of merchantability and fitness of the documents and other instruments of service for any purpose other than that specified by the contract.

1.0 Introduction

R.J. Burnside & Associates Limited (Burnside) was retained by Seaton TFFM Inc. to complete this Functional Servicing and Stormwater Management Report for the Whitevale TFFM Development located north of Whitevale Road in Neighbourhood 19, west of Brock Road in the Community of Seaton, City of Pickering. The boundaries of the subject Whitevale TFFM Development Lands are indicated on Figure 1-1.

A comprehensive design framework for the entire proposed Seaton Community has been completed and documented in the Phase 1 and Phase 2 Master Environmental Servicing Plans (MESPs), prepared by Sernas Associates (now GHD) et al. September 2008 and July 2010, respectively. Further, an amendment to the Phase 2 MESP was completed to address Agency comments and provide additional data and modelling for the Seaton area (Master Environmental Servicing Plan Amendment [MESPA], July 2013).

In addition to the MESP and MESPA documents, many other component studies have been completed as a framework for development of the subject Whitevale TFFM Lands, including the Staged Servicing and Implementation Strategy (GHD 2013), and the Class Environmental Assessment for Water, Wastewater, and Transportation for Seaton, completed by the Region of Durham. These two documents confirm preliminary alignments and locations for key infrastructure necessary to serve the Seaton Community.

1.1 Purpose and Scope

As part of the Neighbourhood Planning process, the Seaton Study Area was broken down into six neighbourhoods, denoted as Neighbourhoods 16, 17, 18, 19, 20, and 21. As outlined in the MESPA for the Seaton Study Area, a Neighbourhood Functional Servicing and Stormwater Report was required for each of the six neighbourhoods in support of Draft Plan of Subdivision and / or Site Plan Applications, as stated in the City of Pickering Official Plan Amendment No. 22 (OPA No. 22, Policy 11.73). During Ontario Municipal Board (OMB) negotiations in October 2013, the requirement for a neighbourhood-scale Functional Servicing Report (FSR) was removed and subsequently the requirement to complete an FSR on a subdivision basis is required in support of the proposed draft plan for the subject Whitevale TFFM Lands. Figure 1-2 indicates the land ownership of Neighbourhood 19.





Figure Title
WHITEVALE TFPM DEVELOPMENT
 KEY PLAN

Client
SEATON TFPM INC.


Drawn AS	Checked HS/SW	Date 23/01/31
Scale 1:7500	Project No. 300043770	

Figure No.
1.1



LEGEND

--- NEIGHBOURHOOD BOUNDARY



BURNSIDE

Client
SEATON TFPM INC.

Figure Title SEATON NEIGHBOURHOOD 19		
LAND OWNERSHIP		
Drawn AS	Checked SW	Figure No. 1.2
Scale 1:15000	Project No. 300043770	

The purpose of this FSR is to provide more functional design of the Whitevale Land Holdings of Seaton TFPM Inc. and further refine the servicing routing, environmental constraints, and Stormwater Management Facility (SWMF) location, size, and outfall locations presented in the MESPA. The MESPA is an overarching guidance document only, and refinement to servicing routes and infrastructure locations based on additional field information and conditions, are specified in the FSR.

Through consultation with both Toronto and Region Conservation Authority (TRCA) and the City of Pickering (the City), an annotated Table of Contents was developed to establish the scope of work required for the preparation of the NFSSRs. This FSR generally follows the format of the established NFSSR Table of Contents. In addition, this FSR has been completed in accordance with Pickering OPA No. 22 and relevant guidelines, including the City of Pickering's Stormwater Management Guidelines (July 2019), Toronto and Region Conservation Authority's SWM Criteria (August 2012), Region of Durham Design Criteria, and the Ministry of Environment, Conservation and Parks (MECP) Stormwater Management Planning and Design Manual (2003). More recently (2017), revisions to SWMFs were made to address design guidelines from the MNRF with respect to best management practices for Redside dace habitat.

There are a number of policies within Pickering's OPA No. 22 that provide guidance and direction as follows, which have been reviewed and followed in the preparation of this FSR:

- City policy on Seaton Natural Heritage System (NHS) – Table 3:
 - Provides direction on grading and infrastructure within the NHS.
- City policy regarding development – Section 11.37 (g) through (k):
 - Provides direction regarding water management (both ground and surface water and both quantity and quality control requirements).
- City policy on Sustainable Water Management – Section 11.44 (a) and (b):
 - Requires the implementation of Low Impact Development (LID) measures and the incorporation of a treatment train approach to stormwater management.
- City policy on Stormwater Management Facility (SWMF) Considerations – Section 11.45 (a) through (j):
 - Provides guidance for the location and design of SWMFs and LID measures.
- City policy on NFSSR – Section 11.73 (a) through (r):
 - Requires the preparation of NFSSRs in support of development applications and outlines the NFSSRs requirements.

The MESPA provides conclusions and recommendations on the following topics, which have all been considered in preparation of this FSR:

- Water resources issues, including the hydrogeological assessment, groundwater modelling, water balance modelling, surface water hydrology for erosion, quantity control target release rates and volumes, natural feature-based water balance assessments, and recommended stormwater management strategies including low impact development measures (Chapter B).
- Existing and planned transportation infrastructure, traffic data, proposed road and transit networks, and road crossing design of the NHS (Chapter C).
- Municipal servicing needs, including service areas, trunk water and wastewater services, non-Municipal utilities, and preliminary servicing cost estimates (Chapter D).
- Endangered Species (Chapter E).
- Potential impacts to aquatic systems and a fish habitat compensation framework (Chapter F).
- Major community facilities and trail connections, including the identification of needs, criteria, and location recommendations for high schools, emergency and operational support facilities, parks, indoor recreational facilities, libraries, trail connections, police, fire, and other uses (Chapter G).
- Public consultation, including agency consultation, public information centres, meetings with review agencies, and Aboriginal consultation (Chapter H).
- Development phasing, including early development of employment lands, cost sharing, and implementation agreements (Chapter I).
- Future study requirements (Chapter J).
- Future monitoring requirements (Chapter K).

This FSR addresses the Municipal Servicing, Grading, and Stormwater Management requirements, in general accordance with the intent of the NFSSR Table of Contents. It includes a summary of the MESPA findings and direction pertaining specifically to the subject Plan of Subdivision; a summary of existing conditions, as per the MESPA and further field work completed for the FSR including:

- Assessment of Species at Risk (SAR) protected under the *Endangered Species Act, 2007* (ESA).
- Conceptual Servicing and Grading.
- Conceptual Grading of Stormwater Management Facilities.
- Locations and sizing of required LID Measures.

1.2 Study Area

The subject lands are located within Neighbourhood 19 of the Seaton Community in the City of Pickering, Regional Municipality of Durham. The Whitevale TFFM Development is located approximately 900 m west of Brock Road, 500 m south of Highway 407 ETR.

Whitevale TFPM Development Functional Servicing and Stormwater Management Report
March 2023

The Development Lands are tributary to and in proximity to both the Ganatsekiagon Creek and Urfe Creek (refer to Figure 1-3).


The study area is located directly north of Phase 2 of the Mattamy Whitevale Development. Detailed Design of Whitevale Phase 2 will commence in 2023. Infrastructure within the Whitevale development is required to support the development of the subject lands.

The study area is comprised of mainly active agricultural tablelands with natural heritage features around the periphery. The Site currently has undulating topography, with slopes throughout the Site ranging from less than 1.0% to as much as 12% in some areas.

The proposed land use breakdown for the Whitevale TFPM Development lands is summarized Table 1.1.


Table 1.1: Summary of Whitevale TFPM Development Proposed Land Use

Proposed Land Use	Total Approx. Area (ha)
Detached Lots	6.81
Rear Lane Towns	0.32
Back to Backs	0.51
Towns	1.77
Site Plan Block	0.89
School	2.56
Park	0.94
SWM Pond 43	1.74
Open Space / Trailhead	0.10
Roads	4.72
Total	20.36



LEGEND

	NEIGHBOURHOOD BOUNDARY
	EXISTING WATERCOURSE
	SUBWATERSHED BOUNDARY
	NHS CROSSING
	SWM FACILITY LOCATION
	NATURAL HERITAGE SYSTEM



Client
SEATON TFPM INC.

Figure Title
WHITEVALE TFPM DEVELOPMENT
SUBWATERSHED AREAS

Drawn AS	Checked SW	Date 23/02/09	Figure No. 1.3
Scale 1:10,000	Project No. 300043770		

2.0 Summary of MESPA Recommendations and Design Criteria


The MESPA provided conclusions and recommendations on a range of items relevant to the subject lands and surrounding developments in Neighbourhood 19. The MESPA provided a summary table of the components and their implications specific to Neighbourhood 19 (MESPA Table B11.10). This has been reproduced in Table 2.1, specific to the Whitevale TFFM Development. Refer to Figure 2-1 for further details.

Table 2.1: Summary of MESPA Recommendations Relevant to Whitevale TFFM Development

Study / Design Component	Neighbourhood 19 Requirements (Whitevale TFFM Development)		
	Ganatsekiagon Creek	Urfe Creek	MESPA Reference
Stormwater Management Facilities (SWMFs)	N/A	SWMF No. 43	Drawing B11.1 for SWMF locations
On-Site Control Areas (OSCA)	N/A	N/A	Drawing B11.1 for OSCA locations
Feature-Based Water Balance			
Roof and / or Rear Yard Runoff to Wetlands	G9 East	U8	Drawing B11.1b for wetland locations
SWMF Discharge to Wetlands	N/A	N/A	Drawing B11.1b for wetland locations
Roof and / or Rear Yard Runoff to woodlands	N/A	N/A	Drawing B11.1 for woodland locations
Roof and / or Rear Yard Runoff to Headwater Drainage Feature (HDF)	N/A	N/A	Drawing B11.1 for HDF locations
LID Measures	5 mm recharge requirement	5 mm recharge requirement	As outlined in Section B11.3
Watercourses for Further Study	N/A	N/A	Drawing B11.1 for locations
Areas of Interest	N/A	N/A	N/A
Reduced Buffer Areas	N/A	N/A	N/A
Crossings of the NHS	N/A	N/A	N/A

2.1 Natural Heritage System (NHS)

The development limit for the subject lands was established as part of the historical land exchange with the province. The west limit of the subject lands is bounded by the Ganatsekiagon Creek NHS, which includes woodlands, wetlands, hedgerows, and watercourse features. The east limit of the development is bound by the Urfe Creek NHS, which includes wetlands, woodlands, and watercourse features. The Natural Heritage Features are delineated on Figure 2-1. The recommendations of the MESPA related to the NHS adjacent to the subject lands are described below.



LEGEND


	HEADWATER DRAINAGE FEATURE
	NEIGHBOURHOOD BOUNDARY
	EXISTING WATERCOURSE
	WETLANDS
	NATURAL HERITAGE SYSTEM
	WOODLANDS



Client
SEATON TFPM INC.

Figure Title
WHITEVALE TFPM DEVELOPMENT
NATURAL HERITAGE FEATURES

Drawn AS	Checked SW	Date 23/02/09	Figure No. 2.1
Scale 1:10,000	Project No. 300043770		



2.1.1 Water Augmentation

The MESPA identified a number of features within the NHS that may potentially be impacted by the proposed Whitevale TFFM Development. This includes Wetland Feature G9, and Wetland Feature U8. Due to the general nature of development, the post-development drainage areas may not mimic pre-development conditions because of grading alterations and an increase in impervious surfaces. Consequently, the MESPA determined that clean water augmentation is necessary to compensate for changes in drainage area and increased imperviousness. The following augmentation measures are outlined in the MESPA document, specific to the Whitevale TFFM Development:

- Wetland Feature G9 East to be augmented with 0.2 ha of roof and / or equivalent rear yard drainage directed to the wetland via the implementation of LIDs (MESPA Table B11.2).
- Wetland Feature U8 to be augmented with 0.2 ha of roof and / or equivalent rear yard drainage directed to the feature via the implementation of LIDs (MESPA Table B11.2).

2.1.2 Fencing Requirements Adjacent to the NHS

The MESPA recommends a 1.2 m high black vinyl-coated chain link fence where lots abut a Stormwater Management Block or where lots are within 40 m (30 m buffer + 10 m) of a significant wetland feature within the NHS.

Based on the approved previous approved landscaping plans, 1.5 m high black vinyl-coated fence was installed between all residential lots and NHS lands. Further fencing requirements (such as surrounding Pond Blocks and outfall access roads) in accordance with the City's Standards and TRCA preferences will be determined during Detailed Design.

2.1.3 Archaeological Site

In conjunction with the MESPA, an archaeological assessment was carried out for the Wonowin Site (AIGs-329), an approximately 1.8 ha area representing a Middle Iroquoian (Ancestral Wendat) village, dating ca. AD 1300-1350. The Wonowin Site is located on the southwest corner of the planned intersection of Peter Matthews Drive and Street C. A 20 m protective buffer was established around the archaeological site as part of the Stage 3 Archaeological Assessment, with lands internal to the buffer to be preserved through incorporation within the NHS. Refer to Appendix A for details of the Stage 3 Archaeological Assessment. The development limits of the subject Whitevale TFFM Site do not encroach within the 20 m protective buffer.

2.2 MESPA Endangered Species Act Considerations

At the time of the MESPA, five SAR listed as Endangered or Threatened under the ESA were identified on the Seaton lands:

- Least bittern (*Ixobrychus exilis*).
- Redside dace (*Clinostomus elongatus*).
- Bobolink (*Dolichonyx oryzivorus*).
- Eastern meadowlark (*Sturna magna*).
- Butternut (*Juglans cinerea*).

The Least bittern record, provided by the MNRF, was located within the Natural Heritage System (NHS). However, the location of this occurrence did not contain suitable habitat conditions for Least bittern when investigated by the MESPA team. Suitable habitat was noted elsewhere in the NHS and the MESPA concluded that there would be no negative impact on this species within the approved development limit; therefore, no further work or protection measures are required in Seaton with regard to Least bittern. Additionally, the subject lands do not contain suitable habitat (wetlands, with a preference for cattail marshes with a mix of open pools and channels) for this species.

A summary of information pertaining to SAR in Neighbourhood 19, based on the MESPA, is provided in the following subsections. Due to the passage of time since detailed field investigations were undertaken, SAR that have been uplisted provincially and / or federally, and site-specific considerations, additional ecological work will be required. Additional SAR investigations are required as part of individual Environmental Site Assessments that were not studied as part of the MESPA, including Barn swallow (*Hirundo rustica*), Chimney swift (*Chaetura pelagica*) and SAR bats that may be present on or adjacent to the approved development limit. These additional studies are discussed in more detail in Section 3.6.

Overall Benefit Plans are outlined in detail in the MESPA for Redside dace, Bobolink, Eastern meadowlark, and Butternut. The following provides an outline of the MESPA findings and recommendations relevant to Whitevale TFPM Development, within the draft plan approved development limit (i.e., the tablelands).

2.2.1 Redside Dace

Numerous occupied and recovery reaches for Redside dace were identified by MNRF in portions of three subwatersheds in the eastern half of the Seaton lands, consisting of Ganatsekiagon Creek, Urfe Creek, and Brougham Creek. Given the scale of development within the Seaton lands, the MESPA advocated a subwatershed scale approach, consistent with the Redside Dace Recovery Strategy (Redside Dace Recovery Team, 2010) and MNRF guidance available at that time. A suite of overall

Whitevale TFFM Development Functional Servicing and Stormwater Management Report
March 2023

benefit opportunities was identified in the MESPA, through field investigations and consultation with the MNR and TRCA. Restoration opportunities included the removal of barriers to fish passage, online pond removals, localized channel rehabilitation works where channels had been impacted by recreational vehicle access, and riparian enhancement plantings.

The extent of regulated Redside dace habitat and the Overall Benefit Plan have been refined since completion of the MESPA, through the development of the Comprehensive Aquatic Framework (CAF; Beacon et al., 2013).

The Whitevale TFFM Development Site is bordered by Ganatsekiagon Creek to the west and Urfe Creek to the east, both of which contain regulated Redside dace habitat as identified in the MESPA, CAF, and Aquatics Species at Risk Mapping (DFO, 2018). The adjacent Ganatsekiagon Creek (Reach GB6-1) and associated wetland (G9) are both considered contributing Redside dace habitat. Urfe Creek (Reach UB7) has been identified as recovery habitat in the vicinity of the project site. As such, the proposed development area will be obligated to provide appropriate mitigation to avoid impacts (direct and indirect) to the adjacent aquatic environments. When impacts to regulated habitat are anticipated, Overall Benefit Permit(s) from the MNR in support of the proposed development may be required. The CAF document was prepared subsequent to the MESPA in this regard and provides additional details on reach delineation (contributing, recovery, and occupied habitat), Overall Benefit opportunities and ESA permitting requirements.

Further assessment of Redside dace, within the approved development limit, is discussed in Section 3.6.

2.2.2 Bobolink and Eastern Meadowlark

Targeted breeding bird surveys for Bobolink and Eastern meadowlark were not undertaken in support of the MESPA. Based on data provided by MNR, there were 18 records of probable breeding pairs of Bobolink recorded within the Seaton Lands, split evenly between the NHS and the developable area. At the time of the MESPA, there were no permit exemptions for development within Bobolink habitat under the ESA. As such, the MESPA proposed a Development Plan for Bobolink and Eastern meadowlark for land parcels that were draft approved on December 17, 2013. This Plan identified four locations in the NHS that would provide suitable habitat for Bobolink, that were of suitable size and vegetation type (i.e., 0.49 to 2.5 ha minimum territory size and did not contain woodland or wetland habitats). The total area for those four locations was approximately 54 ha. This proposed Development Plan was anticipated to support more than 22 breeding pairs and would provide habitat for the nine records of breeding pairs that would be displaced by the development. The Development Plan does not apply to the subject lands as they were not draft plan approved at the time the Plan was

developed. Additional details related to the current ESA approvals process are provided in Section 3.6.

2.2.3 Butternut

As outlined in the MESPA, the FSR is required to investigate the presence of Butternut trees in the approved development limit and does not include infrastructure (e.g., grading, access roads, LIDs, and SWMF areas) located outside of the approved development limit, where there may be intrusions into the NHS. As Butternut has a general habitat of 50 m from the stem (pers. corr. MNRF, 2018), if Butternut trees are identified in these areas or in the 50 m vicinity, then the ESA applies.

Further assessment of Butternut trees within the approved development limit is discussed in Section 3.6.

2.3 Stormwater Management

The MESPA frames the Stormwater Management Plan for the Seaton Community. The following stormwater management measures and / or considerations are outlined:

- End-of-pipe SWMFs (wet ponds) are specified to provide quantity control (where applicable), an enhanced level of water quality control and erosion control.
- Water augmentation requirements as identified in Section 2.1.1 above.
- Roof drainage to be directed to LID measures, where feasible.
- 5 mm rainfall volume retention via LIDs.

2.3.1 Stormwater Management Facilities

Detailed Stormwater Management Modelling was completed, through the MESPA and the Duffins Creek Hydrology Update, 2012 (DCHU), to identify the best approach to minimize erosion and negative impacts to the receiving watercourses. As a result, the following was recommended for the Whitevale TFPM Development Lands in Neighbourhood 19:

End-of-pipe SWMF 43 is to provide the following:

- **Water Quality** – Enhanced protection (minimum 80% total suspended solids removal), based on the MECP SWM Manual (2003).
- **Erosion Control** – Provide extended detention of the 25 mm Rainfall Event for a minimum of 120 hours. This is achieved through the criteria established in Table B11.1 of the MESPA:
 - Unitary Storage Volume: 250 m³ / impervious ha (based on post-development area).
 - Unitary Discharge: 0.6 L/s/ha (based on pre-development area).

- **Water Quantity** – Control of peak flows to target rates established in the DCHU for the 2- through 100-year, 12-hour Atmospheric Environmental Service (AES) Storms.

Stormwater Management controls are discussed in greater detail in Section 9.0.

2.3.2 Low Impact Development Measures

The MESPA recommended Low Impact Development (LID) Measures to address water balance conditions for natural features, as well as for maintaining overall groundwater recharge and providing surface water runoff volume reductions in the developed areas. LID measures will provide retention of 5 mm of rainfall over certain impervious areas as follows (applicable to Whitevale TFPM and residential land use):

- All residential roof areas must be managed on the basis that 5 mm of runoff from each rooftop will be treated through LID measures that can be provided communally and / or on individual lots (at source).
- The 5 mm requirement does not apply to driveways.
- LID measures are not required for local roads, except for local roads that extend through the NHS or where they abut (i.e., physically touch) the NHS.

2.3.3 Areas of Special Interest

In Chapter J, Section 2.1 of the MESPA, 11 areas of special interest have been identified within the Seaton Community that require additional consideration at the FSR Stage. There are no Areas of Special Interest within the subject Whitevale TFPM Development (refer to Figure B5.6 of the MESPA).

2.3.4 Features with Reduced Buffers

The MESPA identified features with reduced buffers on MESPA Figures B5.6 and J2.2. There are no reduced buffer features within the vicinity of the subject lands.

3.0 Existing Conditions

3.1 Hydrology / Hydraulics

Based on the existing site topography, the pre-development storm drainage is directed towards the two watercourses bounding the Whitevale TFPM Lands. Those two watercourses being Urfe Creek and Ganatsekiagon Creek. Within the Whitevale TFPM subdivision limits, approximately 3.99 ha drains to Ganatsekiagon Creek and 17.08 ha draining to Urfe Creek under existing conditions (refer to Figure 3-1). It should be noted that 1.99 ha (of the 17.08 ha) is part of the Mattamy Whitevale Lands to the south of the subject site. Under existing conditions, this area drains to the TFPM Lands;

however, under proposed conditions drains to SWMF 44 in the Mattamy Whitevale Lands.


The 2012 Duffins Creek Hydrology Update – Final February 2013 (DCHU) provides existing and future conditions peak flow rates for the 2- through 100-year AES Storm Events. The study provides unitary release rates and quantity control storage volumes. The study also concludes that quantity controls are not required for the Regional Storm Event.

An update to the hydraulic model and regulatory floodlines for Seaton has been undertaken and documented in a Report entitled Seaton Floodline Mapping Study Update, Seaton Lands, City of Pickering (GHD 2013). The updated mapping was based on the flows presented in the 2012 DCHU. The hydraulic model and floodlines presented in the Seaton Floodplain Mapping Study Update (2013) have been utilized in this FSR for the purposes of providing conceptual design of SWMF and NHS crossings.

3.2 Channel Morphology and Streambank Erosion


Channel Morphology and Streambank Erosion was studied in depth for existing conditions in the Seaton MESP Phase 1 Existing Conditions Report (Sernas et al. 2008) and the MESPA. Meander belt widths for existing conditions were presented in the individual SWM Matrices available in Chapter B, Appendix B6-B of the MESPA (2013). A summary of the field work and characterization of the findings and constraints is provided in Section 4.0 of the Phase 1 MESP and Chapter B, Section 5.9.1 of the MESPA.

Erosion-sensitive sites were analyzed in the MESPA and the reaches under study in this report were not identified as sensitive erosion sites. Refer to Drawing B5.5 in the MESPA which identifies the Sensitive Erosion Sites.



LEGEND

- SUBWATERSHED BOUNDARY
 - SUBDIVISION BOUNDARY
 - URFE
 - GANA
 - UNCONTROLLED REAR YARD DRAINAGE AREAS TO NHS
- EXISTING SUBWATERSHED ID
DRAINAGE AREA IN HECTARES
- EXISTING DRAINAGE AREA TRIBUTARY TO URFE CREEK
17.08 ha
- EXISTING DRAINAGE AREA TRIBUTARY TO GANATSEKIAGON CREEK
3.99 ha



BURNSIDE		WHITEVALE TFPM DEVELOPMENT PRE-DEVELOPMENT STORM DRAINAGE AREA PLAN	
Client <p style="text-align: center;">SEATON TFPM INC.</p>	Drawn MH	Checked HS	Date 22/11/17 Project No. 300043770
			Figure No. <h1 style="margin: 0;">3.1</h1>

3.3 Geotechnical Conditions

Three geotechnical investigations have been completed on the subject Development Lands:

- Technical Memorandum, Golder Associates, August 2012.
- Technical Memorandum, Golder Associates, August 2015.
- Geotechnical Investigation, AME, April 2006.

Two of these Geotechnical Investigations were completed for subject Development Lands prior to the NFSSR 19 being completed in 2013. Additional Geotechnical Analysis will be completed prior to Detailed Design. However, for the purposes of this FSR, the geotechnical content in the GHD FSSR for the Ontario Infrastructure and Lands Corporation (OILC) in 2015, and the Neighborhood 19 NFSSR in 2013, contains sufficient geotechnical information for this preliminary design and in support of the proposed draft plan. Copies of the relevant Reports have been included in Appendix B.

The Geotechnical Investigations confirm that the surficial overburden materials on the subject lands are predominantly sandy-silt till to silty sand to sand deposits. The thickness of the till in most of the boreholes was at least 4.0 m deep. The native soil encountered in the borehole studies was noted as suitable for use in on-site earthworks.

3.4 Hydrogeological Conditions

Groundwater levels were observed through inspection of multiple monitoring throughout the subject area, with follow-up readings for settled groundwater levels. Throughout the property, the groundwater depths varied spatially and seasonally. The shallowest depth observed was 0.42 m, and the depth was shallower near the south edges of the Site (AME MW-2-92-2 and MW2-92-15). The groundwater depth was deeper in the higher upland areas near the centre of the Site (AME MW-2-92-4) with several observations below 6.4 m deep.

On a broader scale, groundwater levels have been measured in monitoring wells, stream piezometers, and wetland piezometers across the Neighbourhood 19 area to characterize the depth to water table, shallow groundwater flow directions, and recharge and discharge conditions. Field tests have also been completed to assess the soil hydraulic conductivity and the potential for use of LID measures for stormwater infiltration. Details of the Hydrogeological Investigations and findings are provided in the Seaton Neighbourhood 19 Hydrogeological Assessment Report (Burnside, 2013), in Appendix C.

Generally, the groundwater flow patterns are interpreted to essentially follow the surface water drainage patterns, with flow generally moving from higher areas to lower areas,

(i.e., southwards across the Neighbourhood with convergence towards the watercourse valleys). The depth to the water table varies across the study area and is generally found at depths approximately 2 m below grade or shallower in the sandier upland areas (recharge areas) and seasonally at grade along the lower valley elevations and incised watercourse valleys (discharge areas).

The results of the Hydrogeological Study show that the till overburden deposits found over most of the Neighbourhood area have relatively low hydraulic conductivity. This limits groundwater movement through the thick, surficial till sediments such that overall groundwater recharge and discharge volumes in the Neighbourhood tend to be quite low. Much of the interaction between groundwater and surface water in the till areas is interpreted to occur very locally and at shallow depths. In the south and southeastern portions of the Neighbourhood, there are sandier sediments mapped at surface along the Iroquois shoreline and alluvial deposits along the watercourse valleys that have higher hydraulic conductivity than the surrounding till. There may also be local areas where small shallow sand layers and lenses within the till (interstadial deposits) have higher hydraulic conductivity and effect local lateral movement of groundwater; however, the more substantial lateral flows occur regionally in the higher hydraulic conductivity sand sediments of the underlying Thorncliffe Aquifer Complex. The Thorncliffe sands are interpreted to intersect the Urfe Creek tributaries in the eastern portion of the study area, and Ganasetkiagon Creek in the southern portion of the study area.

Regional groundwater discharge from the Thorncliffe Aquifer is interpreted to contribute to the watercourses and wetlands along the lower reaches of these creeks, and particularly to the wetlands below and along the Iroquois shoreline at the southern boundary of the Study Area. Based on modelling of the groundwater flow conditions, the MESPA (Final, 2013) reported that groundwater contributions to the wetlands accounted for less than 5% of the net wetland water budget and concluded that the wetlands in the study area generally rely on surface water contributions (precipitation and surface water runoff). The MESPA also presented detailed surface water balance assessments and modelling for the natural features (wetlands, woodlands, and headwater drainage features) in the Neighbourhood and provided feature-based target water volumes to maintain the natural features. The MESPA findings and water volume targets for the features for Neighbourhood 19 have been summarized in the Hydrogeological Assessment Report in Appendix C.

It was envisioned in the MESPA that clean roof drainage from the Development Lands could be conveyed to the natural heritage features to maintain the water balance conditions. Distribution of surface water inputs to the natural features through the use of swales, shallow infiltration trenches, or other spreading techniques located in the feature buffers is generally recommended. The proposed feature augmentation system is described in Section 10.0 of this FSR.

The use of LID measures across all areas of the Neighbourhood was also recommended in the MESPA, to maintain overall recharge to the groundwater regime, and minimize (where possible) the volumes of runoff in the developed areas. Techniques considered are outlined in Section 10.0. Based on the soil characterization and infiltration testing completed during the NFSSR studies, it has been concluded that much of the Neighbourhood 19 area is not considered suitable for the use of large-scale subsurface infiltration techniques due to the low soil hydraulic conductivity and relatively highwater table conditions that present constraints for such techniques.

It is noted; however, that smaller-scale and shallow subsurface infiltration measures, such as galleries, trenches, and soak-away pits may still be feasible in till areas where there is sufficient depth to water table. All areas of Neighbourhood 19 are considered suitable for surface measures, such as directing roof leaders to grass swales, bioswales, etc. This is because the surficial till sediments tend to be weathered and fractured, and this improves the effective shallow hydraulic conductivity. Such measures can be located in the NHS buffers.

Lastly, given the nature of the subsurface stratigraphy, specifically the Halton Till Cap, and nature of the interaction with groundwater, there is no requirement to recharge the Thorncliffe Aquifer with an additional 5 mm volume as was the case in Neighbourhood 16 (Mattamy Taunton Development).



3.5 Feature Based Water Balance

As discussed in Section 2.1.1, the MESPA defined areas of required water augmentation for wetlands, woodlots, and headwaters. Within or adjacent to the subject lands, there are two features requiring augmentation; Wetland U8 and Wetland G9 (see Figure 3-2). The drainage areas to each feature were reviewed based on updated topographical information. Refer to Table 3.1 for a comparison of the MESPA and updated drainage areas to each feature within the subject lands.

Table 3.1: Comparison of MESPA and Updated Feature Drainage Areas

Feature	Existing Condition Drainage Area (ha)		Proposed Conditions Drainage Area (ha, excluding augmentation)	
	MESPA	FSR	MESPA	FSR
Wetlands				
U-8	5.4	9.14	3.6	6.17
G-9	4.6	4.88	2.3	2.37

Refer to Figure 3-2 for delineation of the feature drainage areas.



BURNSIDE

Client: **SEATON TFFM INC.**

Figure Title			
WHITEVALE TFFM DEVELOPMENT			
NHS FEATURE WATER AUGMENTATION DRAINAGE AREAS			
Drawn	Checked	Date	Figure No.
AS	HS/SW	22/11/17	
Scale	Project No.		3.2
1:2,500	300043770		

Based on the updated drainage areas, a PCSWMM Model was prepared for each feature since they were not specifically modelled in the MESPA. A continuous simulation model was run for the six years of continuous rainfall data (1998 to 2003) in accordance with the MESPA. The average months and annual runoff volumes were then extracted from the model and tabulated for comparison to existing conditions. In accordance with the MESPA, the months of March through to October have been highlighted as per TRCA request. The resulting tables are presented in Appendix D, and the PCSWMM files are included with the digital submission (see Section 10.1 for details).

3.6 Species at Risk Considerations

Additional species have been added to the ESA since the completion of the MESPA. As stated in the MESPA, it is the responsibility of all proponents to ensure that the ESA and its regulations are met as development proceeds. The following SAR may be present on or adjacent to the development limits, based on a review of background sources, known records for the area, and previous field surveys that have been conducted for neighbouring sites. Additional ecological field work was conducted by Burnside in 2019, largely due to the passage of time and the uplisting of SAR.

3.6.1 Redside Dace

The MESPA, CAF, and Process for ESA Authorizations (v.4) (Seaton Environmental Consulting Team, 2018; Appendix E) outline works that would require Overall Benefit Permits, with respect to Redside dace. It is anticipated that pursuance of Overall Benefit Permits, or Letter of Advice (LOA) through consultation with MNRF, will be required during Detailed Design when impacts to regulated Redside dace habitat are anticipated. However, as noted above, details provided in this report discuss activities pertaining to the approved development limit and do not address any temporary or permanent alteration to fish and fish habitat, including regulated Redside dace habitat features.

Though direct impacts to Redside dace habitat will not be addressed until Detailed Design, indirect impacts (i.e., water quality) may occur as a result of the proposed activities within the development limit. As such, appropriate mitigation strategies, including a detailed ESC and Water Quality Monitoring Plan, will be required in support of the works. A Letter of Advice (LOA) will be pursued through the MECF following the development of a Construction Monitoring Plan (CMP), in support of the grading and earth works component of the project.

3.6.2 Bobolink and Eastern Meadowlark

As discussed in Section 2.2, all of the land parcels within the Seaton area that were draft approved on December 17, 2013 have been addressed comprehensively by one

Development Plan (MNR File Number AU-DP-001-15, accepted on February 6, 2015). As reported in the Process for ESA Authorizations (v.4), lands shown to be owned by Infrastructure Ontario (IO) did not receive draft approval which includes the subject lands (Seaton Environmental Consulting Team, 2018). Following the MESPA, the IO lands in Neighbourhood 19 were assessed for Bobolink and Eastern meadowlark habitat and inventoried in 2013 and 2014 (GHD, 2015; Seaton Environmental Consulting Team, 2018). The subject lands were found to not have appropriate habitat for Bobolink or Eastern meadowlark. Refer to Appendix E for a copy of these reports. Due to the passage of time, site-specific investigations were undertaken to confirm the absence of these species on the subject lands. Breeding bird surveys, including a specific search for grassland birds, were conducted on May 27, June 12, and June 24, 2019 by a Burnside Avian Specialist. No Bobolink or Eastern meadowlark were recorded during any survey within the development limit.

3.6.3 Barn Swallow

At the time of breeding bird surveys in 2019, Barn swallow was listed as Threatened under the ESA. As of January 25, 2023, Barn swallow has been reclassified to Special Concern under the ESA and no longer received general habitat protection. Regardless, the 2019 data provides confirmation that nesting and foraging habitat for Barn swallow is absent from the subject lands.

3.6.4 Chimney Swift

Chimney swift are listed as Threatened under the ESA. They have historically nested / roosted in large, hollow trees, other tree cavities, and cracks in cliffs. Currently, the majority are found in anthropogenic structures, most commonly in uncapped chimneys (Cadman *et al.*, 2007). Based on a review of aerial imagery, Chimney swift habitat (chimneys on anthropogenic structures) is not present on the subject lands.

3.6.5 Butternut

As outlined in the MESPA, the FSR is required to investigate for the presence of Butternut trees in the approved development limit, and in NHS areas where any development-related activities may intrude.

This section only describes the requirements under the ESA for those Butternut trees found within and immediately adjacent to the development limit and disturbance limits, as documented by the Seaton Environmental Consulting Team in December 2014, and reported in the Process for ESA Authorizations (v.4) (Seaton Environmental Consulting Team, 2018; Appendix E) and the Neighbourhoods 18, 19, and 21 Butternut Health Assessment (Niblett, 2013; Appendix E) in the Seaton Neighbourhood 19 Functional Servicing and Stormwater Report (FSSR) – SWMF No. 43 (GHD, 2015). An updated

Whitevale TFPM Development Functional Servicing and Stormwater Management Report
March 2023

Butternut Health Assessment (BHA) was conducted in August 2019 for the area within the development limit and 50 m adjacent habitat area as the previous data is considered outdated. Any required authorizations under the ESA for clearing within the development limit will be undertaken prior to the submission of this FSR and any required authorizations under the ESA for infrastructure intrusions into the NHS will be undertaken during Detailed Design.

A BHA is required to assess the health of the tree(s) in question, as it relates to infection with Butternut canker (*Ophiognomonia clavigignenti-juglandacearum*), a fungal disease that often results in tree mortality. The Endangered status of Butternut is based on declines in the species due to Butternut canker. The BHA determines to which Category (1-'non-retainable', 2-'retainable', 3-'achievable') the tree belongs, and if the tree is a hybrid. Category 1 (non-retainable) and hybrid trees are not protected under the ESA. Categories 2 (retainable) and 3 (achievable) trees are protected under the ESA. General habitat for Butternut trees includes suitable areas within a 50 m radius, centered on the trunk or stem of each Butternut tree in Ontario (regardless of its size). Category 1 habitat is 25 m from the trunk or stem and includes the immediate habitat conditions surrounding the tree that support the growth and persistence of the tree over its lifetime. Category 2 habitat is 25-50 m from the trunk or stem and includes the surrounding habitat conditions, supporting the cores nut dispersal and seedling establishment areas up to 50 m from a parent tree. In discussion with MNRF (now MECP), it has been established that for the area up to 50 m from a stem should be considered for potential impact to the individual butternut and for reproductive habitat in order to avoid the requirement for authorizations under the ESA. While any activity in the 0-25 m zone is typically considered an impact, activity in the 25-50 m zone may not be considered an impact and is typically discussed with MECP Biologists prior to proceeding with authorizations. Under the ESA, a maximum of 15 Category 2 trees and 5 Category 3 trees may be registered as being affected (i.e., killed, harmed, or taken) by any one development application. Beyond this threshold, remaining trees must be retained, or an Overall Benefit Permit is required.

Niblett Environmental Associates Inc. (2013) identified 5 'Retainable' (now called Category 2) and 10 'Non-retainable' (now called Category 1) Butternut on and within 50 m of the subject property. The Seaton Community Process for ESA Authorizations (v.4) (Seaton Environmental Consulting Team, 2018) identified 5 Category 2 (retainable) and 11 Category 1 (non-retainable) Butternut trees on and within 50 m of the subject property. Given the date of these observations (prior to December 2014), the MNRF (now MECP) requires that these BHAs are updated to review for Category 3 (archivable) Butternut, a new Category added to O.Reg. 242/08 in 2014. Additionally, it is possible that the health of these Butternut trees has changed, and / or that there are additional Butternut in the area. A Burnside Ecologist conducted the updated BHA on August 30, 2019. A total of 13 Butternut trees was recorded, with two resulting as

Category 2 Butternut and the remaining 11 resulting as Category 1 Butternut. All samples tested for Butternut hybridity had no hybridity detected; therefore, they were all deemed to be pure species. As stated above, Category 1 Butternut are not protected under the ESA. The two Category 2 Butternut trees, one located within the development limit and one located immediately adjacent to the development limit, have been registered under section 23.7 of O.Reg. 242/08 on October 1, 2021 (M-103-4435454016). No other Butternut will require registration unless additional encroachment into the NHS is determined through Detailed Design. At which time, and additional Butternut search and applicable BHAs should be completed. If Butternut are found and need to be registered, the registration will occur under the updated Butternut exemptions, set out in O.Reg. 830/21.

3.6.6 Bats

There are four species of bats that are listed as Endangered under the ESA:

- Little brown myotis (*Myotis lucifugus*) – listed in 2013.
- Northern myotis (*Myotis septentrionalis*) – listed in 2013.
- Eastern small-footed myotis (*Myotis leibii*) – listed in 2014.
- Tri-coloured bat (*Perimyotis subflavus*) – listed in 2016.

Significant population declines are attributed to a rapidly spreading fungus, *Pseudogymnoascus destructans*, which causes white-nose syndrome, and thrives in caves and mines where bats hibernate. While potential hibernacula habitat for these species is not present in the subject lands or adjacent areas (i.e., no caves or mines), there is growing concern over protecting bat maternity colonies and roosting habitat for these species.

Leaf-off surveys look for trees with habitat features suitable for Little brown myotis and Northern myotis maternity roosts. These surveys were conducted for the north parcel on March 5, 2021 and for the west parcel on May 9, 2022. Leaf-off surveys were conducted for the hedgerows, woodlands, and NHS intrusions. Leaf-on surveys look for Oak (*Quercus sp.*) and Maple (*Acer sp.*) trees, with dead and dying leaf clusters, where Tri-colored bats may roost. These surveys were conducted as acoustic monitoring stations were being installed, to help influence station location.

The subject lands were surveyed using acoustic stations and exit surveys. Four acoustic stations were deployed on June 14, 2021 and retrieved on June 28, 2021. The recorders were deployed for a total of 14 nights (i.e., sunset to sunrise), to ensure the required ten days of suitable weather conditions (i.e., ambient temperatures above 10° C and no rain), per MNRF protocols. Exit surveys were conducted at three stations on the dates of June 10 and June 24.

Whitevale TFPM Development Functional Servicing and Stormwater Management Report
March 2023

No SAR bats were detected on-site. However, one Little brown myotis call was identified by Kaleidoscope software within the NHS in 2021, north of the subject lands. No intrusions are currently expected in this area. However, future SWM pond outfalls will be investigated to determine if bat habitat will be impacted. If it is found that candidate maternity bat habitat will be impacted by future intrusions, MECP will be notified, and habitat compensation requirements discussed.

An Information Gathering Form (IGF) will be submitted to MECP to detail the investigation and findings. This IGF will also include other lands included in the Whitevale area to provide a holistic view of the area and its impact on SAR. Discussion with MECP will determine the level of mitigation and compensation that may be required. Mitigation measures will require trees to be taken down in winter, outside the bat active period. Compensation in the form of a rocket-style bat box may be required.

4.0 Municipal Servicing, Grading, and Erosion and Sediment Control

4.1 Grading

The Site Grading Design will take into consideration the following requirements and constraints:

- Conform to the City's Grading Criteria.
- Match existing boundary grading conditions with some grading into the NHS buffers where setbacks allow.
- Minimize earth moving operations and work towards achieving a balanced site.
- Provide minimum cover on proposed servicing.
- Provide overland flow conveyance for major storm conditions.


Grading has been completed to match pre-development drainage patterns to the greatest extent possible. Conceptual Grading Plan has been provided in Figure 4-1.

Road grading has been designed such that the right-of-ways (ROWs) will be utilized as overland flow routes to direct the major storm system to the proposed stormwater management facilities. Overland drainage will be conveyed to SWMF 43 via the subdivision ROWs as shown on Figure 4-6.

The design of Peter Matthews Drive (Rossland Road extension) along the western TFPM frontage is under a developer-led Regional Works Spine contract which has not yet been awarded. However, as this design advances, it will be coordinated closely with the Whitevale TFPM Subdivision design to ensure that the Regional Road profile, grading transitions, culvert crossings, and stormwater management capture are all considered, among other items. In order to ensure storm flows will not cross Peter

Whitevale TFPM Development Functional Servicing and Stormwater Management Report
March 2023

Matthews Drive, a 100-year storm capture point will be required on the west side of the intersection as shown in Figure 4-2.





100 YR 1
1.57 ha
0.81
10.00 min
0.651 cms


LEGEND

⇨ EMERGENCY SPILLWAY

100 YR 2	100 YR CAPTURE ID
2.74ha	DRAINAGE AREA
0.80	RxA
12.63 min	TIME OF CONCENTRA
0.430 cms	FLOW @ 100 YR CAPTURE POINT

 100 YEAR CAPTURE AREA



	WHITEVALE TFPM DEVELOPMENT			4.2
	100 YR CAPTURE			
Client:	Drawn:	Checked:	Date:	Figure No.:
SEATON TFPM INC.	AS	SWHS	22/12/19	
	Scale:		Project No.:	
	1:1,250		300043770	

File: \\scotney\share\proj\300043770_100 YR CAPTURE.dwg Date Plotted: February 14, 2020 4:27 PM



4.2 Grading Outside Site Limits

In some locations adjacent to the Whitevale TFPM Development lands, grading within the NHS tablelands are required to meet the City's grading standards for lots and SWMFs. Where grade transitioning is required within the NHS, a slope of 3:1 is proposed to allow for stability and minimize intrusion. Utilizing erosion control methods (as presented in Section 7.2) and restoring cut or fill slopes with appropriate vegetative cover will ensure impacts to the NHS buffers will be both temporary and minimal.



Figure 4-3 shows that, in general, this grading encroachment to the NHS does not extend into the limits of vegetation but, in most cases, remains within tableland buffers that are currently (or were recently) disturbed by agricultural practices. The notion of providing a more subtle grading transition, further into the agricultural buffer around the NHS is supported and promoted by TFPM. This would provide opportunities for planting and more natural integration with the existing vegetation edge within the NHS. Further discussion with all stakeholders is encouraged to advance this opportunity for Whitevale TFPM.


In the areas around SWMF 43 where there is more significant grading proposed within the NHS, enhancement plans will be developed to maintain the functionality and connectivity of the NHS. Areas which will be enhanced are shown on Figure 4-4. Detailed enhancement plans will be developed at the Detailed Design stage, in consultation with TRCA.


Within the NHS, a diversion swale will be required to convey drainage around the boundary of the proposed lots. In the existing condition, drainage would sheet drain across the Site towards the U8 Feature. In order to avoid ponding water at the development limit and to ensure that this external drainage continues to feed the U8 Feature, a diversion swale is required to convey the flow. The drainage area contributing to this swale is delineated on Figure 4-7 and the associated 100-year peak flow utilizing the rational method was determined to be 1.62 m³/s (see Appendix F). With this peak flow, the diversion swale was found to have a flow depth of 0.65 m which can be contained within the swale and will not spill into proposed lots. During Detailed Design, the option to enhance this swale will be explored to further provide quality control for runoff entering the U8 Feature.



LEGEND

	TEMPORARY DISTURBANCE FOR GRADING WITHIN PROVINCIAL NHS
	POTENTIAL PERMANENT EASEMENTS ON PROVINCIAL NHS LANDS

 BURNSIDE		WHITEVALE TFPM DEVELOPMENT INFRASTRUCTURE AND GRADING WITHIN PROVINCIAL NHS TABLE LANDS	
Client <p style="text-align: center;">SEATON TFPM INC.</p>	Drawn AS	Checked HS/SW	Date 23/02/13 Project No. 300043770
			Figure No. <h1 style="margin: 0;">4.3</h1>



LEGEND

- BUFFER ENHANCEMENT PLANTING ZONE
- BUFFER NATIVE SEEDING ZONE
- 10m TREE LINE SETBACK
- STAKED DRIPLINE
- WATERCOURSE
- 30m FISHERIES SETBACK
- BUFFER ENHANCEMENT LIMIT
- MEANDER BELT WIDTH
- APPROXIMATE DRIPLINE

BURNSIDE

SEATON TFPM INC.

Figure Title
WHITEVALE TFPM DEVELOPMENT
NHS BUFFER ENHANCEMENT

Client	SEATON TFPM INC.	Drawn	AS
		Checked	HS
		Date	22/11/17
		Project No.	300043770
		Scale	1:2000
Figure No.	4.4		

4.3 Proposed Storm Drainage

4.3.1 Minor Storm Drainage

The Minor Storm System will consist of a series of storm sewers sized to convey the 5-year Return Period Storm to the end-of-pipe SWM facility (SWMF). The storm sewer network will be designed to the City's Design Standards. A Preliminary Storm Sewer Design is depicted on Figure 4-5.


4.3.2 Major Storm Drainage

The Major Storm System design requirements for capture and conveyance have been established in detail in previous sub-sections. The major system will be designed to convey the 100-year storm event minus the 5-year event overland via proposed roadways to the SWMF. Overland flow routes have been identified on the Preliminary Grading Plans, which are illustrated on Figure 4-1.

A preliminary analysis of the major system conveyance has been completed in support of the FSR. One critical node within the overland flow route was identified based on drainage area and slope of the road, as shown on Figure 4-6, this location has the largest major system contributing drainage area within the entire subject site. Calculation of the 100-year major system flow rates are shown in Appendix G. The analysis concluded that the roads can safely convey the major system runoff to a safe outlet at velocities and flow depths permissible according to the City's SWM Guidelines Table 5. Further analysis of the major system conveyance (including a detailed inlet capacity) will be carried out during detailed design according to the criteria in Section 4.2.3.

4.3.3 Roof Drain Collector System

As per Section 3.6, the MESPA outlined the requirement to maintain flow to features within the TFFM Lands. These features are known as U8 and G9. The general recommendation involved the redirection of clean roof or rear yard stormwater runoff be utilized for this feature augmentation. To help achieve the required augmentation a roof drain collector system (RDC) is proposed on Street 8 and Street 9. The RDC on Street 8 outlets to Feature U8 and the RDC on Street 9 outlets to Feature G9. It should be noted that Feature G9 is a part of Catchment 35, more specifically the GB6-1 Reach of the Ganatsekiagon Creek. Please refer to Section 10.0 for more details.





DVS
4.35 ha
0.70
9.60 min
1.616 cms

LEGEND

100 YR 2	100 YR CAPTURE ID
2.74ha	DRAINAGE AREA
0.80	RUNOFF COEFFICIENT
9.60 min	TIME OF CONCENTRATION
0.430 cms	FLOW @ DIVERSION SWALE

--- DRAINAGE BOUNDARY
--- 10m TREE LINE SETBACK
--- LIMIT OF DEVELOPMENT



 BURNSIDE		Figure Title		WHITEVALE TFPM DEVELOPMENT DIVERSION SWALE DRAINAGE AREA										
		SEATON TFPM INC.			<table border="1"> <tr> <td>Drawn</td> <td>Checked</td> <td>Date</td> </tr> <tr> <td>AS</td> <td>HS/SW</td> <td>22/11/29</td> </tr> <tr> <td>Scale</td> <td colspan="2">Project No.</td> </tr> <tr> <td>1:1,250</td> <td colspan="2">300043770</td> </tr> </table>	Drawn	Checked	Date	AS	HS/SW	22/11/29	Scale	Project No.	
Drawn	Checked	Date												
AS	HS/SW	22/11/29												
Scale	Project No.													
1:1,250	300043770													
				Figure No. 4.7										

5.0 Wastewater Servicing

5.1 Wastewater Design Criteria

The sanitary sewer network for the Whitevale TFPM Development will be designed to follow Region of Durham Development Standards, and MECP Design Guidelines. It will be of sufficient depth to provide adequate gravity servicing connections to all individual lots within the developments.

5.2 External Wastewater Servicing

The proposed trunk sanitary sewer network is presented in Figure D3.1 of Chapter D in the MESPA. The section of trunk sewer that goes through the Whitevale TFPM Site is noted as 1LS-1 on this Figure. Subsequent to the MESPA, an investigation of the trunk sanitary sewers within the Seaton development was completed by GHD, the subject sewer is noted as "Sub-Trunk 3" in this investigation. Further to these investigations, Burnside has prepared the Detailed Design of the Whitevale Phase 1 Development and Assignment 7C for the Region of Durham. The trunk sewer proposed on Street 1 found on Figure 4-5 is coordinated with the constructed downstream infrastructure.

5.3 Internal Wastewater Sewer Design

The internal subdivision will be serviced by a standard gravity sewer network with a minimum size of 200 mm diameter of sufficient depth to provide adequate gravity servicing connections to all individual lots.

The sewer network generally follows the proposed road grading from the high side of the Site in the northwest towards the low side of the Site near the south end of the pond, and outlets into the previously discussed trunk sewer at the southeast end of the Site.

Figure 4-5 shows a proposed internal sanitary sewer design concept for the Development.

6.0 Water Distribution

6.1 Water Distribution Design Criteria

Water distribution within the Whitevale TFFM subdivision will be used for potable domestic consumption and fire suppression and will be designed in conformance with the City's, Region of Durham, and MECP Design Standards / Guidelines. Hydrants will be spaced on local watermains to provide adequate fire protection. The Region will ensure, through analysis of its water skeleton model, that the system is capable of supplying sufficient pressure and fire flows under various demand scenarios to all areas of the Whitevale TFFM Development.

6.2 External Water Servicing and Pressure Zones

A number of feeder mains, pumping stations and reservoirs to service the entire Seaton Community are currently being designed in accordance with Durham Region's Environmental Assessment.

The Whitevale TFFM Development is located within two separate pressure zones, Zone 4 and Zone 5 pressure districts, and is, at a minimum, dependent on the following external Regional Works to be completed, that are part of the overall Seaton build-out per the MESP and CPDP EA (Refer to MESP Figure D1.1 and CPDP Figure 3.3-24):

1. Construction of Zone 1 Feedermain from Tillings Road and the Canadian Pacific Railway to Zone 1 Reservoir.
2. Construction of Zone 1 Reservoir and Zone 3 Pumping Station.
3. Construction of Zone 3 Feedermain and Reservoir.
4. Construction of Zone 4 Pumping Station.
5. Construction of Zone 4 Distribution mains from Zone 4 Pumping station along Whitevale Road to the Mattamy Whitevale development (600 mm diameter).
6. Construction of Zone 4 Feedermain.
7. Construction of Zone 5 Pumping Station and Zone 5 Elevated Tank.
8. Construction of Zone 5 Distribution mains from Zone 5 Elevated Tank, along City east / west collector (Nathaniel Hastings Drive).

As the design of the Spine Infrastructure Projects are advanced, more specific connection details will be developed in coordination with the Detailed Design of the Whitevale TFFM Subdivision.

In the event that Zone 5 water distribution infrastructure has not been fully constructed, the development may be phased along the limit of the pressure zone which will be

confirmed by the Region of Durham during Detailed Design. In this case, only items 1. to 5. in the list above would be required for lots within the Zone 4 pressure district.

6.3 Internal Water Servicing

Conceptual Watermain Layout and sizing has been prepared as part of this report. Refer to Figure 4-5 for the proposed internal water distribution design. Provisions have been made for looping through the subdivisions to provide security of supply and circulation within the Whitevale TFPM Lands. Strategic valve configurations at Detailed Design will ensure that isolation of small segments of the system can be achieved in the event of required maintenance, additional connections, or other shutdown requirements. All local watermains will be designed at 1.8 m depth below final grade.

7.0 Construction Considerations

Based on previous geotechnical recommendations and experience working in the Seaton Whitevale area, the following provisions are generally recommended for servicing installation:

- Temporary shallow excavations for sewers, trenches, basements, and utilities are not expected to pose any difficulty.
- Undisturbed natural soil is suitable for supporting watermain, sewers, manholes, etc.
- Bedding to meet the City's and Region of Durham Standards.
- Excavation in the native material below the groundwater level will require a positive system of dewatering.

There are a number of factors and conditions that should be taken into consideration when installing buried services throughout the Seaton Community. Each is discussed below.

7.1 Construction Below the Groundwater Table

The construction of buried services below the groundwater table has the potential to capture and redirect groundwater flow through more permeable fill materials typically placed in the base of excavated trenches. Over the long-term, these impacts can lower the local groundwater table. Particularly in the vicinity of local wetlands and woodlots, it is important to maintain the groundwater table levels within their natural elevation ranges in order to continue to support these natural features. Permeable trenches also have the potential to provide conduits for migration of contaminants through the subsurface.

To mitigate these effects, it is important that any services constructed below the groundwater table be constructed using best management practices to reduce or prevent redirection of groundwater flow and overall lowering of the water table adjacent

to features. This may involve the use of anti-seepage collars or clay plugs surrounding the pipes to provide barriers to prevent groundwater flow along granular bedding material and erosion of the backfill materials.

7.1.1 Dewatering Requirements

Temporary dewatering for construction may be required where sewer excavations must extend below the local groundwater table. In areas of surficial till overburden, the hydraulic conductivity of the soils is relatively low, and as such, significant dewatering is not anticipated for residential construction excavations. In these cases, groundwater and drainage can often be managed by occasional pumping of accumulated water from sumps. There are; however, areas of surficial sands and gravels that have higher hydraulic conductivity and could require more significant dewatering. Construction of deeper infrastructure could also encounter local water bearing zones that may require dewatering and / or depressurization for construction.

Should the contractor need to pump water at rates exceeding 400,000 L/d, a Permit to Take Water (PTTW) from the MECP will be required for construction dewatering. The PTTW must be obtained in accordance with the Provincial Regulations prior to dewatering activities.

7.1.2 Environmentally Sensitive Areas

For Environmentally Sensitive Areas, sediment and erosion control practices during construction will be in accordance with the Greater Golden Horseshoe Conservation Authorities Erosion and Sediment Control Guideline for Urban Construction. The following provides a general outline of the standard mitigation measures to be implemented for construction:

- **In-Water Works** – Only if necessary, will occur during the applicable fisheries window, or as otherwise directed by the MNRF.
- **Fish Rescue and Relocation** – Fish rescue will be completed by a qualified Biologist, utilizing a combination of seine nets, dip nets, and an Electrofisher. All methodologies related to electrofishing will be completed following the MNRF (2004) Guidelines. Electrofishing will only be used when less invasive methods cannot be effectively applied.
- **Construction Supervision** – A team comprised of Engineers, Ecologists, and Fluvial Geomorphologists will be present as necessary during construction to ensure proper function of the ponds, outlets, and instream works. This will enable quick and appropriate response to construction issues and ensure implementation of important design details and construction techniques. As per a signed Agreement per Draft Conditions from the TRCA, Burnside will have a CISEC Certified Professional

complete periodic inspections of sediment and erosion control installations on-site to ensure they are functioning as designed.

- **Erosion Control** – A multiple barrier approach to sediment and erosion control will be used, where feasible. Detailed Erosion and Sediment Control Plans and Reports will be prepared during Detailed Design, outlining detailed construction management strategies, phasing, and staging of works.
- **Unwatering** – Sediment-laden unwatering discharge will be pumped to a stilling basin or filtering system well away from the watercourse and allowed to settle and / or filter through the riparian vegetation before re-entering the watercourse downstream of the construction area.
- **Newly Constructed Vegetation** – Rapid establishment of vegetation on any channel banks and adjacent floodplains will minimize potential erosion, where applicable. Vegetation also provides cover, which improves aquatic habitat and water quality. An aggressive planting plan is; therefore, warranted.
- **Site Stabilization** – Immediately following construction, all disturbed areas will be graded to finished design elevation and organic soil will be added with the appropriate seed mix. Disturbed areas within 2 m of the work area, and along valley walls, will be covered with coir cloth, jute mat, or crimped straw. The Site will be re-vegetated as soon as conditions allow. As it is likely that the build-out of the development will be phased to some extent, exposed areas will be stabilized as soon as possible if they will be sitting dormant for an extended period of time, until future development takes place on the lands.
- **Materials and Equipment** – Any stockpiled materials should be stored and stabilized away from watercourses and temporary and ultimate SWMFs. Vehicle and equipment re-fueling and / or maintenance should be conducted away from the watercourse. Any part of a vehicle and / or equipment entering the water should be free of fluid leaks and externally cleaned / degreased to prevent deleterious substances from entering the water.

7.2 Erosion, Sediment, and Topsoil Control Strategy

Erosion and sediment control will be implemented for all construction activities, including tree removal, topsoil stripping, earth moving operations, foundation excavation, and stockpiling of materials. Detailed Erosion and Sediment Control / Construction Management Plans and a Report will be prepared under separate cover in support of necessary Permit Applications for site alteration.

Erosion and Sediment Control (ESC) Plans will be designed in conformance with the City's, TRCA, and Ministry of the Environment, Conservation and Parks and Climate Change (MECP) Guidelines and the Greater Golden Horseshoe Conservation Authorities Erosion and Sediment Control Guideline for Urban Construction. TFPM will have a CISEC-accredited Professional undertake periodic inspections and file reports to

ensure conformity with the approved Construction Management / ESC Plans and best practices.

ESC strategies will include the following:

- Perimeter Heavy Duty Silt Fence and Double Silt Fence / Straw Bale Barriers along sensitive outfall areas and along the entire NHS boundary.
- Immediately following construction, all disturbed areas are to be graded to design pre-grades and organic soil added with the appropriate seed mix. Site to be re-vegetated as soon as conditions allow.
- Rapid establishment of vegetation on any channel banks and adjacent floodplains to minimize potential erosion, where applicable.
- Temporary sediment control fence at construction limits, and / or downstream of any disturbed areas prior to grading.
- Gravel mud mats and vehicle wash-down stations at construction vehicle access points to minimize off-site tracking of sediments.
- Material stockpiles located a reasonable distance from watercourses, stabilized and bordered by temporary sediment control fence.
- Vehicle and equipment re-fueling and / or maintenance conducted a reasonable distance from watercourses.
- Temporary sediment ponds as required, utilizing the permanent stormwater management facilities, where possible.
- Sediment laden unwatering discharge pumped to a stilling basin or filtering system well away from the watercourse and allowed to settle and / or filter through the riparian vegetation before re-entering the watercourse, downstream of the construction area.
- Rock Check dams for erosion / velocity control.
- Sediment traps to be placed in catchbasins (once underground servicing is installed).
- Routine inspection, monitoring, and repair as necessary of all temporary ESC measures during construction.
- Removal of temporary controls once the areas they serve are restored and stable.
- In water works, if necessary, will occur during the allowable fisheries window, or as otherwise directed by the MNRF.
- Turbidity monitoring may be required periodically to ensure that the quality of water being released from unwatering, dewatering, or any other construction operation is compliant.

7.3 Utility Requirements

The Seaton Community will require electrical servicing, telephone and television telecommunications, and natural gas supply. Within the City of Pickering, the service utility companies are Veridian Connections, Bell Canada, Rogers Communications, and

Enbridge Gas Distribution, respectively. These utility companies have been advised of the scope and timing of the proposed developments within the Seaton Community. The MESPA states that the Seaton Community, including the Study Area, can be serviced with either the extension of existing services or the implementation of new infrastructure as required as development advances.

Street illumination for local, collector, and arterial roadways will also be required. Street lights internal to the Whitevale TFPM Subdivision will ultimately be municipally owned and maintained. It will be a requirement for each developer to retain an electrical consultant for the design of street lights and to coordinate the electrical supply to the street lights. The City has released the Seaton Community Street Lighting Guidelines, dated December 2016. This version supersedes the Guidelines dated March 2016. These Guidelines incorporate the requirements for street lights to have a color temperature of 3,000 k on local roads, and revised Region of Durham Specifications for Roadway Lighting. These will be used to inform the detailed lighting designs. Another Consultant will be completing a composite utility coordination plan.

8.0 Transportation

The transportation system for the subject lands, including all roads, the transit system (where applicable), trails, sidewalks, and bike lanes, will be developed during Detailed Design and will generally follow the recommendations of the MESPA, Regional Roads EA and City Roads EA, and City of Pickering Placemaking Guidelines.

8.1 ROW Cross Sections

The subject development includes 17 m local road ROWs and a 10 m laneway. The City's approved cross-sections are proposed for the development of the Site. Peter Matthews Drive is a 36 m ROW section, the road and intersection design will be coordinated as part of the Detailed Design process.

8.2 Noise Attenuation

A Noise Assessment Report has not yet been prepared for the subject site and will be completed in support of Detailed Design. It is not expected to have any excess noise areas that would affect the layout of the proposed draft plan. Measures such as noise fence and a/c units may be utilized to mitigate noise in areas noted as required by the noise consultant during Detailed Design.

9.0 Stormwater Management Strategy

9.1 Design Parameters / Terms of Reference

An extensive analysis of the watersheds within the Seaton Community was completed through the MESP and the MESPA in addition to the 2012 DCHU. The following criteria for Urfe Creek within the subject Whitevale TFFM Lands have been developed based on the modelling completed to date.

Quality Control

Enhanced (Level 1) protection (minimum 80% total suspended solids removal), is required based on MECP SWM Manual (2003).

Erosion Control

Extended detention of the first 25 mm rainfall event is required for a minimum of 120 hours. This is achieved with an extended detention unit storage of 250 m³/imp. ha (based on post-development area) and an outflow of 0.0006 m³/s/ha (based on pre-development area) as per the MESPA.

Quantity Control

Control of post-development 2-year to 100-year peak flows is required. Release rate requirements were established in the 2012 DCHU for Catchment 38, which encompass the Whitevale North TFFM Lands under post-development drainage conditions.

SWM Pond Grading

The stormwater facilities are required to be designed in accordance with MECP, TRCA, MNRF, and the City's Design criteria, as summarized below:

- Minimum Length to Width Ratio of 4:1.
- Side Slopes:
 - 3:1 from the bottom of the permanent pool to 500 mm below the normal water level (NWL).
 - 6:1 within 3.0 m on either side of NWL.
 - 4:1 where the slope backs onto the rear yard lot line or an adjacent valley system.
 - 4:1 where the pond is adjacent to a municipal boundary.
 - 5:1 where the slope backs onto an adjacent road system.

- Water Levels:
 - Permanent Pool: 3.0 m deep.
 - Extended Detention Storage: 1.5 m max depth.
 - Quantity Control Storage: 2.0 m max depth.
- Berming:
 - Max berm height: 3 m
 - Where berm >2 m it must be assessed and possibly designed by a Geotechnical Engineer as a Dam.
- Maintenance access road / walking trail.
- Emergency spillway.

9.1.1 Storm Sewer Design and Modelling

The Minor Storm System will consist of a series of storm sewers sized to convey the 5-year Return Period Storm to the end-of-pipe SWMF. The storm sewer network will be designed to the City's Design Standards and will generally be of sufficient depth to allow gravity service connections to individual lots.

In addition to the storm sewer network, in order to achieve water augmentation to existing features, and achieve the 5 mm recharge requirement, a local Roof Drainage Collector Pipe System (RDC) may be situated within ROWs to the various discharge locations.

A Preliminary Storm Sewer Design is depicted on Figure 4-5 and Figure 4-6.

The storm sewer design for the Whitevale TFFM Development will be based on the City of Pickering Stormwater Management Design Guidelines. An HGL Analysis based on the following criteria is required:

1. For watersheds greater than 40 ha in size, the 100-year 1-hour AES Storm will determine the Design HGL for the storm sewer (minor system).
2. For watersheds less than 40 ha in size, a Rational Method spreadsheet will be used for HGL analysis.
3. The starting elevation for the HGL modelling shall be the height of the 100-year water surface elevation within the receiving system (i.e., SWMF).
4. The modelling shall be completed assuming the full 100-year peak flow is conveyed by the pipes.
5. Hydraulic losses must be accounted for in the minor system.
6. For detailed criteria, refer to Section 6.3.1 in the City of Pickering Stormwater Management Design Guidelines.


A full HGL analysis will be performed at the Detailed Design stage.

9.2 Impervious Ground Cover

To determine the quality and erosion control storage requirements, a weighted percent impervious value was calculated based on the land use presented in the Draft Plan. The percent impervious for various land use types was calculated based on draft City of Pickering By-laws for Seaton regarding lot setback requirements for residential land uses and the City's SWM Guidelines (2019) for all other land use types. For residential lands, details of the impervious area coverage assumed for the various typical lot sizes and unit types are presented on Figure 9-1 and Figure 9-2. The imperviousness of each type of land use is summarized below in Table 9.1.

Table 9.1: Percent Impervious Cover Based on Land Use

Land Use	Percentage
Low Density (Single Detached)	68%
Medium Density (Townhouses)	73%
Medium Density (Rear Lane Towns)	82%
Medium Density (Back-to-Backs Towns)	88%
Site Plan Block	75%
Open Space (Including Park Blocks)	21%
Trailhead Block	59%
SWMF Block	50%
Roads Only (Combination of ROWs)	85%
School Block	80%




LOT AREA	= 86.4	LOT AREA	= 118.0	LOT AREA	= 175	LOT AREA	= 252	LOT AREA	= 302	LOT AREA	= 360	LOT AREA	= 427
ROOF AREA	=57	ROOF AREA	=90	ROOF AREA	= 91	ROOF AREA	= 114	ROOF AREA	= 153	ROOF AREA	= 207	ROOF AREA	= 248
PERCENTAGE ROOF	=66%	PERCENTAGE ROOF	=76%	PERCENTAGE ROOF	= 52%	PERCENTAGE ROOF	= 45%	PERCENTAGE ROOF	= 51%	PERCENTAGE ROOF	= 58%	PERCENTAGE ROOF	= 58%

NOTE:
ROOF AREA BASED ON 110% OF
ENVELOPE FOR SINGLES AND ALL
ROOF AREA INCLUDED


		Figure Title		
		WHITEVALE TFPM DEVELOPMENT ROOF AREA CALCULATION		
Client	Drawn	Checked	Date	Figure No.
	MH	SW	18/12/13	
	Scale	Project No.		
SEATON TFPM INC.		NTS		9.1

**TYPICAL
6.4m B2B**




LOT AREA = 86.4m²
 TOTAL AREA (INCL. ROW) = 140.9m²
 IMPERVIOUS AREA @ 100% = 123.4m²
 PERVIOUS AREA @ 0% = 17.5m²
NET IMPERVIOUS = 88%
 ROOF AREA = 57m²
ROOF (% OF LOT ONLY) = 66%

**TYPICAL
6.05m REAR
LANE TOWN**




LOT AREA = 118.0m²
 TOTAL AREA (INCL. ROW) = 195.1m²
 IMPERVIOUS AREA @ 100% = 160.3m²
 PERVIOUS AREA @ 0% = 34.8m²
NET IMPERVIOUS = 82%
 ROOF AREA = 100m²
ROOF (% OF LOT ONLY) = 85%

**23'
TOWN**




LOT AREA = 175m²
 TOTAL AREA (INCL. ROW) = 234.9m²
 IMPERVIOUS AREA @ 100% = 171.8m²
 PERVIOUS AREA @ 0% = 63.1m²
NET IMPERVIOUS = 73%
 ROOF AREA = 102m²
ROOF (% OF LOT ONLY) = 58%

30'




LOT AREA = 252m²
 TOTAL AREA (INCL. ROW) = 329.4m²
 IMPERVIOUS AREA @ 100% = 207.5m²
 PERVIOUS AREA @ 0% = 121.9m²
NET IMPERVIOUS = 63%
 ROOF AREA = 126m²
ROOF (% OF LOT ONLY) = 50%

36'




LOT AREA = 302m²
 TOTAL AREA (INCL. ROW) = 396m²
 IMPERVIOUS AREA @ 100% = 264.1m²
 PERVIOUS AREA @ 0% = 131.9m²
NET IMPERVIOUS = 67%
 ROOF AREA = 154m²
ROOF (% OF LOT ONLY) = 51%

43'



LOT AREA = 360m²
 TOTAL AREA (INCL. ROW) = 471.9m²
 IMPERVIOUS AREA @ 100% = 317.6m²
 PERVIOUS AREA @ 0% = 154.3m²
NET IMPERVIOUS = 67%
 ROOF AREA = 192m²
ROOF (% OF LOT ONLY) = 53%

50'



LOT AREA = 427m²
 TOTAL AREA (INCL. ROW) = 556.6m²
 IMPERVIOUS AREA @ 100% = 376.2m²
 PERVIOUS AREA @ 0% = 180.4m²
NET IMPERVIOUS = 68%
 ROOF AREA = 238m²
ROOF (% OF LOT ONLY) = 56%



Figure Title
WHITEVALE TFPM DEVELOPMENT
 ROOF AND IMPERVIOUS AREA CALCULATION

Client
SEATON TFPM INC.

Drawn MH	Checked SW	Date 23/02/13	Figure No. 9.2
Scale NTS	Project No. 300043770		

9.3 Uncontrolled Rear Lots to NHS

The rear roof and rear yard areas from all lots abutting the NHS, as well as some of the trailhead block, will not be collected and conveyed to the SWMF. These uncontrolled areas total approximately 1.37 ha and are depicted on Figure 9-3. In an effort to mimic natural hydrology, these areas will sheet flow towards the NHS. A vegetated filter strip at the edge of the NHS will attenuate runoff prior to it reaching the NHS; therefore, no overcontrol in the SWMF is required.

9.4 Stormwater Management Facility Details (SWMF 43)


There is one SWMF proposed within the Whitevale TFPM Development Lands – SWMF 43. The Preliminary Design of the SWMF, including catchment area, pond footprint, grading, and cross-sections, are provided in Figure 9-3 through Figure 9-5.

A Visual HYMO Model was prepared to establish the functional volumes required to meet the release rate targets established in the DCHU, as discussed in Section 9.1. SWMF 43 has been sized based on control of the major and minor drainage areas to the pond. The total drainage area to SWMF 43 is 16.19 ha with an overall impervious of 71% (refer to imperviousness calculations that can be found in Appendix H). The curve number of 75 used in the modelling of SWMF 43 is as per Table A.1 in the DCHU for Catchment 38.

Table 9.2: Summary of SWMF Target Release Rates

Storm Event	SWMF 43 – 16.19 ha Drainage Area	
	Unitary Discharge (L/s/ha)	Target Discharge (L/s)
25 mm (Extended Detention)	0.6	10.3
2-year	2.36	38.2
5-year	3.79	61.4
10-year	4.80	77.7
25-year	6.22	100.7
50-year	7.33	118.7
100-year	8.50	137.6

A brief discussion of the pond is presented in the Sections below.




LEGEND:

- - - TREE LINE SETBACK (10m)
- - - REGIONAL FLOODLINES
- - - FISHERIES SETBACK (30m)
- EX. WATERCOURSE
- - - MEANDER BELT WIDTH
- - - STABLE TOP OF SLOPE
- - - EROSION HAZARD LIMIT
- ~ ~ ~ EX. TREELINE
- WETLAND BOUNDARY

- School Block
- Site Plan Block
- Townhouses (Back to Back)
- Townhouses (Rear Lane Towns)
- Medium Density Townhouses
- Low Density
- Low Density to Feature
- SWMF
- Uncontrolled Rear Lots and Rear Roofs
- Trailhead
- Open Space
- Park


PROPOSED STORMWATER MANAGEMENT FACILITY POST DEVELOPMENT DRAINAGE AREA

16.08 DRAINAGE AREA (ha)
SWMF#43 DRAINAGE ID



BURNSIDE		Figure Title WHITEVALE TFPM DEVELOPMENT SWMF#43 DRAINAGE AREA	
Client SEATON TFPM INC.	Drawn AS	Checked SW/HS	Date 23/02/13 Project No. 300043770
			Figure No. 9.3

File: \\barkley\shared work areas\043770 - tfpm whitevale north\sr02_Production\Drawg\043770_FSR_SWMF-DRAINAGE-AREA.dwg Date Plotted: February 14, 2023 - 4:29 PM



SWM FACILITY OPERATING CHARACTERISTICS				
	DISCHARGE (m³/s)	REQUIRED STORAGE (m³)	PROVIDED STORAGE (m³)	ELEVATION (m)
FOREBAY	-----	746	760	181.30
PERMANENT POOL	-----	2995	5553	181.30
EXTENDED DETENTION	0.0103*	2863*	2982	181.90
100 YEAR	0.1376**	9490	9490	183.26

*FROM 2013 MESPA
**FROM 2012 DCHU

LEGEND

- TREE LINE SETBACK (10m)
- REGIONAL FLOODLINES
- FISHERIES SETBACK (30m)
- EX. WATERCOURSE
- MEANDER BELT WIDTH
- STABLE TOP OF SLOPE
- EROSION HAZARD LIMIT
- EX. TREELINE
- WETLAND BOUNDARY
- EXISTING CONTOUR
- STORM SEWER AND MAINTENANCE HOLE
- OVERLAND FLOW DIRECTION








		Figure Title	
		WHITEVALE TFPM DEVELOPMENT SWMF#43 PLAN	
Client	Drawn	Checked	Date
	SEATON TFPM INC.	MH/AS	HS/SW
	Scale	Project No.	
	1:1000	300043770	
			Figure No.
			9.4

Section A-A



Section B-B



		Figure Title		
		WHITEVALE TFPM DEVELOPMENT SWMF#43 SECTIONS		
Client	Drawn	Checked	Date	Figure No.
	PH/MH/SD	HS/SW	23/02/13	
SEATON TFPM INC.	Scale	Project No.		9.5
	H 1:1000 V 1:200	300043770		

9.4.1 Stormwater Management Facility 43 (SWMF)

9.4.1.1 Drainage Area

SWMF 43 is located at the east limit of the Whitevale TFFM Lands in Urfe Subcatchment 38 (refer to DCHU), and outlets to Urfe Creek Reach UB6. The total drainage to SWMF 43 is 16.19 ha, and consists of low, medium, and high-density residential, open space, roads, a park, a school, and a SWM block as previously indicated (see Figure 9-3). Appendix H includes a detailed impervious calculation. The Preliminary Design of SWMF 43 is shown on Figure 9-4, cross-sections on Figure 9-5, and pond calculations are included in Appendix H.

A portion of the drainage area from the draft plan proposed as part of the Whitevale TFFM Lands was considered in the design of SWMF 44 which was completed as part of the Whitevale Central SWM report. In the report, 2.47 ha of drainage at 74% impervious was considered in the SWMF 44 design. Based on the grading design proposed for the Whitevale TFFM Lands, 2.45 ha at 76% impervious will drain to SWMF 44. The overall impervious area (Area x %imp) draining to SWMF 44 has been increased by 1.60% which will result in a slight increase in flows to SWMF 44. The minor increase in flows is expected to be negligible.

9.4.1.2 Water Quality

Enhanced (Level 1) protection (minimum 80% total suspended solids removal), based on MECP SWM Manual (2003) is required to meet water quality objectives. SWMF 43 has been designed as a wet pond and provides a permanent pool volume of 5,553 m³ which is sufficient to meet the required 3015 m³ permanent pool volumes to satisfy Enhanced Fisheries Protection as per MECP Guidelines. The main cell of the pond has been designed with a 2.3 m deep permanent pool as well as a 3.0 m deep plunge pool (as it discharges to Redside dace habitat). Refer to Appendix H for the permanent pool sizing calculations.

9.4.1.3 Erosion Control / Extended Detention

Extended detention of the first 25 mm Rainfall Event for a minimum of 120 hours is required to meet erosion control objectives. This is accomplished using an extended detention unit storage of 250 m³/imp. ha (based on post-development area of 16.19 ha) and outflow rate of 0.0006 m³/s/ha (based on pre-development area of 17.09 ha). This corresponds to a volume requirement of 2,863 m³ and an extended detention release rate of 0.010 m³/s to Urfe Creek. The target release rate to the creek will be achieved using an outlet control structure, to be designed during Detailed Design, in accordance with the City's Guidelines.

9.4.1.4 Quantity Control

Control of post-development 2-year to 100-year 12-hour AES peak flows to targets established in the DCHU is required for SWMF 43. Table 9.3 below outlines the preliminary stage storage requirements for SWMF 43. The target release rate to the creek will be achieved using an outlet control structure, to be designed during Detailed Design in accordance with the City's Guidelines. Detailed calculations and actual stage-storage relationships have been provided in Appendix H.

Table 9.3: Summary of SWMF 43 Storage / Release Rates

Storm Event	Peak Release Rate (L/s)	Peak Release Rate (L/s)		Active Storage (m ³) Required	Pond Elevations (m)
	SWMF 43 Inflow (16.19 ha)	SWMF 43 Outflow (16.19 ha)	Urfe Creek Target		
25 mm	896.0	9.7	10.3	2863	181.90
2-year	671.6	36.9	38.2	4410	182.60
5-year	894.4	59.1	61.4	5780	182.79
10-year	1064.6	74.4	77.7	6640	182.90
25-year	1260.5	87.5	100.7	7830	183.06
50-year	1410.8	102.2	118.7	8700	183.16
100-year	1557.1	127.0	137.6	9490	183.26

9.4.1.5 SWMF Grading

The Preliminary Grading Design of SWMF 43 has been completed with 3:1 slopes adjacent to the access road where tying into existing ground, 5:1 slopes have been provided where the SWMF is adjacent to the Municipal roadway, and 4:1 slopes have been provided where the SWMF is adjacent to lots. Within the pond itself, the slopes have been graded in accordance with the criteria listed in Section 9.1.

9.4.1.6 SWMF 43 Outfall

The SWMF 43 outfall is proposed at the south end of the pond block, discharging to Reach UB6 which differs from the proposed location shown in the NFSSR. The outflow location was revised to allow overland flows (major system) entering the pond to discharge directly into the main cell, thereby reducing the resuspension of solids in the forebay during larger storm events. This new outfall location will require a field review and staking to assess existing physical constraints. Details related to the outfall will be provided at Detailed Design.

9.4.1.7 SWMF 43 Summary

Table 9.4 below outlines design details for SWMF 43, and further details including actual stage-storage can be found in Appendix H and on Figure 9-4.

Table 9.4: Summary Table for SWMF 43 Design

Features	Technical Data
Drainage	Drainage Area Quantity & Quality = 16.19 ha % IMP = 70.7%
Permanent Pool	Volume Required = 2,995 m ³ Volume Provided = 5,553 m ³ Max Depth = 3.0 m
Extended Detention	Volume Required: 2,863 m ³ Volume Provided: 2,982 m ³ Elevation: 181.90 m Release Rate: 9 L/s
Active Storage	Volume Required: 9,490 m ³ Elevation: 183.26 m Release Rate: 127.0 L/s
Top of Pond	Elevation: 184.00 m Max Berm Height = 3.0 m
Emergency Overflow Weir	5.56 m wide trapezoidal weir; Max Depth of 0.3 m at Elevation 183.40 m Max. Outflow: 1.56 m ³ /s

10.0 Low Impact Development (LID) Measures

As summarized in Section 2.0, the MESPAs recommended Low Impact Development (LID) measures to address:

1. Water balance augmentation to natural features.
2. Water quality control.
3. Maintaining overall groundwater recharge and providing surface water runoff volume reductions in the developed areas.

LID measures shall be designed to accept 5 mm of rainfall over specified impervious roof areas. Maintaining the water balance of Wetland U8 and Wetland G9 is the priority. The 5 mm volume from the remaining roof areas is to be made available for maintaining groundwater recharge and subsequently providing surface volume reductions in developed areas and at end-of-pipe facilities (despite no credit towards this). These three categories of LIDs are described in the following Sections.

Determining the specific available volume of runoff from roofs is required to support several of the LID calculations in this report, and this requires an informed estimate of

the roof area for various lot types. Figure 9-1 shows the roof area coverage for the various residential lot types. This analysis is based on zoning requirements established for the Seaton Community and assumes the full building envelope will be utilized. The roof areas estimated for each lot type have subsequently been used to size the LID facilities.

10.1 LID Measures for Feature-Based Water Balance

Section 3.5 outlined the natural features requiring water augmentation and summarized the existing conditions of the feature drainage. The MESPA provided direction on the augmentation requirements to maintain flow to the features, and generally recommended that LID measures involving the redirection of clean roof or rear yard stormwater runoff be utilized. The MESPA recommended that this flow be directed into a dry swale or bioswales located in buffers prior to the release of flows into the features.

The MESPA identified preliminary roof areas needed for water augmentation for each feature. This has been further refined in accordance with the NFSSR Terms of Reference. The proposed water augmentation plan calls for a combination of roof and rear yard drainage to be directed towards Wetland U8 and Wetland G9. Rear yards and roofs abutting the NHS adjacent to the features will either sheet drain directly to the features or sheet drain to a bioswale which outlets the feature. Additional drainage from roofs internal to the Site will be piped via a RDC sewer to Features U8 and G9.

A PCSWMM Model was created to analyze the pre- and post-development runoff volumes and peak flows for each feature for the period of March to October as well as annually. This included a calculation of the percent change in runoff volume between the average existing and future conditions with augmentation for six years (1998 to 2003) of continuous rainfall data. The percent change was then compared to the natural variability of runoff to the feature under existing conditions. If the future change in runoff volume was not within the natural variability range of the feature, then the roof area was either increased or decreased and the model re-run. The models were iterated until the percent change in runoff volume between post- and pre development conditions was predicted to be within the natural variability of the feature under existing conditions. Refer to Appendix D for a summary of the modeling procedure.

Table 10.1 and Table 10.3 show the existing natural variability in runoff volume for Wetland Feature U8 and Wetland G9, respectively, and Table 10.2 and Table 10.4 indicate the projected future percent change for the same features under continuous simulation modelling. See Appendix D for pre- and post-development results, and the model summary for each of the augmented features within the Whitevale TFPM Development.

Table 10.1: U8: Existing Conditions Percent Variability from Average Runoff Volumes

1998 to 2003	Minimum	Maximum
% Variability March to October Average	-31%	34%
% Variability Yearly Average	-28%	13%

Table 10.2: U8: Proposed Conditions Percent Change in Runoff Volume from Existing Average Runoff

Percent Change	1998	1999	2000	2001	2002	2003	Average
March to October	27%	28%	8%	-8%	-33%	-7%	3%
Yearly	20%	7%	6%	-10%	-21%	8%	2%

Table 10.3: G9: Existing Conditions Percent Variability from Average Runoff Volumes

1998 to 2003	Minimum	Maximum
% Variability March to October Average	-41%	50%
% Variability Yearly Average	-38%	22%

Table 10.4: G9: Proposed Conditions Percent Change in Runoff Volume from Existing Average Runoff

Percent Change	1998	1999	2000	2001	2002	2003	Average
March to October	24%	34%	12%	-12%	-34%	-10%	2%
Yearly	19%	12%	9%	-13%	-22%	5%	2%

As demonstrated, under proposed conditions, both features generally demonstrated variability within the natural range that was observed under existing conditions. The proposed augmentation plan for Wetland U8 resulted in an exceedance of 7% in 1998, and a deficit of 2% from March to October in 2002 when compared to the natural variability. The area proposed to augment the wetland was optimized to reduce the runoff volume outside the natural variability range as much as possible in these two cases. These results demonstrate satisfactory augmentation to maintain the pre-development water balance and functionality of Wetland U8 and Wetland G9.

Table 10.5 summarizes the updated recommended roof and rear yard areas for augmentation for each feature based on the analysis described above. The roof area as specified in the MESPA is also shown for comparison purposes.

Table 10.5: Drainage Area for Feature Augmentation

Feature	Roof Area to Feature (ha)	Yard Area to Feature (ha)
Wetland U8	0.77	0.39
Wetland G9	0.51	0.20

Time-varied runoff was also plotted as hydrographs and reviewed for the 6-year period for the proposed augmentation. Each year of data was broken into three hydrographs showing spring (March to May), summer (June to August), and fall (September to November). The hydrographs are presented in Appendix D.

It should be noted that the modelling presented does not include the proposed LID systems at the outfall to Wetland G9. The purpose of the modelling was to confirm that the appropriate roof and rear yard area was being utilized to augment the feature. The LID measures proposed at the outfall will dampen and disperse the peak flow in addition to providing detention, evapotranspiration, and some infiltration. Therefore, these functions are not represented in the model or hydrographs. The hydrographs are generally representative of proposed conditions and show the general trends when looking at peak flows and duration; however, do not provide the exact peak flow or duration of flows to the feature under future conditions.

When establishing the appropriate area for augmentation, conclusions have been drawn from the analysis of runoff volumes. The conclusion is that the roof and rear yard areas, provided in the table above, will provide augmentation to the features such that any increases or decreases in runoff volume will be within the range of increases and decreases in runoff volume that the features experience under existing conditions. During some rainfall events, peak flows may be higher and the duration longer under proposed conditions; however, LID measures will work towards dampening and dispersing the flow to the feature. Further details for the LID measures are to be determined during Detailed Design.

Based on the prescribed requirements for feature-based water balance to Feature G9, LID measures to convey and distribute flows from the areas provided in Table 10.5 have been located within and adjacent to the subject lands. The locations of the LID measures are schematically shown on Figure 10-1.

At Detailed Design, each feature LID measure will be designed to convey the flows to the feature while providing detention, retention, infiltration, and evapotranspiration in accordance with the TRCA / CVC LID SWM Planning and Design Guide (2010, LID Guide). The key design criteria are as follows:

- Bottom width of 0.75 m to 3.0 m.
- Slope between 0.5% and 4%; check dams for slopes greater than 3%.

- Maximum flow depth of 100 mm and maximum flow velocity of 0.5 m/s during a 4-hour, 25 mm Chicago Storm Event.
- Sized to convey the 10-year Design Storm Event.
- Maximum side slopes of 2.5:1.

10.1.1 Outlet to U8

The proposed LIDs for the area providing stormwater recharge to Wetland Feature U8 are located west of the wetland. The LID will receive RDC sewer discharge via a proposed headwall. While the intent of the proposed augmentation system is to match runoff volumes to Feature U8, directing rooftop runoff has the potential to increase peak flows and velocities compared to existing conditions.

To dampen peak flows and reduce velocities, discharge from the proposed RDC sewer will outlet to a sub-surface level spreader (stone core wetland) and then overland to the feature. A scoped EIS will be prepared in support of the Detailed Design of this outlet. Refer to Figure 10-1 for the preliminary layout of the outlet for augmentation of Feature U8.

SWALE AND HEADWALL
OUTLETING TO ENGINEERED
STONE CORE WETLAND AT
FEATURE U8. WETLAND DESIGN
TO BE COMPLETED AT
DETAILED DESIGN STAGE.

U8


G9

HEADWALL OUTLETING TO
ENGINEERED STONE CORE
WETLAND AT FEATURE G9.
WETLAND DESIGN TO BE
COMPLETED AT DETAILED
DESIGN STAGE.

PROVIDE MAINTENANCE
ACCESS FROM ROW
GRADE PER MUNICIPAL
STANDARDS

RDC HEADWALL 5 TO
PROVIDE LINEAR
SUB-SURFACE OUTLET TO
ENCOURAGE SHEET FLOW
AND MINIMIZE EROSION

RECEIVING FEATURE	CONTRIBUTING ROOF AREA	CONTRIBUTING YARD AREA
U-8	0.77 ha	0.39 ha
G-9	0.51 ha	0.20 ha



CATCHMENT ID	TOTAL ROOF AREA (Ha)	TOTAL YARD AREA (Ha)	NUMBER OF UNITS WITHIN AREA
R1	0.15	0.20	11

- PROPOSED LOT AREA WITH ROOF DRAINAGE CONTRIBUTING TO FEATURE U8 VIA RDC SYSTEM
- PROPOSED LOT AREA WITH ROOF AND REAR YARD SHEET DRAINING TO FEATURE U8
- PROPOSED LOT AREA WITH ROOF AND REAR YARD SHEET DRAINING TO FEATURE G9
- PROPOSED LOT AREA WITH ROOF DRAINAGE CONTRIBUTING TO FEATURE G9 VIA RDC SYSTEM
- EXISTING LIMIT OF WETLAND FEATURE
- ROOF DRAIN COLLECTION (RDC) SYSTEM

BURNSIDE

Client
SEATON TFPM INC.

Figure Title
WHITEVALE TFPM DEVELOPMENT
WATER AUGMENTATION TO FEATURES

Drawn AS	Checked HS/SW	Date 22/11/29	Figure No. 10.1
Scale 1:2000		Project No. 300043770	

10.1.2 Outlet to G9

The proposed LIDs for the area providing stormwater recharge to Wetland Feature G9 are located east of the wetland. The LID will receive RDC sewer discharge via a proposed headwall. While the intent of the proposed augmentation system is to match runoff volumes to Feature G9, directing rooftop runoff has the potential to increase peak flows and velocities compared to existing conditions.

To dampen peak flows and reduce velocities, discharge from the proposed RDC sewer will outlet to a sub-surface level spreader (stone core wetland) and then overland to the feature. A scoped EIS will be prepared in support of the Detailed Design of this outlet. Refer to Figure 10-1 for the preliminary layout of the outlet for augmentation of Feature G9.

The MESPA describes that Feature G9 should be fed to match existing conditions by a combination of the TFPM Whitevale site as well as the Mattamy Whitevale West site (on the west side of Peter Matthews Drive). During preliminary engineering of the Site and with correspondence with the City and TRCA, it was determined that the preference for Feature G9 was to eliminate the outlet on the west side from Whitevale West Development. As a result, the entire required augmentation (refer to Figure 10-1) balance will be satisfied by the TFPM Whitevale site.

10.2 LID Measures for Water Quality

There are no areas within the subject lands that require the use of LIDs for quality control as it is anticipated that all areas of the Site can adequately drain to a SWMF. The City has been clear in that LIDs, regardless of their intent for quality, or volume control, will not be credited toward quantity control volume requirements for the end-of-pipe SWMFs.

10.2.1 LID Measures for Recharge and Runoff Volume Reductions

The MESPA identified that LID measures are required to maintain overall groundwater recharge, provide surface water runoff volume reductions, and mitigate erosion in the developed areas. These LID measures are required to treat 5 mm of roof runoff for all roofs (or equivalent impervious area in the event some roof runoff cannot be captured) not needed for feature augmentation. Table 10.6 summarizes the volume control requirements.

Table 10.6: Volume Retention Requirements

Roof Drainage Ultimate Outlet	Number of Units	Total Roof Area (ha)	Infiltration volume Requirement (m ³)
SWMF 43	266	3.03	152

The following Sections outline the strategy for the subject lands for both Municipal ROW and lot level drainage.

10.2.2 LID Measures for ROWs

The MESP stipulates that LID measures shall be considered for implementation on local roads that extend through, or directly abut the NHS. There is only one location on the Site where the road directly abuts the NHS in the northwest corner. However, this location is not feasible to direct drainage to, as it is located at the highest point of the Site; therefore, an LID is not proposed at this location. The infiltration gallery proposed at the southeast corner of the Site (lowest area) has sufficient capacity to handle all infiltration requirements for the entire site.

10.2.3 Recharge / Runoff LID Strategies

For the Whitevale North TFPM residential lands, the following options and strategies have been considered for groundwater recharge and surface water volume reductions, and are presented in order of preference and suitability:

1. Centralized Infiltration Facilities.
2. Restoration of the Natural Heritage System Buffer (Enhancement / Planting).
3. Lot Level Infiltration Facilities / Rain Barrels for lots with frontages over 12 m.

Based on our preliminary discussions with the City and history working in the Seaton Community, we understand the acceptable practice for infiltration is to design LID facilities that provide the infiltration volume required, to meet the 5 mm target. Based on the Site topography and constrains, we propose that a centralized facility is the most suitable for this development.

10.2.3.1 Centralized LID Facility

A Centralized Infiltration Gallery (IG-43) located within the tableland NHS is proposed as the main recharge option. Generally, it is understood that the City prefers centralized facilities over lot-level controls. The preferred option for centralized IGs is that fed by SWMF discharge. Such facilities do not require an RDC third pipe system. The SWMF outlet will be designed to convey the equivalent 5 mm roof runoff volume for all TFPM

Whitevale TFPM Development Functional Servicing and Stormwater Management Report
March 2023

Whitevale North. One facility is proposed, at the outfall of SWMF 43 to Urfe Creek, as shown on Figure 10-2.

The seasonally high groundwater in the location of the infiltration gallery has been approximated on the design figures, based on groundwater readings on the Site. We plan to have a test pit program completed in 2023 to support the Detailed Design of the gallery, by determining groundwater conditions and infiltration rates.

The bottom of IGs should be a minimum of 1.0 m above the seasonally high groundwater level (MECP, 2003), the City requested that the bottom and sides be founded in native soil where possible. A preliminary concept is shown on Figure 10-3. Note that the top IG-43 will be constructed at existing grade (fill on top to proposed grade = ~3.3 m above) and will extend down 1.0 m below grade. The bottom of the infiltration gallery will be at an elevation of roughly 1.0 m below existing ground. Detailed servicing specifications cleanout, and overflow pipe will be incorporated at Detailed Design stage.

It is understood that additional groundwater monitoring and infiltration testing will be required prior to constructing IG-43. This work will be carried out during Detailed Design in support of IG-43. The purpose of the infiltration calculations found in Appendix I is to show that the proposed location of IG-43 is adequate, the exact sizing will be completed at Detailed Design. Details of the proposed facility are provided in Table 10.7.

Table 10.7: Details of Proposed SWMF Effluent Fed-Centralized Infiltration Galleries

Infiltration Gallery	Location	Required Area (m ²)	Proposed Area (m ²)	Proposed Depth (m)	Proposed Volume (m ³)	Required volume (m ³)
IG-43	Southeast of SWMF 43	379	8 x 66.5	1.0	213	152

LEGEND


- IG1 — IG DRAINING ID
- 100 | 1.50 — TOTAL ROOF AREA (Ha)
- NUMBER OF UNITS WITHIN AREA
- - - - - PROPOSED LID DRAINAGE AREA LIMIT
- ROOF AREA TO HAVE 5mm STORM EVENT INFILTRATED IN PROVIDED CENTRALIZED LID FACILITY (IG 43)
- ENTIRE ROOF AREA TO NHS FOR FEATURE WATER BALANCE AUGMENTATION (NO FILTRATION REQUIRED)
- REAR ROOF AREA TO NHS (NO INFILTRATION REQUIREMENT)



8.0m BY 66.5m LONG INFILTRATION GALLERY (IG43) WITH PERFORATED PIPE (REFER TO FIG 10.3 FOR DETAILS) WITH 4m ACCESS ROAD IG TO BE FED FROM POND 43


** IG 43 HAS BEEN OVERSIZED TO INFILTRATE THE EQUAVILANT ROOFTOP AREA DRAINING TO POND 44 WITHIN THIS DEVELOPMENT

		Figure Title		Figure No.
		<p>WHITEVALE TFPM DEVELOPMENT</p> <p>CENTRALIZED LID FACILITY IG 43</p>		
Client	Drawn	Checked	Date	<p>10.2</p>
<p>SEATON TFPM INC.</p>	MH	SW	23/02/13	
	Scale		Project No.	
	1:2000		300043770	





SECTION B-B


SCALE - 1:250



SECTION A-A

SCALE - 1:250



		Figure Title	
		WHITEVALE TFPM DEVELOPMENT INFILTRATION GALLERY DETAILS	
Client	Drawn	Checked	Date
	SEATON TFPM INC.		PH/MH/SD/AS HS/SW
	Scale	Project No.	
	AS NOTED	300043770	
			Figure No.
			10.3

11.0 Conclusions and Recommendations

As demonstrated herein, the Whitevale TFPM Subdivision lands can be developed in conformance with the agency standards and under the detailed framework established by the adopted Seaton MESPA.

A considerable amount of pre-consultation and analysis has already been completed to ensure that the Draft Plan of Subdivision adheres to all standards, and design preferences. We trust that this report is sufficient to support Draft Plan approval to allow the development to proceed with Detailed Design.



BURNSIDE

[THE DIFFERENCE IS OUR PEOPLE]

Appendix A

Archaeological Study



BURNSIDE

[THE DIFFERENCE IS OUR PEOPLE]

Appendix B

Geotechnical Reports



BURNSIDE

[THE DIFFERENCE IS OUR PEOPLE]

Appendix C

Hydrogeological Assessment



BURNSIDE

[THE DIFFERENCE IS OUR PEOPLE]

Appendix D

Feature Based Water Balance



BURNSIDE

[THE DIFFERENCE IS OUR PEOPLE]

Appendix E

Environmental Input



BURNSIDE

[THE DIFFERENCE IS OUR PEOPLE]

Appendix F

Diversion Swale



BURNSIDE

[THE DIFFERENCE IS OUR PEOPLE]

Appendix G

Overland Conveyance



BURNSIDE

[THE DIFFERENCE IS OUR PEOPLE]

Appendix H

Stormwater Management Calculations



BURNSIDE

[THE DIFFERENCE IS OUR PEOPLE]

Appendix I

Recharge Volume and LID Sizing Calculations

