






TOPOGRAPHIC INFORMATION SHOWN AS PER J.D BARNES SERVICING INFRASTRUCTURE PLACEMENT TO BE SURVEY 22-25-073-00 DATED 2/2/2023. ELEVATIONS HEREON FINALIZED AT DETAILED DESIGN STAGE. LOCATIONS ARE GEODETIC AND ARE REFERRED TO CITY OF PICKERING SHOWN ARE FOR PROOF OF CONCEPT ONLY. BENCHMARK No. 1-059, HAVING A PUBLISHED ELEVATION OF 84.111m (CGVD-1928: 1978) - FUTURE WALNUT LANE 300Ø WM **KEY PLAN** N.T.S LEGEND PROPERTY LINE PROPOSED UNDERGROUND LIMITS PROPOSED WATERMAIN PROPOSED STORM PROPOSED SANITARY PROPOSED TEMPORARY WATERMAIN TOP 86.40 SW INV. 80.85 SE INV. 80.55 PROPOSED WATERMAIN INSTALLED BLDG. A IN PREVIOUS PHASES – FUT. STM MH 5A (B.O.) ROVIDED VOLUME = 520 m³ - FUT. SAN MH-SA1 (B.O.) PROPOSED STORM INSTALLED ___ 100-YEAR RELEASE RATE = 16.93 L/s TOP 86.53 IN PREVIOUS PHASES NW INV. 80.46 LEAD 300Ø STM @ 0.5% NE INV. 80.40 PROPOSED SANITARY INSTALLED - FUTURE WALNUT LANE IN PREVIOUS PHASES STORM SERVICE (BY OTHERS) FUT. SAN MH-SA10 (B.O.) — FUTURE WALNUT LANE FUT. SAN MH-SA11 (B.O.) EXISTING STORM SEWER TO REMAIN SANITARY SERVICE (BY OTHERS) BUILDING 'A' DOMESTIC & FIRE CONNECTIONS TO 3000 WM — FUT. STM MH 5B (B.O.) EXISTING SANITARY SEWER TO FUT. STM MH 7 (B.O.) REMAIN FUT. SAN MH-SA12 (B.O. EXISTING WATERMAIN TO REMAIN - FUT. SAN MH-SA13 (B.O.) TOP 85.31 TOP 86.25 PHASE 1 S INV. 80.00 W INV. 79.88 CAP EX. WM CAP PROPOSED WM AT NE INV. 83.32 PH1 LIMIT OF 17.0m R.O.W PHASE 2 PROPOSED 300Ø WATERMAIN W INV. 79.67 BUILDING E INV. 79.64 FUT. STM MH 10 (B.O.) **EXISTING** INSTALL 300Ø WM IN PHASE 2 PUBLIC ROAD **PARKING** EX. W INV. 83.22 N INV. 83.09 LOT S INV. 83.09 EX. STM MH 10 -TOP 85.06 / N INV. 83.00 EX. NE INV. 83.12 EX. S INV. 83.00 EX. 600Ø STM @ 0.60% — (PIPE SLOPE AS PER am. candaras associates inc. "Site -ISSUED FOR ZBA & OPA KK 25-01-24 ervicing & Storm Water Management Plan" dated May 21, 2010 N INV. 82.78 KK 23-10-27 ISSUED FOR ZBA & OPA S INV. 82.74 w/ ORIFICE PLATE EX. STM MH 9 📥 REVISIONS TO DRAWING EXISTING EASMENTS AND LEGAL LINES — TOP 84.98 AS PER TOPOGRAPHIC SURVEY 22-25-073-00 EX. N INV. 82.68 SUPERPIPE ALL PREVIOUS ISSUES OF THIS DRAWING ARE SUPERSEDED BY JD BARNES J.D BARNES DATED FEB 2, NE INV. 82.71 CAP PROPOSED WM -2023. EXISTING EASEMENTS OVER ALL EX. SE INV. 82.65 ROAD PIPES THAT ARE PROPOSED TO REMAIN EX. SW INV. 83.04 (ASSUMED TO BE ABANDONED) TRIBUTE (BROOKDALE) TOP 84.77 WITHIN THE PRIVATE ROADS, AND ARE EX. 300Ø STM (ASSUMED TO BE ABANDONED) -NE INV. 82.89 USED TO CONVEY FLOWS TOP 85.10 STM MH 3 LIMITED - SW INV. 82.89 TOP 85.05 SW INV. 82.89 FROM DIXIE ROAD TO THE EXISTING NE INV. 82.89 HEADWALL ARE TO REMAIN. SW INV. 82.89 (PIPE SLOPE AS PER am. candaras associates inc. "Site MUNICIPALITY ervicing & Storm Water Management Plan" dated May 21, 2010 TOP 84.92 NE INV. 82.89 CITY OF PICKERING S INV. 82.74 OGS STC 6000 w/ ORIFICE PLATE EX. 600Ø STM @ 0.60% -DIXIE FOR EX BUILDING DOMESTIC & (PIPE SLOPE AS PER am. candaras associates inc. "Site FIRE WM CONNECTIONS. icing & Storm Water Management Plan" dated May 21, 2010 CONNECT CHAMBER TO PHASE 3 1101A, 1105, and 1163 20m ROW WM. KINGSTON ROAD **EXISTING** AND FIRE WATER SERVICES FOR EX. 600Ø STM @ 0.39% — **EXISTING BUILDING AND CONNECT** BUILDING TO EXISTING SERVICES AS SHOWN SITE SERVICING PLAN PHASE 2 DED VOLUME = 440m³ 100-YEAR RELEASE RATE = 63.82 L/s OUTLET INV. 83.11 EX. STM MH 6 -LEAD 300Ø STM @ 2.0% EX. 675Ø STM @ 0.39% -(SLOPE ASSUMED) 🦟 EX. СВ 19 ^Е 10.0m OFFSET -FROM TRCA **FLOODLINE** - 600Ø STM @ 0.29% – EX. STM MH 18 750Ø STM @ 0.39% (ASSUMED) -TOP 85.05 (PIPE SLOPE TO BE CONFIRMED) └─ 750Ø STM @ 0.23% NW INV. 82.86 EX. NE INV. 82.07 EX. STM MH 23 SW INV. 82.77 TOP 87.27 EX. NW INV. 82.57 EX. STM MH 19 TOP 86.18 EX. NW INV. 82.35 EX. NE INV. 82.28 AS PER am. candaras associates inc. "Site Servicing & OGS TOP 84.02 NE INV. 82.57 orm Water Management Plan" dated May 21, 2010 Z.B. CAD 20 K.K. SW INV. 82.54 HIGHWAY 401 EX. NE INV. 82.02 EX. SW INV. 82.26 SCALE EX. SW INV. TO OCTOBER 2023 JOB NUMBER SHEET NUMBER SS2 221-12931



































TRCA EROSION AND SEDIMENT CONTROL NOTES:

- EROSION AND SEDIMENT CONTROL (ESC) MEASURES WILL BE IMPLEMENTED PRIOR TO, AND MAINTAINED DURING THE CONSTRUCTION PHASES, TO PREVENT ENTRY OF SEDIMENT INTO THE WATER. ALL DAMAGED EROSION AND SEDIMENT CONTROL MEASURES SHOULD BE REPAIRED AND/OR REPLACED WITHIN 48 HOURS OF THE INSPECTION.
- 2. DISTURBED AREAS WILL BE MINIMIZED TO THE EXTENT POSSIBLE, AND TEMPORARILY OR PERMANENTLY STABILIZED OR RESTORED AS THE WORK PROGRESSES.
- ALL IN-WATER AND NEAR-WATER WORKS WILL BE CONDUCTED IN THE DRY AND APPROPRIATE EROSION AND SEDIMENT CONTROLS
- 4. THE EROSION AND SEDIMENT CONTROL STRATEGIES OUTLINED ON THE PLANS ARE NOT STATIC AND MAY NEED TO BE UPGRADED/AMENDED AS SITE CONDITIONS CHANGE TO MINIMIZE SEDIMENT LADEN RUNOFF FROM LEAVING THE WORK AREAS. IF THE PRESCRIBED MEASURES ON THE PLANS ARE NOT EFFECTIVE IN PREVENTING THE RELEASE OF A DELETERIOUS SUBSTANCE, INCLUDING SEDIMENT, THEN ALTERNATIVE MEASURES MUST BE IMPLEMENTED IMMEDIATELY TO MINIMIZE POTENTIAL ECOLOGICAL IMPACTS. TRCA ENFORCEMENT OFFICER SHOULD BE IMMEDIATELY CONTACTED. ADDITIONAL ESC MEASURES TO BE KEPT ON SITE AND USED, AS NECESSARY.
- AN ENVIRONMENTAL MONITOR WILL ATTEND THE SITE TO INSPECT ALL NEW CONTROLS IMMEDIATELY AFTER INSTALLATION. INSPECTION OF ESC MEASURES TO BE WILL OCCUR, AT MINIMUM:
- 5.1. ON A WEEKLY BASIS;
- 5.2. PRIOR TO SIGNIFICANT RAINFALL EVENTS (MINIMUM PREDICTED 25MM OVER 24
- AFTER EVERY RAINFALL/SNOWMELT EVENT; AND
- DAILY DURING EXTENDED RAINFALL PERIODS.

INSPECTIONS WILL FOCUS ON MEASURES RELATED TO EROSION AND SEDIMENT CONTROLS, DEWATERING OR UNWATERING, RESTORATION AND IN-OR NEAR- WATER WORKS. SHOULD CONCERNS ARISE ON SITE THE

ENVIRONMENTAL MONITOR WILL CONTACT THE TRCA ENFORCEMENT OFFICER AS WELL AS THE PROPONENT.


- 6. ALL ACTIVITIES, INCLUDING MAINTENANCE PROCEDURES, WILL BE CONTROLLED TO PREVENT THE ENTRY OF PETROLEUM PRODUCTS, DEBRIS, RUBBLE, CONCRETE OR OTHER DELETERIOUS SUBSTANCES INTO THE WATER. VEHICULAR REFUELING AND MAINTENANCE WILL BE CONDUCTED A MINIMUM OF 30 METRES FROM THE WATER
- ALL GRADES WITHIN THE REGULATORY FLOOD PLAIN WILL BE MAINTAINED OR MATCHED.
- THE PROPONENT/CONTRACTOR SHALL MONITOR THE WEATHER SEVERAL DAYS IN ADVANCE OF THE ONSET OF THE PROJECT TO ENSURE THAT THE WORKS WILL BE CONDUCTED DURING FAVOURABLE WEATHER CONDITIONS. SHOULD AN UNEXPECTED STORM ARISE, THE CONTRACTOR WILL REMOVE ALL UNFIXED ITEMS FROM THE REGIONAL STORM FLOOD PLAIN THAT WOULD HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTRUCTION TO FLOW, E.G., FUEL TANKS, PORTA-POTTIES, MACHINERY, EQUIPMENT, CONSTRUCTION MATERIALS, ETC.
- ALL DEWATERING/UNWATERING SHALL BE TREATED AND RELEASED TO THE ENVIRONMENT AT LEAST 30 METRES FROM A WATERCOURSE OR WETLAND AND ALLOWED TO DRAIN THROUGH A WELL VEGETATED AREA. NO DEWATERING EFFLUENT SHALL BE SENT DIRECTLY TO ANY WATERCOURSE, WETLAND OR FOREST, OR ALLOWED TO DRAIN ONTO DISTURBED SOILS WITHIN THE WORK AREA. THESE CONTROL MEASURES SHALL BE MONITORED FOR EFFECTIVENESS AND MAINTAINED OR REVISED TO MEET THE OBJECTIVE OF PREVENTING THE RELEASE OF SEDIMENT LADEN WATER.
- 10. ALL ACCESS TO THE WORK SITE SHALL BE FROM EITHER SIDE OF THE WATERCOURSE. NO EQUIPMENT OR VEHICLES ARE PERMITTED TO CROSS THROUGH THE WATERCOURSE UNLESS APPROVED BY TRCA.


PICKERING Erosion and Sediment Control General Notes


- Prior to commencement of any on-site work/topsoil stripping, erosion and sedimen control (ESC) measures, as per approved Erosion & Sediment Control Plan, must be installed to prevent surface runoff from leaving the site "untreated". All ESC measures are to be maintained until the site has been stabilized.
- The contractor shall be responsible for the proper installation, maintenance and removal of all temporary erosion and sediment control measures during construction, as directed by the Engineer or the City of Pickering.
- 3. Sediment control fence to use geotextile with weave density of 270R terrafix or
- 4. All exposed soils shall be immediately stabilized as directed by the Engineer or City of
- 5. Check dams are to be used in any temporary drainage swales required during the
- Additional erosion and sediment control measures may be required and shall be determined by the Engineer or the City of Pickering.
- Inspection of the proposed erosion and sediment control measures will occur on a
 weekly basis, after rainfall events exceeding 10mm or after rapid snow melt events and
 daily during extended rain or snow melt periods. The silt control fence must be
 inspected for rips or tears, broken stakes, blow outs and accumulation of sediment. The silt control fence must be fixed and/or replaced immediately when damaged. Accumulated sediment must be removed from the silt control fence when accumulation
- has accumulated to a depth greater than 50% of all the upstream check dams.
- 10. Cleaning and repair of mud mats and any other temporary sediment control measures shall be done as necessary through regular inspection or as directed by the Engineer or City of Pickering. All damaged ESC measures shall be repaired and/or replaced within 48 hours of the inspection.
- 11. Materials to repair damaged ESC measures must be kept on-site at all times.
- 12. The ESC strategies on these plans are not static and may need to be upgraded/amended as site conditions change to prevent sediment releases. Failed ESC measures must be repaired immediately.


- No construction activity or machinery shall intrude beyond the silt control fence or limit
 of development. All construction vehicles shall leave the site at designated locations as shown on the plans. All materials and equipment shall be stored on site in a designated area. No materials or equipment shall be stored on the Municipal right of
- The contractor must clean adjacent roads on a regular basis. The road shall be, at a minimum scraped daily and flushed (if necessary) on Friday evenings or Saturday
- 16. Dust control to be reviewed daily. Water truck or calcium chloride is to be provided on-site and haul roads/working areas are to be treated as required to ensure that dust
- 17. At the end of construction period, accumulated sediment is to be removed off site prior to the removal of the silt fence.
- 19. All topsoil stockpiles shall be surrounded with sediment control fence and stabilized with seed mix as per this drawing.
- Disturbed areas are to be minimized to the extent possible and stabilized as the work progresses. Any area exposed for more than 30 days will be stabilized.












N.T.S **KEY PLAN** LEGEND





APPROVED R. STARR


ACCESS (URBAN CROSS-SECTION)



P-824.2







CAD 20

DESIGNED Z.B.

JOB NUMBER

221-12931

SCALE

CHECKED

SHEET NUMBER

K.K.

OCTOBER 2023

ESC6