# TRIBUTE (BROOKDALE) LIMITED

1101A, 1105, and 1163 Kingston Road

January 24, 2025



# wsp



# 1101A, 1105 AND 1163 KINGSTON ROAD FUNCTIONAL SERVICING REPORT

TRIBUTE (BROOKDALE) LIMITED

FUNCTIONAL SERVICING REPORT

PROJECT NO.: 221-12931 DATE: JANUARY 2025

WSP CANADA INC. 150 COMMERCE VALLEY DRIVE WEST THORNHILL, ON, CANADA L3T 7Z3

WSP.COM

# REVISION HISTORY

#### FIRST ISSUE

2023-10-27	Issued for Zoning By-Law Amendment (ZBA), and Official Plan Amendment (OPA)		
Prepared by	Reviewed by	Approved By	
Zack Banks, EIT	Kostas Kyriopoulos, P, Eng.	Kostas Kyriopoulos, P, Eng.	
REVISION 1			
Zack Banks	Kostas Kyriopoulos, P, Eng.	Kostas Kyriopoulos, P, Eng.	
Prepared by	Reviewed by	Approved By	
REVISION 2			
Prepared by	Reviewed by	Approved By	

# SIGNATURES

PREPARED BY



2025-01-24

Date

Zack Banks, EIT Designer

REVIEWED BY	SPROFESSION AL	
A	S K. KYRIOPOULOS 100149502 Jan. 24, 2025	
	BUNCE OF ONTATI	-

Kostas Kyriopoulos, P.Eng., Manager

2025	5-0	1-2	24

Date

This report was prepared by WSP Canada Inc. (hereinafter "WSP") for the account of Tribute (Brookdale) Limited, in accordance with the professional services agreement. The disclosure of any information contained in this report is the sole responsibility of the intended recipient. The material in it reflects WSP Canada Inc.'s best judgement in light of the information available to it at the time of preparation. With the exception of the City of Pickering who can rely on this report for permitting and approvals, any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. WSP Canada Inc. accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report. This limitations statement is considered part of this report.

The original of the technology-based document sent herewith has been authenticated and will be retained by WSP for a minimum of ten years. Since the file transmitted is now out of WSP's control and its integrity can no longer be ensured, no guarantee may be given with regards to any modifications made to this document.

# wsp

# TABLE OF CONTENTS

1		1
1.1	Site Description	1
1.2	Public Right - Of - Way	2
2	WATER SUPPLY AND APPURTENANCES	6
2.1	Existing Conditions	6
2.2	Municipal Watermain Improvements	6
2.3	Proposed Water Services	6
2.3.1	Phase 1	6
2.3.2	Phase 2	7
2.3.3	Phase 3	8
2.3.4	Phase 4	8
2.3.5	Phase 5	8
3	SANITARY SEWAGE SYSTEM	15
3.1	Existing Conditions	15
3.2	Design Parameters	15
3.3	Post - Development Sewage Flow	16
3.4	Proposed Sanitary Servicing	16
3.4.1	Phase 1	16
3.4.2	Phase 2	17
3.4.3	Phase 3	17
3.4.4	Phase 4	18
3.4.5	Phase 5	18
3.5	Sanitary Capacity Analysis	19
4	STORM DRAINAGE SYSTEM	26
4.1	Existing Conditions	
4.2	Proposed Minor Storm Drainage System	
4.2.1	Phase 1	27
4.2.2	Phase 2	28

# wsp

4.2.3	Phase 3	29
4.2.4	Phase 4	29
4.2.5	Phase 5	
4.3	Major Storm Drainage System	
5	SITE GRADING	
5.1	Existing Conditions	
5.2	Proposed Conditions	
6	EROSION AND SEDIMENT CONTROL	39
7	CONCLUSIONS	40
7.1	Water	40
7.2	Sanitary	40
7.3	Storm	40

#### FIGURES

	/
FIGURE 1-B - PRE-DEVELOPMENT PLAN	4
FIGURE 1-C - POST-DEVELOPMENT PLAN	5
FIGURE 2-A - EXISTING WATERMAINS	9
FIGURE 2-B - PHASE 1 WATER SERVICING	0
FIGURE 2-C - PHASE 2 WATER SERVICING	11
FIGURE 2-D - PHASE 3 WATER SERVICING	2
FIGURE 2-E - PHASE 4 WATER SERVICING	3
FIGURE 2-F - PHASE 5 WATER SERVICING14	4
FIGURE 3-A - EXISTING SANITARY SEWERS	0
FIGURE 3-B - PHASE 1 SANITARY SERVICING2	21
FIGURE 3-C - PHASE 2 SANITARY SERVICING	2
FIGURE 3-D - PHASE 3 SANITARY SERVICING	23
FIGURE 3-E - PHASE 4 SANITARY SERVICING	4
FIGURE 4-A – EXISTING STORM SEWERS	52
FIGURE 4-B - PHASE 1 STORM SERVICING	53
FIGURE 4-C – PHASE 2 STORM SERVICING	4
FIGURE 4-D – PHASE 3 STORM SERVICING	55
FIGURE 4-E – PHASE 4 STORM SERVICING	6

# vsp

#### TABLES

#### APPENDICES

- **A** SANITARY FLOW CALCULATIONS AND DESIGN SHEETS
- **B** STORM FLOW CALCULATIONS AND DESIGN SHEETS
- **C** SITE SERVICING AND GRADING PLANS
- D EROSION AND SEDIMENT CONTROL PLANS
- **E** SUPPORTING DOCUMENTS

# **1** INTRODUCTION

WSP has been retained by Tribute (Brookdale) Limited to prepare a Functional Servicing Report in support of the proposed redevelopment of the site located at 1101A, 1105 and 1163 Kingston Road in the City of Pickering, Ontario. The proposed plan, which will be constructed in five phases, involves the redevelopment of the existing commercial site into a five building multi-use development. This report provides the conceptual framework for water distribution, sanitary sewage and storm drainage for the site prior to the commencement of detailed design. A Stormwater Management Report outlining the proposed conceptual Stormwater Management controls on this site has been prepared by WSP under a separate cover.

In preparing this report, WSP staff secured and reviewed the Site Plan prepared by Turner Fleischer Architects Inc., topographic surveys prepared by J.D. Barnes Ltd. (see **Appendix E**), and record drawings provided by the Region of Durham (see **Appendix E**). This report is intended to provide the functional design framework for the proposed development. All required approvals from the City of Pickering, Region of Durham, and all other governing bodies shall be obtained as part of the registration of the development.

## 1.1 SITE DESCRIPTION

The subject site is approximately 7.75 ha (19.15 acres), and it is located at 1101A, 1105 and 1163 Kingston Road in the City of Pickering, Ontario. The site is bounded by Kingston Road to the north-west, a segment of Walnut Lane and a segment of Public Road to the north-east, Highway 401 to the south and existing commercial lands to the west. Under the existing conditions, the site contains five commercial buildings. The location and existing site conditions are illustrated in **Figure 1-A** – **"Location Map",** and **Figure 1-B** – **"Pre-development Plan"** respectively.

Based on the site plan provided by Turner Fleischer, the proposed development will be mixed use, and it will include five buildings that will be constructed across five phases. The intention of the phasing is to keep the existing commercial developments located outside of the phase limits operational in the interim. The existing public driveway that runs along the north-east boundary of the site will also be replaced by a complete 20.0 m R.O.W. as part of the Walnut Lane extension project.

The first phase, which will be located at the north end of the development, will introduce one new building (Building A). With the introduction of this building, two of the existing commercial developments located within the site will be removed. The second phase, which will be located at the south-east corner of the site, will introduce one new Building (Building 'B') and one existing commercial development will be removed. The third phase, located at the north-west corner of the site, will introduce one new Building commercial development will be removed. The third phase, located at the north-west corner of the site, will introduce one new building 'C') and an existing commercial development will be removed. The fourth phase, which will be in the middle of the site, will introduce one new building (Building 'D') and a Park. No existing commercial developments will be removed in Phase 4. The fifth

phase will introduce one new Building (Building 'E') and one existing commercial development will be removed.

The development statistics that summarize each of the proposed phases are outlined in Table 1. The ultimate conditions are illustrated in **Figure 1-C – "Post Development Plan"**.

Phase	Area (ha)	Building	Land Use	Units	Residential Population	Commercial GFA (sq.m.)	Number of Floors
1	1.13	Building 'A'	Mixed-Use Residential	582	1,157	4,771	19+MPH
2	1.39	Building 'B'	Residential	1,259	2507	N/A	35+MPH
3	0.60	Building 'C'	Residential	598	1,191	N/A	23+MPH
4	2.16	Building 'D'	Residential	852	1,696	1,249	35+MPH
5	2.47	Building 'E'	Mixed-Use Residential	1,973	3,927	565	35+MPH
TOTAL	7.75			5,264	10,478	6,585	

 Table 1 – Development Statistics Summary

<sup>(1)</sup> Occupancy rates, per capita flows and peaking factor are as per the Region of Durham Design Specifications

<sup>(2)</sup> Unit Counts and Floor Areas from drawings prepared by Turner Fleisher

## 1.2 PUBLIC RIGHT - OF - WAY

Public roads that run through the site and connect to Walnut Lane are proposed as part of the site plan. A 17.0 m right - of - way will wrap around the south side of the Phase 1 lands and the west side of the Phase 4 lands. The 17.0 m right - of – way will have an 8.5 m pavement width with boulevard areas on both sides. A 20.0 m right - of - way will wrap around the north-west side of the Phase 1 lands and the south side of the Phase 4 lands. The 20.0 m right - of – way will have 9.75 m pavement width with boulevard areas on both sides. The 20.0 m right - of – way will terminate at the west property boundary, with the option to extend this road to Dixie Road in the future. The proposed road layout is outlined in **Figure 1-C – "Post Development Plan".** 







# 2 WATER SUPPLY AND APPURTENANCES

## 2.1 EXISTING CONDITIONS

Based on the record drawings from the Region of Durham, and the topographic surveys prepared by J.D. Barnes Ltd the existing infrastructure in the vicinity of the site is as follows:

- > a 300 mm diameter watermain on Kingston Road north of the site;
- a 250 mm diameter watermain on Walnut Lane;
- a 100 mm diameter watermain on Walnut Lane;
- a series of 100 250 mm diameter watermains located within the existing commercial site that service the existing commercial developments; and
- an external chamber and backflow preventor room located east of Walnut Lane that services all buildings within the existing development.

The location of the existing water services is illustrated in Figure 2A - "Existing Watermains".

### 2.2 MUNICIPAL WATERMAIN IMPROVEMENTS

A new 300 mm diameter watermain will be constructed north of the site as part of the future Walnut Lane extension. The proposed watermain will connect to the existing watermains on Liverpool Road and Kingston Road. The future watermain will be active at the time of the proposed redevelopment of this site, so the intention is to use it as the connection point for the proposed development. At this time, it is WSP's understanding that the 300 mm diameter watermain will have the capacity to service the proposed development.

### 2.3 PROPOSED WATER SERVICES

An illustration of the proposed water servicing strategy for each phase is outlined in **Figures 2B – 2F**. The following subsections describe the proposed water servicing in detail.

#### 2.3.1 PHASE1

In Phase 1, a 300 mm diameter watermain will be constructed along the proposed 17.0 m public right-of-way south of Building 'A'. This watermain will connect to the 300 mm diameter watermain within Walnut Lane and will be capped at the limit of the 17.0m right-of-way until the right-of-way is continued in Phase 4.

A set of domestic and fire water service connections will be made directly to the proposed 300 mm diameter watermain within the 17.0m right-of-way to service Building 'A'. The connections will be made in accordance with Region of Durham Standards. If the height of these towers exceeds 84 m, a secondary fire connection will be provided as per Ontario's building code requirements. Sizing of the water service connections will be coordinated with the Region of Durham and the mechanical engineering consultant at the detailed design stage.

To limit the disturbance to the existing commercial development during the construction of Phase 1, all existing non-essential watermains intersecting the Phase 1 limits will be capped at the phase limit. Based on the topographic survey, it is believed that the existing building within the Phase 3 lands relies on the existing 200 mm diameter fire main and the 100 mm diameter domestic watermain that falls within the proposed Phase 1 lands. Temporary water services will be constructed off of the proposed 300 mm watermain within the 17.0m right-of-way to ensure that water service to the existing building within Phase 3 is preserved. Refer to **Figure 2B - "Phase 1 Water Servicing"** for an illustration of the proposed water servicing strategy for Phase 1.

#### 2.3.2 PHASE 2

In Phase 2, a 300 mm diameter watermain will be constructed along the proposed 17.0 m public right-of-way west of Building 'B'. This watermain will tie into the 300 mm diameter watermain on Walnut Lane. The domestic and fire connections for Building 'B' will connect directly into this proposed watermain and the connections will be in accordance with Region of Durham Standards. If the height of these towers exceeds 84 m, a secondary fire connections will be provided as per Ontario's building code requirements. Sizing of the water service connections will be coordinated with the Region of Durham and the mechanical engineering consultant at the detailed design stage.

According to the topographic surveys prepared by J.D. Barnes Ltd, the existing commercial development in the south of the site has water connections that fall within the west limits of Phase 2. These connections will have to be removed to accommodate the underground structure of Building 'B', so temporary domestic and water service connections will have to be installed to reroute these existing services outside of the proposed underground structure. The temporary connections will tie into the proposed 300 mm diameter watermain within Phase 2 to prevent additional disruption to the existing development. Since the existing building relies on an external chamber and backflow preventor room located within the Phase 4 lands, a temporary chamber and backflow preventor room are proposed to be installed to service the existing building in the interim condition.

Refer to **Figure 2C - "Phase 2 Water Servicing"** for an illustration of the proposed water servicing strategy for Phase 2.

#### 2.3.3 PHASE 3

To service Building 'C', a set of domestic and fire water service connections is proposed to connect into the proposed 300 mm diameter watermain within the Phase 117.0 m right-of-way. The connections will be made in accordance with Region of Durham Standards, and if the height of the buildings exceeds 84 m, a secondary fire connection will be provided as per Ontario's building code requirements. Sizing of the water service connections will be coordinated with the Region of Durham and the mechanical engineering consultant at the detailed design stage.

Refer to **Figure 2D - "Phase 3 Water Servicing"** for an illustration of the proposed water servicing strategy for Phase 3.

#### 2.3.4 PHASE 4

In Phase 4, a 300 mm diameter watermain will be installed within the proposed 20.0 m and 17.0 m right-of-ways that fall within Phase 4. The watermain will complete a loop to the future watermain in Walnut Lane. The water services for Building 'D' will connect to the proposed 300 mm diameter watermain within the 20.0 m right-of-way. The connections will be in accordance with Region of Durham Standards, and if the height of these towers exceeds 84 m, a secondary fire connection will be provided as per Ontario's building code requirements. Sizing of the water service connections will be coordinated with the Region of Durham and the mechanical engineering consultant at the detailed design stage. Refer to **Figure 2E - "Phase 4 Water Servicing"** for an illustration of the proposed water servicing strategy for Phase 4.

#### 2.3.5 PHASE 5

In Phase 5, Building 'E' will have domestic and fire water service connections to the proposed 300 mm diameter watermain within the 20.0 m right-of-way north of the building. The water connections for Building 'E' will be made in accordance with Region of Durham Standards, and if the height of these towers exceeds 84 m, a secondary fire connections will be provided as per Ontario's building code requirements. Sizing of the water service connections will be coordinated with the Region of Durham and the mechanical engineering consultant at the detailed design stage. Refer to **Figure 2F - "Phase 5 Water Servicing"** for an illustration of the proposed water servicing strategy for Phase 5.













# **3 SANITARY SEWAGE SYSTEM**

## 3.1 EXISTING CONDITIONS

Based on the record drawings from the Region of Durham, and the topographic surveys prepared by J.D. Barnes Ltd the existing infrastructure in the vicinity of the site is as follows:

- 1050 mm diameter trunk sanitary sewer on the south side of the site;
- > 200 mm diameter sanitary sewers located in an easement on the west side of the site;
- > 200 mm diameter sanitary sewer on Walnut Lane; and
- > 200 mm diameter sanitary sewer north of the site on Kingston Road.

In the existing condition, all sanitary waste generated within the site is ultimately discharged to the 1050 mm diameter trunk sewer. The methods of connection to the trunk are summarized below:

- > The two buildings on the south side of the site have direct connections to the trunk;
- The building on the west side of the site is conveyed to the trunk via the 200 mm diameter sanitary sewer located in the easement on the west side of the site; and
- The two buildings on the north side of the site have connections to the Kingston Road sanitary sewer before connecting to the 1050 mm diameter trunk sewer.

Figure 3A - "Existing Sanitary Sewers" illustrates the existing on - site sanitary servicing strategy.

### 3.2 DESIGN PARAMETERS

To calculate the peak sanitary flows, the following Region of Durham design criteria has been utilized:

- > 180,000 L / ha / day average day flow generation rate for commercial use;
- 364 L / cap / day average day flow generation rate for residential use;
- > Population equivalent based on unit type for residential use:
  - o 1.5 people per one Bedroom residential apartment unit;
  - o 2.5 people per two Bedroom residential apartment unit;
  - o 3.5 people per three Bedroom residential apartment unit; and
  - o 4.5 people per four Bedroom residential apartment unit.
- Peaking Factor for residential use: Harmon Formula  $KH = 1 + \frac{14}{4+R^{0.5}}$ ; and
- Infiltration: 0.26 L / ha / s.

## 3.3 POST - DEVELOPMENT SEWAGE FLOW

The anticipated post - development sanitary flows to the downstream sanitary sewer system have been calculated based on the Region of Durham Design Criteria and site statistics provided by Turner Fleischer Architects. Detailed flow generation design sheets are included in **Appendix A**. The flow summary for each phase is included in **Table 2**.

Phase	Buildings	Average Daily Flow	Peak Flow
1	Building 'A'	6.16 L/s	19.61 L/s
2	Building 'B'	10.92 L/s	37.41L/s
3	Building 'C'	5.17 L/s	18.97 L/s
4	Building 'D'	7.97 L/s	26.83 L/s
5	Building 'E'	17.30 L/s	56.03 L/s

#### Table 2 – Sanitary Flow Generation Summary

### 3.4 PROPOSED SANITARY SERVICING

As part of the Walnut Lane extension project, there will be a sanitary sewer installed within the Walnut Lane R.O.W that will be sized to convey flows from the proposed development. The future Walnut Lane sewer will discharge to the 1050 mm diameter trunk sanitary sewer south of the site.

As the subject site is developed, connections from the proposed development to the future sanitary sewer in Walnut Lane will be made via sanitary sewers installed within the site. The following subsections outline the proposed sanitary servicing strategy in detail. Sanitary design sheets and drainage plans corresponding to the proposed sanitary servicing strategy are given in **Appendix A**.

#### 3.4.1 PHASE1

In Phase 1, one sanitary sewer connection that services Building 'A' will be made to the future sanitary sewer on Walnut Lane. Preliminary sizing of the sanitary connection suggests that the connection should be 250 mm diameter. However, the final size will be coordinated with the Mechanical Engineer at the detailed design stage.

The topographic survey indicates that the existing commercial developments within the Phase 1 lands utilize a sanitary service connection to Kingston Road. It is proposed that during Phase 1 construction this existing sanitary connection is abandoned.

Refer to **Figure 3B - "Phase 1 Sanitary Servicing"** for an illustration of the proposed sanitary servicing strategy for Phase 1.

#### 3.4.2 PHASE 2

In Phase 2, a public sanitary sewer that connects to the future sanitary sewer on Walnut Lane will be constructed within the proposed 20.0 m right-of-way west of Building 'B'. This leg of public sanitary sewer will be sized to convey all sanitary flows from Phase 2, Phase 4, and Phase 5. Preliminary sizing suggests that this sewer in the R.O.W should be 300 mm diameter. However, the size will be confirmed during detailed design.

To provide sanitary service to Building 'B', a connection will be provided to the proposed sanitary sewer within the proposed 20.0 m right-of-way. Preliminary sizing suggests that this connection should be 200mm diameter, but the final size will be coordinated with the Mechanical Engineer at the detailed design stage. Refer to **Figure 3C - "Phase 2 Sanitary Servicing"** for an illustration of the proposed sanitary servicing strategy for Phase 2.

According to the topographic surveys prepared by J.D. Barnes Ltd, the existing commercial development has a sanitary connection to the existing trunk sanitary sewer that runs along the south side of the site. It is proposed that this existing sanitary service connection to the trunk is removed during Phase 2 construction. However, the trunk sanitary sewer must be protected and maintained during all phases of construction.

#### 3.4.3 PHASE 3

In Phase 3, a 200 mm diameter sanitary sewer is proposed to connect to the existing sanitary sewer network that runs in an easement along the west side of the site. This existing system ultimately flows south and ties into the existing 1050 mm diameter trunk sanitary sewer on the south side of the site.

To service Building 'C', a connection to the proposed 200 mm diameter sanitary sewer within the 17.0 m right-of-way before will be made. Preliminary sizing suggests that this connection should be 200mm diameter, but the final size will be coordinated with the Mechanical Engineer at the detailed design stage.

As per the topographic survey, connecting Building 'C' to the existing sanitary sewer network that runs in an easement along the west side of the site matches the existing sanitary drainage strategy for the development currently within the Phase 3 lands. As per the Phase 3 sanitary design sheet included in **Appendix A**, WSP does not have concerns with the capacity of the existing local sanitary network to convey sanitary flows to the trunk.

The existing sanitary connection for the commercial development within the Phase 3 lands will be removed during Phase 3 construction. Refer to **Figure 3D - "Phase 3 Sanitary Servicing"** for an illustration of the proposed sanitary servicing strategy for Phase 3.

#### 3.4.4 PHASE 4

In Phase 4, a public sanitary sewer that connects to the future sanitary sewer on Walnut Lane will be constructed within the proposed public R.O.W south of Building 'D'. This leg of public sanitary sewer will be sized to convey all sanitary flows from Phase 4 and 5. Preliminary sizing suggests that this sewer in the R.O.W should be 300 mm diameter. However, the size will be confirmed during detailed design.

Building 'D' will have one sanitary service connection to the sanitary sewer within the proposed public R.O.W. Preliminary sizing of the sanitary connection suggests that the size should be 200 mm diameter. However, the final size will be coordinated with the Mechanical Engineer at the detailed design stage.

The proposed sanitary sewer in the public R.O.W south of Building 'D' will not be extended along the full length of the R.O.W to the property line on the west side of the development. WSP believes that even with minimal pipe sloping, there is too much length and not enough cover to have a sanitary sewer drain by gravity from the lands to the west and connect to the future sanitary sewer in Walnut Lane. Thus, any future redevelopment within the lands to the west shall direct sanitary flows west to Dixie Road before draining south to the 1050 mm diameter trunk sewer.

Although no existing buildings will be removed during Phase 4, the topographic surveys prepared by J.D. Barnes Ltd shows that there is an existing 200 mm diameter sanitary connection to the municipal sanitary sewer on the west side of the site that falls within the proposed Phase 4 Lands. This connection is shown to be capped and WSP believes it is not currently being used to service a development. Thus, it is proposed that this connection be removed as part of the Phase 4 redevelopment.

Refer to **Figure 3E - "Phase 4 Sanitary Servicing"** for an illustration of the proposed sanitary servicing strategy for Phase 3.

#### 3.4.5 PHASE5

In Phase 5, Building 'E' is proposed to have one sanitary service connection to the sanitary sewer within the proposed R.O.W north of the building. Preliminary sizing of the sanitary connection suggests that the connection should be 250 mm diameter. However, the final size will be coordinated with the mechanical engineer at the detailed design stage.

According to the topographic surveys prepared by J.D. Barnes Ltd, the existing commercial development on the south side of the site has a sanitary connection to the 200 mm diameter municipal sanitary sewer that runs along the west boundary of the site. It is proposed that this existing service connection is removed during the Phase 5 redevelopment, while the other existing municipal sanitary sewers within the Phase 5 lands are proposed to remain.

Refer to **Figure 3F - "Phase 5 Sanitary Servicing"** for an illustration of the proposed sanitary servicing strategy for Phase 5.

## 3.5 SANITARY CAPACITY ANALYSIS

WSP contacted the Region of Durham regarding the 1050 mm diameter trunk sanitary sewer capacity for a nearby site in October of 2021. At that time, it was indicated that capacity was to be allocated on a first come first serve basis at the time of signing a development agreement. There are currently other ongoing developments within the service area and as such the Region of Durham is in the process of confirming capacity limitations through the use of ongoing flow monitoring. This will form the basis of determining any potential upgrades that will be required as development continues to proceed within the existing sanitary drainage boundary of Pickering City Centre area and beyond.













# **4 STORM DRAINAGE SYSTEM**

A Stormwater Management Report for this development also prepared by WSP has been prepared under a separate cover. It identifies the stormwater controls under which this site will operate to comply all relevant Wet Weather Flow Management Guidelines (WWFMG).

## 4.1 EXISTING CONDITIONS

Based on the record drawings from the Region of Durham, and the topographic surveys prepared by J.D. Barnes Ltd the existing infrastructure in the vicinity of the site is as follows:

- > 200 mm 900 mm diameter storm sewers across the site;
- Two quantity control chambers (one within the proposed Phase 1 lands, and one within the proposed Phase 2 lands);
- On site surface storage;
- On site roof storage;
- > One headwall at the south side of the site. This headwall contains two (2) inlets; and
- ▶ 1.83 m x 1.83 m box culvert located at the south end of the site.

In the existing condition, all of the on - site storm sewers ultimately discharge to the 1.83 m x 1.83 m box culvert located at the south end of the site. It is WSP's understanding that the box culvert runs beneath Highway 401 and discharges to a 900 mm culvert under the Go Transit and CNR tracks. It is understood that all flows from the site are ultimately discharged to Frenchman's Bay. Based on the topographic surveys prepared by J.D. Barnes Ltd, it is believed that the existing on - site storm sewers are very shallow due to the outlet elevation and size of the site. The methods of connection are as follows:

- The section of the site that falls within the future Phase 1, Phase 3, and Phase 4 lands drain via the storm network that runs along the west side of the site (herein referred to Existing Storm Network A). Sewers in the main network range from 450 mm diameter to 675 mm diameter in size, and this network has a direct connection to the headwall before discharging to the box culvert. The network also has an existing 150 mm diameter orifice at EX. STM MH 10 that provides quantity control and allows the network to backflow into an on site quantity control chamber located in the future Phase 3 Lands;
- The section of the site that falls within the future Phase 2, and Phase 5 lands drains through a network that runs along the east and south sides of the site (herein referred to Existing Storm Network B). Sewers in the main network range from 450 mm diameter to 525 mm diameter in size. Based on the topographic surveys prepared by J.D. Barnes Ltd, it is believed that this network discharges directly to the box culvert and avoids the headwall. The network also has an existing 150 mm diameter orifice at EX. STM MH 18 that provides quantity control and allows the

network to backflow into an on - site underground storage chamber located in the future Phase 2 Lands; and

The segment of driveway within the Phase 4 lands that is located west of the headwall drains via a storm network that runs beneath the driveway (herein referred to Existing Storm Network C). The sewers of the main network that fall within the proposed development range from 525 mm diameter to 900 mm diameter and the system has a direct connection to the headwall. Based on the topographic surveys prepared by J.D. Barnes Ltd, it is believed that this storm network west of the headwall collects drainage from Dixie Road and the existing commercial developments to the west.

The existing on - site storm features are illustrated in figure Figure 4A - "Existing Storm Sewers".

## 4.2 PROPOSED MINOR STORM DRAINAGE SYSTEM

As part of the Walnut Lane extension project, there will be a storm network installed within the Walnut Lane R.O.W that will be sized to capture and convey the proposed storm flows within Walnut Lane. The future Walnut Lane sewer will discharge flows to a proposed headwall east of the site. The proposed development will not use the future Walnut Lane storm sewer network to convey its storm flows. Instead, the proposed development will use on - site sewer networks to convey flows to the box culvert located south of the site. The proposed on-site minor storm drainage system will capture all flows up to the 100-year event and release them to the box culvert at the allowable release rate.

The following sections outline the proposed phased storm servicing strategy in detail. Additional details regarding the allowable release rate and overall storm servicing strategy for the site is outlined in the Stormwater Management Report prepared by WSP under a separate cover.

#### 4.2.1 PHASE1

All storm flows from Phase 1 that are outside of the proposed 17.0m right-of-way will be collected by an internal storm drainage system and directed to a storage tank within Building 'A'. Details regarding the internal drainage system will be determined at the detailed design stage, but the system is to be fit with a jellyfish treatment unit to provide the required quality control for the impervious at grade areas within Phase 1. The storage tank will discharge the flows to a maximum release rate of 16.93 L/s during the 100-year storm event, and it will be designed to hold a volume of 520 m<sup>3</sup>. Preliminary sizing of the storm service connection from the storage tank indicates that the size should be 300 mm diameter. However, the final size will be confirmed at the detailed design stage.

Storm flows from the Phase 1 right-of-way will be conveyed into a proposed superpipe that will be located within the 17.0m right-of-way. As demonstrated in **Figure 4B - "Phase 1 – Storm Servicing"**, both the Phase 1 storm tank and the 17.0m right-of-way will be routed through this superpipe and into Existing Storm Network A. Preliminary sizing suggests that this superpipe should be 975 mm diameter in size. However, the final size will be confirmed at the detailed design stage.

A manhole fitted with a flow control device will limit the release rate from the entire Phase 1 area into Existing Storm Network A to 54.98L/s during the 100-year storm event. At this time, it is planned to have the existing OGS STC 6000 within Existing Storm Network A provide the required quality control for the right of-way drainage. The ability for this existing unit to meet the treatment objectives will be assessed at the detailed design stage.

Since the proposed release rate from the Phase I area is less than the allowable release rate, there will be no adverse effects to Existing Storm Network A. The Phase I storm sewer drainage plans and design sheets that support this are included in **Appendix B**. Additional details relating to the proposed Phase I storm servicing strategy and modelling are included in the Stormwater Management Report prepared by WSP under a separate cover.

#### 4.2.2 PHASE 2

Storm flows from Phase 2 (excluding the R.O.W) will be collected by an internal storm drainage system and directed to a storage tank within Building 'B'. Specifications regarding the internal drainage system will be determined at the detailed design stage, but the system is to be fit with a jellyfish treatment unit to provide the required quality control for the impervious at grade areas within Phase 2. The storage tank will discharge the flows to a maximum release rate of 63.82 L/s during the 100-year event. The proposed tank will have a storage volume of 440 m<sup>3</sup>.

A storm connection is proposed to connect Building 'B' to Existing Storm Network B. Preliminary sizing suggests that the connection should be 300mm diameter. However, the final size will be confirmed at the detailed design stage.

To avoid backflow into proposed Building 'B', the 10m-250 mm diameter orifice on the northeast side of STM MH 18 will be removed. Remodelling the system without the orifice and backflow suggests that the existing 525 mm diameter sewers will need to be upgraded to sizes ranging from 600 to 750 mm diameter. In the analysis, it was assumed that the existing pipe slopes measured from the topographic surveys prepared by J.D. Barnes Ltd wiill be maintained.

Storm flows from the Phase 2 right-of-way will be conveyed into a proposed 1200 mm diameter superpipe that will span across the site and tie into Existing Storm Network A via Existing MH 9. In the interim condition, the superpipe will only take flows from the Phase 2 right-of-way and discharge will be limited to a maximum 8.7 L/s in the 100-year storm event by a manhole fitted with a flow control device. In the ultimate conditions this superpipe will take additional flows from the Phase 4 Park, building and 20.0m right-of way areas. As mentioned in Section 4.2.1, it is planned to have the existing OGS STC 6000 within Existing Storm Network A provide the required quality control for the right of-way drainage. The ability for this existing unit to meet the treatment objectives will be assessed at the detailed design stage. This strategy is discussed further in **Section 4.2.4** and the Stormwater Management Report prepared by WSP under a separate cover.

In Phase 2 it is proposed to drain a 0.12ha area east of Building 'B' uncontrolled to Pine Creek. This area will also contain infiltration pits and the overall release rate flowing towards Pine Creek will be reduced in the proposed conditions. This strategy is discussed further in the Stormwater Management Report prepared by WSP under a separate cover.

The proposed Phase 2 storm servicing layout is shown on **Figure 4C - "Phase 2 – Storm Servicing"**. Following the recommended upgrades to Existing Storm Network B, there are no capacity concerns with the Existing Storm Network A and B's ability to convey the proposed flows. The Phase 2 storm sewer drainage plans and design sheets are included in **Appendix B**.

Additional details relating to the proposed Phase 2 storm servicing strategy and modelling are included in the Stormwater Management Report prepared by WSP under a separate cover.

#### 4.2.3 PHASE 3

Storm flows from Phase 3 will be collected by an internal storm drainage system and directed to a storage tank within Building 'C'. Specifications regarding the internal drainage system will be determined at the detailed design stage, but the system is to be fit with a jellyfish treatment unit to provide the required quality control for the impervious at grade areas within Phase 3. The storage tank will discharge the flows to a maximum allowable release rate of 29.08 L/s during the 100-year storm event and it will have a volume of 280m<sup>3</sup>. A storm connection is proposed from Building 'C' to into the 975 mm diameter superpipe installed in Phase 1. Preliminary sizing of the storm service connection suggests that it should be 300 mm diameter. However, the final size will be confirmed at the detailed design stage.

Since drainage from Phase 3 will be processed through the superpipe, it will ultimately be discharged to Existing Storm Network A. Following Phase 3 construction, the total release rate from the Phase 1 & 3 areas to Existing Storm Network A will be 84.06 L/s during the 100-year storm event. This controlled flow will be provided by a manhole fitted with a flow control device.

The proposed Phase 3 storm servicing layout is shown on **Figure 4D - "Phase 3 – Storm Servicing"**. There are no capacity concerns with Existing Storm Network A's ability to convey the proposed flows. This is supported by the Phase 3 storm sewer drainage plans and design sheets included in **Appendix B.** 

Additional details relating to the proposed Phase 3 storm servicing strategy and modelling are included in the Stormwater Management Report prepared by WSP under a separate cover.

#### 4.2.4 PHASE 4

Storm flows from Phase 4 (excluding the R.O.W and Park) will be collected by an internal storm drainage system and directed to a storage tank within Building 'D'. Specifications regarding the internal drainage system will be determined at the detailed design stage, but the system is to be fit with a jellyfish unit to provide the required quality control for the impervious at grade areas within Phase 4. The storage tank will discharge the flows to a maximum allowable release rate of 16.67 L / s during the 100-year storm event. The proposed tank will have a volume of 340.0 m<sup>3</sup>. A storm is proposed from Building 'D' to the proposed 1200 mm diameter superpipe within the proposed
20.0m right-of-way. Preliminary sizing of the storm service connection suggests that it should be 250 mm diameter. However, the final size will be confirmed at the detailed design stage.

Storm flows from the Phase 4 park will be captured and controlled by a subsurface storage system with a volume of 280 m<sup>3</sup>. The system will be designed to release flows to a maximum of 37.09 L/s during the 100-year storm event. The subsurface storage system will discharge into the proposed 1200 mm superpipe within the 20.0m right-of-way. Preliminary sizing suggests that the connection will be 250mm in diameter. However, final sizing will be confirmed at the detailed design stage.

Storm flows from the 20.0m right-of-way within Phase 4 will be routed through the 1200 mm superpipe within the 20.0m right-of-way. All storm flows captured from the 20.0m right-of-way areas (Phase 2 and 4), the Phase 4 building area, and the phase 4 park areas will all be conveyed into Existing Storm Network A via this superpipe. A manhole fitted with a flow control device will limit the release rate from these areas to 98.53L/s during the 100-year storm event.

Storm flows from the 17.0m right-of-way within Phase 4 will be routed through the proposed 975 mm superpipe within the 17.0m right-of-way. This 975 mm superpipe will process all of the storm drainage from Phase 1, Phase 3, and the Phase 4 17.0m right-of-way areas A manhole fitted with a flow control device will limit the release rate from these areas to 99.42L/s during the 100-year event.

As mentioned in Section 4.2.1, it is planned to have the existing OGS STC 6000 within Existing Storm Network A provide the required quality control for the right of-way drainage. The ability for this existing unit to meet the treatment objectives will be assessed at the detailed design stage.

The proposed Phase 4 storm servicing layout is shown on **Figure 4E - "Phase 4 – Storm Servicing"**. There are no capacity concerns with Existing Storm Network A's ability to convey the proposed flows. This is supported by the Phase 4 storm sewer drainage plans and design sheets included in **Appendix B.** 

Additional details relating to the proposed Phase 4 storm servicing strategy and modelling are included in the Stormwater Management Report prepared by WSP under a separate cover.

### 4.2.5 PHASE 5

Storm flows within the Phase 5 building area and driveway areas immediately to the south and west of the building will be collected by an internal storm drainage system and directed to a storage tank within Building 'D'. Specifications regarding the internal drainage system will be determined at the detailed design stage but the system is to be fit with a jellyfish treatment unit to provide the required quality control for these impervious at grade areas within Phase 5. The storage tank will discharge the flows to a maximum release rate of 88.72 L / s during the 100-year storm event and will have a storage volume of 680 m<sup>3</sup>. A storm connection is proposed from the Building 'E' storm tank to Existing Storm Network B. Preliminary sizing of the storm connections suggest that it should be 300 mm diameter. However, the final size will be confirmed at the detailed design stage.

Storm flows within Phase 5 landscape area located east of the headwall, and south of the proposed driveway are proposed to flow uncontrolled to Frenchman's Bay. For the section of Phase 5 private

road that is located west of the headwall, the intention is to match the existing condition and have this area drain to the headwall via Existing Storm Network C.

The proposed Phase 5 storm servicing layout is shown on **Figure 4F - "Phase 5 – Storm Servicing".** There are no capacity concerns with Existing Storm Network A's ability to convey the proposed flows. This is supported by the Phase 5 storm sewer drainage plans and design sheets included in **Appendix B.** Since the intention is to match the existing condition west of the headwall and preserve all of Existing Storm Network C, this segment of the network was excluded from the analysis.

Following the implementation of the proposed stormwater management measures, the total release rate from the site will be reduced in the post-development condition. Additional details relating to the proposed storm servicing strategy and modelling are included in the Stormwater Management Report prepared by WSP under a separate cover.

## 4.3 MAJOR STORM DRAINAGE SYSTEM

The major storm system is a conveyance system for flows in excess of the minor system flows. Stormwater run-off from events up to and including the 100 - year storm event will be contained on - site and released at a controlled rate within the allowable post-development limits to the minor storm system. For major storm events exceeding the 100 - year storm, overland flow routes will be designed to direct excess flows to the existing culvert at the south end of the site via the on - site roadways.

For the development of the site, the grading design will be prepared such that the surface (i.e., roads, walkways and landscaped areas) grades will direct surface drainage away from the building to approved outlets. The proposed grading of the subject site will ensure that existing grade elevations at the time of construction will be met along the property limits. The plumbing system for each building will be coordinated with the mechanical consultant to ensure that they are designed to convey a 100-year run-off from the development. For major storm events exceeding the 100 - year storm and the capacity of the proposed storage tanks, an overflow will be designed to direct excess flows to grade and ultimately to the existing box culvert at the south end of the site via the on - site roadways. Refer to **Appendix C** for the preliminary site grading plan.













# 5 SITE GRADING

## 5.1 EXISTING CONDITIONS

In the existing condition the site falls from north to south. Runoff is conveyed away from the existing buildings to a series of on – site drains. In the emergency situation where runoff cannot be captured, it is conveyed to the existing box culvert located at the south end of the site via the on - site driveways.

## 5.2 PROPOSED CONDITIONS

The proposed grading design for the new development will direct storm drainage to the on - site collection points. Since the site grading will be phased, the objective is to capture as much runoff within each phase as possible and prevent overland flow to the existing property. However, since the existing site falls from north to south, the emergency overland flow route for the major storm events must go through the existing site towards the box culvert located at the south end of the site. This flow will be via the on - site driveways and R.O.W's and it will ensure that drainage is diverted away from all of the buildings.

The proposed grading plans for each phase are included in **Appendix C**. In summary the plans consider the following:

- Proposed grades along all boundaries (phase and site) are to match to existing so that there is no impact to the adjacent properties;
- Minimize disruption to all existing municipal rights-of-way containing existing utilities and services;
- Promote drainage into the minor sewer systems;
- Grade the lands to direct overland flow away from the proposed structures;
- Create high points within the development area to direct flows towards drainage inlets with a maximum proposed ponding depth of 0.30 m; and
- Ensure that minimum and maximum grades conform to AODA and City of Pickering standards.

# 6 EROSION AND SEDIMENT CONTROL

Temporary Erosion and Sediment Control must be provided onsite during construction to prevent sediment runoff to the neighbouring developments and municipal roads. Fencing and hoarding will be erected surrounding the perimeter of each phase, and mud mats will be required at site access points. In addition, catchbasins that are to remain in close proximity to the construction zones will be protected with geotextile fabric. All Erosion and Sediment Control Best Management Practices shall be designed, constructed and maintained for the duration of construction. The preliminary Erosion and Sediment Control Plans for each phase are outlined in **Appendix D**.

# 7 CONCLUSIONS

## 7.1 WATER

The proposed development will rely on the future 300mm diameter watermain in Walnut Lane for water servicing. At this time. it is WSP's understanding that this watermain will have the capacity to service the proposed development. Buildings within the proposed development will either have service connections directly to the watermain in Walnut Lane, or to the proposed extension of the watermain within the future right-of-ways within the site. Each building's water service connection will at minimum consist of one domestic connection and one fire connection. If the height of any building exceeds 84 m, a secondary fire connection will be provided as per Ontario's building code requirements. The service connection sizing will be coordinated with the Region of Durham and the mechanical engineering consultant at the detailed design stage. The connections will be made in accordance with Region of Durham standards.

## 7.2 SANITARY

Sanitary flows from the proposed development will be conveyed to the future sanitary sewer that will be installed in Walnut Lane or the existing system on the west side of the site. These local sewer systems ultimately discharge to the existing 1050 mm diameter trunk sanitary sewer that runs along the south side of the site. WSP does not have capacity concerns with the local sewers leading to the trunk.

For a nearby development, WSP was informed by the Region of Durham that the capacity for the trunk sewer was to be allocated on a first come first serve basis at the time of signing a development agreement. It is WSP's understanding that there are currently other ongoing developments within the service area and as such the Region of Durham is in the process of confirming capacity limitations through use of ongoing flow monitoring. This will form the basis of determining any potential upgrades that will be required as development continues to proceed within the existing sanitary drainage boundary of Pickering City Centre area and beyond. Thus, it is assumed that at the time of the proposed redevelopment of the subject lands, there will be capacity in the trunk sewer to accept the proposed sanitary flows.

### 7.3 STORM

All storm flows from the site up to the 100-year event will ultimately be released at the allowable release rate to the 1.83 m x 1.83 m box culvert located at the south end of the site. On site quantity control chambers and superpipes will be used to provide the necessary quantity controls throughout the site.

Storm flows from Phases 1, 3, and 4 the proposed right-of-ways will be conveyed into Existing Storm Network A on the west side of the site. Preliminary sizing suggests that Existing Storm Network A has enough capacity to convey the flows to the box culvert in each of the proposed conditions.

Storm flows from Phase 2 (excluding the right-of-way), and flows within Phase 5 building and driveway areas that are east of the headwall will be conveyed into Existing Storm Network B that runs along the south side of the site. Preliminary sizing suggests that minor pipe upgrades to Existing Storm Network B will be required to accommodate the proposed flows.

Storm flows within Phase 5 that are tributary to west of the headwall will flow to the box culvert via Existing Storm Network C (southwest side of the site) matching the existing condition.

There are two proposed uncontrolled drainage areas on-site. In Phase 2 it is proposed to drain a 0.12ha area east of Building 'B' uncontrolled to Pine Creek. This area will contain infiltration pits and the overall release rate flowing towards Pine Creek from this area will be reduced in the proposed conditions. In Phase 5 it is proposed to drain the area south of the proposed driveway on the south side of the Building 'E' uncontrolled to Frenchman's Bay.

Following the implementation of the proposed stormwater management measures, the total release rate from the site will be reduced in the post-development condition. Additional details relating to the proposed storm servicing strategy and modelling are included in the Stormwater Management Report prepared by WSP under a separate cover.





#### PHASE 1

Project: Job No.:

# 1101A, 1105, and 1163 KINGSTON ROAD 221-12931

Building	Unit Count/ GFA (ha)	Site Area (ha)	Occupancy Rate	Equivalent Population	Per Capita Flow	Average Daily Flow (L/s)	Peaking Factor	Peak Flow (L/s)
			Building	A				
Residential	582			1157	364 L/cap/day	4.87	3.76	18.32
BACH+1B	344		1.5 ppu	516				
2B	192		2.5 ppu	480				
3B	46		3.5 ppu	161				
Retail	0.48				180000 L/ha/day	0.99	1.00	0.99
Infiltration		1.13				0.29		0.29
Subtotal				1157		6.16		19.61
Phase 1 Residential Subtotal				1157	364 L/cap/day	4.87	3.76	18.32
Phase 1 Retail/Daycare Subtotal	0.48				180000 L/ha/day	0.99	1.00	0.99
Phase 1 Infiltration		1.13				0.29		0.29
PHASE 1 TOTAL						6.16		19.61

Notes:

#### PHASE 2

Project: Job No.:

# 1101A, 1105, and 1163 KINGSTON ROAD 221-12931

Building	Unit Count/ GFA (ha)	Site Area (ha)	Occupancy Rate	Equivalent Population	Per Capita Flow	Average Daily Flow (L/s)	Peaking Factor	Peak Flow (L/s)
			Building	В				
Residential	1259			2507	364 L/cap/day	10.56	3.51	37.05
BACH+1B	742		1.5 ppu	1113				
2B	416		2.5 ppu	1040				
3B	101		3.5 ppu	354				
Retail	0.00				180000 L/ha/day	0.00	1.00	0.00
Infiltration		1.39				0.36		0.36
Subtotal				2507		10.92		37.41
Phase 2 Residential Subtotal				2507	364 L/cap/day	10.56	3.51	37.05
Phase 2 Retail Subtotal	0.00				180000 L/ha/day	0.00	1.00	0.00
Phase 2 Infiltration		1.39				0.36		0.36
PHASE 2 TOTAL						10.92		37.41

Notes:

#### PHASE 3

Project: Job No.:

# 1101A, 1105, and 1163 KINGSTON ROAD 221-12931

Building	Unit Count/ GFA (ha)	Site Area (ha)	Occupancy Rate	Equivalent Population	Per Capita Flow	Average Daily Flow (L/s)	Peaking Factor	Peak Flow (L/s)
			Building	C				
Residential	598			1191	364 L/cap/day	5.02	3.75	18.82
BACH+1B	353		1.5 ppu	530				
2B	197		2.5 ppu	493				
3B	48		3.5 ppu	168				
Retail	0.00				180000 L/ha/day	0.00	1.00	0.00
Infiltration		0.60				0.16		0.16
Subtotal				1191		5.17		18.97
Phase 3 Residential Subtotal				1191	364 L/cap/day	5.02	3.75	18.82
Phase 3 Retail Subtotal	0.00				180000 L/ha/day	0.00	1.00	0.00
Phase 3 Infiltration		0.60				0.16		0.16
PHASE 3 TOTAL						5.17		18.97

Notes:

#### PHASE 4

Project: Job No.:

# 1101A, 1105, and 1163 KINGSTON ROAD 221-12931

Building	Unit Count/ GFA (ha)	Site Area (ha)	Occupancy Rate	Equivalent Population	Per Capita Flow	Average Daily Flow (L/s)	Peaking Factor	Peak Flow (L/s)
			Building	D				
Residential	852			1696	364 L/cap/day	7.15	3.64	26.01
BACH+1B	503		1.5 ppu	755				
2B	281		2.5 ppu	703				
3B	68		3.5 ppu	238				
Retail	0.12				180000 L/ha/day	0.26	1.00	0.26
Infiltration		2.16				0.56		0.56
Subtotal				1696		7.97		26.83
Phase 4 Residential Subtotal				1696	364 L/cap/day	7.15	3.64	26.01
Phase 4 Retail Subtotal	0.12				180000 L/ha/day	0.26	1.00	0.26
Phase 4 Infiltration		2.16				0.56		0.56
PHASE 4 TOTAL						7.97		26.83

Notes:

#### PHASE 5

Project: Job No.:

# 1101A, 1105, and 1163 KINGSTON ROAD 221-12931

Building	Unit Count/ GFA (ha)	Site Area (ha)	Occupancy Rate	Equivalent Population	Per Capita Flow	Average Daily Flow (L/s)	Peaking Factor	Peak Flow (L/s)
			Building	ΙE				
Residential	1973			3927	364 L/cap/day	16.54	3.34	55.27
BACH+1B	1164		1.5 ppu	1746				
2B	651		2.5 ppu	1628				
3B	158		3.5 ppu	553				
Retail	0.06				180000 L/ha/day	0.12	1.00	0.12
Infiltration		2.47				0.64		0.64
Subtotal				3927		17.30		56.03
Phase 4 Residential Subtotal				3927	364 L/cap/day	16.54	3.34	55.27
Phase 4 Retail Subtotal	0.06				180000 L/ha/day	0.12	1.00	0.12
Phase 4 Infiltration		2.47				0.64		0.64
PHASE 4 TOTAL						17.30		56.03

Notes:



# THE REGIONAL MUNICIPALITY OF DURHAM SANITARY SEWER DESIGN SHEET

F	PROJECT :         1101A, 1105, and 1163 KINGSTC           JOB No. :         221-12931-00           FROM :         Residential						ROAD Phase 1							DESIGNED CHECKED DATE :	) BY: BY :	<u>ZB</u> <u>KK</u> 2025-01-15					
			Residential			C	ommerc	ial	Industrial	Institutional			Flow in L/	s			Proposed Sewer				
ſ	MH.	Gross	Population	Population	Peak	Lot	Floor	Floor	Lot	Lot	Res.	flow	Comm.	Indus.	Inst.	Total	Actual	Slope	Capacity	Velocity	
1	No.	area	density		flow	area	space	area	area	(ha)	Infil*	Sewage				flow	Pipe	%	in	in	Load
		(ha)			factor	(ha)	Index	(ha)			L/S 0.26	L/S 0.0042	L/S 2.08	L/S 1.04	L/S 1.30	L/s	size mm		L/s	m/s	%
SAN	NMH1A	1.13		1157				0.48													
S	SAN MH2A	1.13		1157	3.76			0.48			0.29	18.32	0.99	0.00	0.00	19.61	250	2.00	84.10	1.71	23%
																	۱				
SAN	NMH2A	0.00		0				0.00													
F	FUT. SAN MH-SA1	1.13		1157	3.76			0.48			0.29	18.32	0.99	0.00	0.00	19.61	375	0.50	123.98	1.12	16%

Notes:

<u>ZB</u>	
<u>KK</u>	
2025-01-15	)

# THE REGIONAL MUNICIPALITY OF DURHAM SANITARY SEWER DESIGN SHEET

	PROJECT : JOB No. : FROM :	KINGSTON F	N ROAD Phase 2								DESIGNE CHECKE DATE :	ED BY: D BY :	<u>ZB</u> <u>KK</u> 2025-01-15								
			Residential			C	ommerc	cial	Industrial	Institutional	Flow in L/s			s				Proposed	d Sewer		
	MH.	Gross	Population	Population	Peak	Lot	Floor	Floor	Lot	Lot	Res.	flow	Comm.	Indus.	Inst.	Total	Actual	Slope	Capacity	Velocity	
	No.	area	density		flow	area	space	area	area	(ha)	Infil*	Sewage				flow	Pipe	%	in	in	Load
		(ha)			factor	(ha)	Index	(ha)			L/S	L/S	L/S	L/S	L/S	L/s	size		L/s	m/s	%
											0.26	0.0042	2.08	1.04	1.30		mm				
SAI	N MH5A	1.39		2507				0.00													
	SAN MH4A	1.39		2507	3.51			0.00			0.36	37.05	0.00	0.00	0.00	37.41	200	2.00	46.38	1.48	81%
SA	N MH4A	0.00		0				0.00													
	SAN MH6A	1.39		2507	3.51			0.00			0.36	37.05	0.00	0.00	0.00	37.41	300	2.00	136.76	1.93	27%
SAI	N MH6A	0.00		0				0.00													
	FUT. SAN MH-SA13	1.39		2507	3.51			0.00			0.36	37.05	0.00	0.00	0.00	37.41	300	2.00	136.76	1.93	27%
lataa																					

Notes:

Occupancy rates, per capita flows and peaking factor are as per the Region of Durham Design Specifications For Sanitary Sewers
 Unit Counts and Floor Areas from drawings prepared by Turner Fleisher,

q

<u>ZB</u>	
<u>KK</u>	
<u>2025-01-15</u>	

#### THE REGIONAL MUNICIPALITY OF DURHAM SANITARY SEWER DESIGN SHEET

1101A, 1105, and 1163 KINGSTON ROAD Phase 3

PROJECT :

DESIGNED BY: CHECKED BY :

JOB No.	

.:

	FROM :													DATE:		2025-01-15					
			Residential			C	ommerc	ial	Industrial	Institutional			Flow in L	/s				Proposed	Sewer		
	MH. No.	Gross area	Population density	Population	Peak flow	Lot area	Floor space	Floor area	Lot area	Lot (ha)	Res. Infil*	flow Sewage	Comm.	Indus.	Inst.	Total flow	Actual Pipe	Slope %	Capacity in	Velocity in	Load
		(ha)			factor	(ha)	Index	(ha)			L/S 0.26	L/S 0.0042	L/S 2.08	L/S 1.04	L/S 1.30	L/s	size mm		L/s	m/s	%
BL	.DG C	0.60		1191				0.00													
	SAN MH7A	0.60		1191	3.75			0.00			0.16	18.82	0.00	0.00	0.00	18.97	200	2.00	46.38	1.48	41%
SA	N MH7A	0		0				0.00													
	EX. SAN MH#8	0.60		1191	3.75			0.00			0.16	18.82	0.00	0.00	0.00	18.97	200	2.00	46.38	1.48	41%
ЕX	<u>(, SAN MH#8</u>	0		0				0.09 (4)													
	EX. SAN MH#7	0.60		1191	3.75			0.09			0.16	18.82	0.19	0.00	0.00	19.16	200	1.40	38.81	1.24	49%
EX	<u>(, SAN MH#7</u>	0		0				1.09 (4)													
	EX. SAN MH#6	0.60		1191	3.75			1.18			0.16	18.82	2.46	0.00	0.00	21.43	200	1.40	38.81	1.24	55%
EX	<u>(, SAN MH#6</u>	0		0				0.00													
	EX. SAN MH#5	0.60		1191	3.75			1.18			0.16	18.82	2.46	0.00	0.00	21.43	200	1.12	34.71	1.10	62%
EX	<u>(, SAN MH#5</u>	0		0				0.00													
	EX. SAN MH#4 (TRUNK)	0.60		1191	3.75			1.18			0.16	18.82	2.46	0.00	0.00	21.43	200	3.10	57.75	1.84	37%

Notes:

Occupancy rates, per capita flows and peaking factor are as per the Region of Durham Design Specifications For Sanitary Sewers
 Unit Counts and Floor Areas from drawings prepared by Turner Fleisher

<u>221-12931-00</u>

3. Infiltration considered for entire Site Area to account for any future changes in plan

4. Existing Commercial area as measured using Google Earth.

<u>ZB</u>	
<u>KK</u>	
<u>2025-01-15</u>	

# THE REGIONAL MUNICIPALITY OF DURHAM SANITARY SEWER DESIGN SHEET

	PROJECT : JOB No. : FROM :		<u>1101A, 110</u> 221-12931	<u>05, and 1163 k -00</u>	(INGSTON R	OAD		Phase 4-5			DESIGNED BY: <u>ZB</u> CHECKED BY: <u>KK</u> DATE: <u>2025-01-15</u>													
			Residentia			С	ommer	cial	Industrial	Institutional			Flow in L	/s				Proposed	d Sewer					
	MH. No.	Gross area (ha)	Population density	Population	Peak flow factor	Lot area (ha)	Floor space Index	Floor area (ha)	Lot area	Lot (ha)	Res. Infil* L/S 0.26	flow Sewage L/S 0.0042	Comm. L/S 2.08	Indus. L/S 1.04	Inst. L/S 1.30	Total flow L/s	Actual Pipe size mm	Slope %	Capacity in L/s	Velocity in m/s	Load %			
BL	DG D	2.16		1696				0.12																
	SAN MH3A	2.16		1696	3.64			0.12			0.56	26.01	0.26	0.00	0.00	26.83	200	2.00	46.38	1.48	58%			
BL	DG E	2.47		3927				0.06																
	SAN MH3A	2.47		3927	3.34			0.06			0.64	55.27	0.12	0.00	0.00	56.03	250	2.00	84.10	1.71	67%			
SA	N MH3A	0.00		0				0.00																
	SAN MH4A	4.63		5623	3.20			0.18			1.20	75.74	0.38	0.00	0.00	77.32	300	2.00	136.76	1.93	57%			
SA	N MH5A	1.39		2507				0.00																
	SAN MH4A	1.39		2507	3.51			0.00			0.36	37.05	0.00	0.00	0.00	37.41	200	2.00	46.38	1.48	81%			
SA	N MH4A	0.00		0				0.00																
	SAN MH6A	6.02		8130	3.04			0.18			1.56	104.24	0.38	0.00	0.00	106.18	300	2.00	136.76	1.93	78%			
SA	N MH6A	0.00		0				0.00																
	FUT. SAN MH-SA13	6.02		8130	3.04			0.18			1.56	104.24	0.38	0.00	0.00	106.18	300	2.00	136.76	1.93	78%			

Notes:

Occupancy rates, per capita flows and peaking factor are as per the Region of Durham Design Specifications For Sanitary Sewers
 Unit Counts and Floor Areas from drawings prepared by Turner Fleisher

3. Infiltration considered for entire Site Area to account for any future changes in plan



# B STORM FLOW CALCULATIONS AND DESIGN SHEETS







221-12931





![](_page_64_Figure_2.jpeg)

#### STORM SEWER DESIGN SHEET 1101A, 1105, and 1163 KINGSTON ROAD - PHASE 1

#### City of Pickering

STREET	FROM M.H.	то м.н.	CATCHMENT ID.	ha AREA Mixed/Use	R RUNOFF COEFFICIEN	2.78 NI A.R.	ACCUM 2.78 A.R.	T <sub>c</sub> ( MIN )	i Q1 RAINFALL PEAK UNCONTI INTENSITY (L/ (mm/hr)	<sup>00</sup> ROLLED FLOV S)	Q <sub>CON</sub> CONTROLLED FLOW (L/S)	Q <sub>TOTAL</sub> Q <sub>100</sub> + Q <sub>CON</sub> (L/S)	PIPE DIA. ( mm )	SLOPE (%)	LENGTH (m)	CAPACITY (L/s)	VELOCITY (m/s)	TIME IN SECTION (min.)	TOTAL TIME ( min. )	LOAD %	COMMENTS
					•				EA	ST SITE											
Phase 1	PHASE 1 SWM TANK	STM MH 8	PH1	0.93	0.77	-	-	10.00	186.69 -		16.93	16.93	300	0.50	9.0	68.38	0.97	0.16	10.16	25%	- PH1 CONTROLLED RELEASE RATE THROUGH SWM TANK
Phase 1	STM MH 7	STM MH 8	ROW 1	0.20	0.88	-	-	10.00	186.69 -		54.98	54.98	975	-	21.5	-	-	-	-	-	RELEASE RATE. REFER TO SWM REPORT FOR DYNAMUC MODELLING
Phase 1	STM MH 8	STM MH 10	-	-	-	-	-	10.00	186.69 -		-	54.98	975	-	38.5	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
Phase 1	STM MH 10	STM MH 1	-	-	-	-	-	10.00	186.69 -		-	54.98	975	-	5.4	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
Phase 3	STM MH 1	EX STM MH 10	EX. 6	0.60	1.00	-	-	10.00	186.69 -		34.50 (1)	89.48	975	-	17.2	-	-	-	-	-	- EXISTING RELEASE RATE ASSUMED TO BE EQUAL TO THE ALLOWABLE RELEASE RATE FOR PHASE 3. NOTE AS PER TOPOGRAPHIC SURVEY, THIS AREA IS CONTROLLED BY AN ORIFICE ON THE SOUTH EAST CORNER OF STM MH 14. AT THIS TIME THE ORIGINAL DESIGN DETAILS FOR THE EXISTING STORMWATER MANAGEMENT SYSTEM WITHIN THE PHASE 3 LANDS ARE UNKNOWN. HOWEVER, SINCE THE SIZEING OF THE DOWNSTREAM SYSTEM IS NOT BEING REDUCED, THERE ARE NO CAPACITY CONCERNS WITH THE
Existing Development	EX STM MH 29	EX STM MH 10	EX. 1	1.69	1.00			10.00	186.69 -		90.89	90.89	150	-	10.0	-	-	-	-	-	Q=CA (2gh)^0.5 WHERE: C = 0.8 (orifice tube), A = 0.0177m^2 (150 mm DIA. ORIFICE) , g = 9.81 m/s^2, h= 85.10 (HIGH WATER LEVEL PER a.m candaras associates inc STORMWATER MANAGEMENT REPORT DATED JANUARY, 2015) - 83.00 = 2.10m Q=0.8°0.0177m^22°(2°9.81m/s^2°2.10m) Q=0.09089m^3/s Q= 90.89 L/s
Existing Development	EX STM MH 10	EX STM MH 9	-	-	-	-	-	10.00	186.69 -		-	180.37	600	0.68	46.8	506.33	1.79	0.44	10.44	36%	CONSERVATIVELY ASSUMED THAT PEAR FLOW FROM ALL UPSTREAM TRIBUTARIES OCCURS TOGETHER. PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY J.D BARNES DATED FEB 2. 2023
Existing Development	EX STM MH 9	EX STM MH 8 (OGS)	-	-	-	-	-	10.44	182.54 -		-	180.37	600	0.60	9.4	475.61	1.68	0.09	10.53	38%	- PIPE SLOPE AS PER a.m candaras associates inc. "SITE SERVICING & STORM WATER MANAGEMENT PLAN" DATED May 21, 2010. DESIGN INFO USED BECAUSE SURVEY CONTAINS CONFLICTING INFORMATION THROUGH THIS SEGMENT. SLOPE TO BE VERIFIED DURING DETAILED DESIGN.
Existing Development	EX STM MH 8 (OGS)	EX STM MH 7	-	-	-	-	-	10.53	181.68 -		-	180.37	600	0.60	7.4	475.61	1.68	0.07	10.60	38%	- PIPE SLOPE AS PER a.m candaras associates inc. "SITE SERVICING & STORM WATER MANAGEMENT PLAN" DATED May 21, 2010. DESIGN INFO USED BECAUSE SURVEY CONTAINS CONFLICTING INFORMATION THROUGH THIS SEGMENT. SLOPE TO BE VERIFIED DURING DETAILED DESIGN.
Existing Development	EX STM MH7	EX STM MH 6	-	-	-	-	-	10.60	181.00 -		-	180.37	600	0.39	51.1	383.45	1.36	0.63	11.23	47%	- PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023 - UPSIZE EX. 600mm DIA. SEWER TO 675mm DIA. TO ACCOMMODATE FUTURE PHASES
Existing Development	EX STM MH 6	Headwall	-	-	-	-	-	11.23	175.45		-	180.37	675	0.39	35.6	524.95	1.47	0.40	11.63	34%	- PIPE SLOPE UNKNOWN, ASSUMED SAME SLOPE AS UPSTREAM PIPE. SLOPE TO BE VERIFIED DURING DETAILED DESIGN.

\*i<sub>100</sub>=2096.425/(T<sub>c</sub>+6.485)^0.863

RUNOFF COEFFICIENTS

0.25 0.50 SOFT LANDSCAPING/PARK

GREEN ROOF

0.95 IMPERVIOUS AT GRADE 0.95 IMPERVIOUS ROOF

0.90 0.90

NOTES 1) EXISTING RELEASE RATE ASSUMED TO BE EQUAL TO THE ALLOWABLE RELEASE RATE FOR PHASE 3. REFER TO COMMENTS IN THE LAST COLUMN OF THE DESIGN SHEET.

PREPARED BY:	Z.B.
CHECKED BY:	К.К.
DATE:	15-Jan-25
LAST PRINTED:	15-Jan-25
FILE No	221-12931

No. OF SHEETS

										STORM SEWER	DESIGN SHEET										PREPARED BY: Z.B. CHECKED BY: K.K.
WSP CANADA INC.									1101A,	1105, and 1163 KIN	IGSTON ROAD - P	PHASE 2									DATE: 15-Jan-25
										City of P	ickering										FILE No 221-12931
			CATCHMENT	ha		2.79	ACCUM	Ŧ			0		DIDE		1		1	TIME IN	TOTAL		
STREET	FROM	то	ID.	AREA	RUNOFF COEFFICIEI	2.76 NI A.R.	2.78	10		PEAK UNCONTROLLED FLOW	CONTROLLED FLOW	Q <sub>100</sub> + Q <sub>CON</sub>	DIA.	SLOPE	LENGTH	CAPACITY	VELOCITY	SECTION	TIME	LOAD	COMMENTS
	M.H.	M.H.		Mixed/Use			AR.	(MIN)	(mm/hr)		(L/S)	(L/S)	(mm)	(%)	(m)	(L/s)	(m/s)	( min. )	( min. )	76	
Phase 1	PHASE 1 SWM TANK	STM MH 8	PH1	0.93	0.77	-	-	10.00	186.69	-	16.93	16.93	300	0.50	9.0	68.38	0.97	0.16	10.16	25%	- PH1 CONTROLLED RELEASE RATE THROUGH SWM TANK
Phase 1	STM MH 7	STM MH 8	ROW 1	0.20	0.88	-	-	10.00	186.69	-	54.98	54.98	975	-	21.5	-	-	-	-	-	- PH1 CONTROLLED RELEASE RATE THROUGH SUPERPIPE + PH1 ROW RELEASE RATE. REFER TO SWM REPORT FOR DYNAMUC MODELLING
Phase 1	STM MH 9	STM MH 10						10.00	196.60			54.99	075		29.5						
Phase 1	STM MH 10	STM MH 1	-				_	10.00	186.69			54.98	975		5.4	_					REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
Thuse T	CTM MIT TO	UTIM MITT	-		-	-	-	10.00	100.00	-	-	04.00	515	-	0.4	-	-	-	-	-	EXISTING RELEASE RATE ASSUMED TO BE FOUND TO THE ALLOWARDE
																					RELEASE RATE FOR PHASE 3. NOTE AS PER TOPOGRAPHIC SURVEY, THIS AREA IS CONTROLLED BY AN ORIFICE ON THE SOUTH EAST CORNER OF
Phase 3	STM MH 1	EX STM MH 10	EX. 6	0.60	1.00	-	-	10.00	186.69		34.50 (1)	89.48	975	-	17.2	-	-	-	-	-	STM MH 14. AT THIS TIME THE ORIGINAL DESIGN DETAILS FOR THE EXISTING STORMWATER MANAGEMENT SYSTEM WITHIN THE PHASE 3
																					DOWNSTREAM SYSTEM IS NOT BEING REDUCED, THERE ARE NO CAPACITY CONCERNS WITH THE EXISTING SYSTEM
																					WHERE: C = 0.8 (orifice tube), A = 0.0177m <sup>4</sup> 2 (150 mm DIA. ORIFICE), g = 9.81 m/s <sup>4</sup> 2, h= 85.10 (HIGH WATER LEVEL PER a.m candaras associates inc
Existing Development	EX STM MH 29	EX STM MH 10	EX. 1	1.69	1.00	-	-	10.00	186.69	-	90.89	90.89	150	-	10.0	-	-	-	-	-	STORMWATER MANAGEMENT REPORT DATED JANUARY, 2015) - 83.00 = 2.10m
																					Q=0.8*0.0177m^2*(2*9.81m/s*2*2.10m) Q=0.09089m*3/s
																					Q= 90.89 L/s - CONSERVATIVELY ASSUMED THAT PEAK FLOW FROM ALL UPSTREAM
Existing Development	EX STM MH 10	EX STM MH 9	-	-	-	-	•	10.00	186.69		-	180.37	600	0.68	46.8	506.33	1.79	0.44	10.44	36%	TRIBUTARIES OCCURS TOGETHER. PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY J.D BARNES DATED EFB 0.2022
																					FED 2, 2023
PH2 ROW	STM MH 12	STM MH 3	ROW 2	0.15	0.85	-	-	10.00	186.69	-	8.70	8.70	1200	-	11.3	-	-	-	-	-	- PH2 ROW CONTROLLED RELEASE RATE THROUGH SUPERPIPE
PH4 ROW	STM MH 3	STM MH 4	-	-	-	-	-	10.00	186.69	-	-	8.70	1200	-	98.5	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
PH4 ROW	STM MH 4	STM MH 5	-	-	-	-	-	10.00	186.69	-	-	8.70	1200	-	114.0	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
PH4 ROW	STM MH 5	STM MH 6	-	-	-	-	-	10.00	186.69	-	-	8.70	1200	-	16.2	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
PH4 ROW	STM MH 6	STM MH 11	-		-	-	-	10.00	186.69	-	-	8.70	1200	-	6.3	-	-	-	-		- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
																					EXISTING 600 DIA STM TO REMAIN
PH4 ROW	STM MH 11	STM MH 9	-	-	-	-	•	10.00	186.69		-	189.07	600	0.60	10.4	475.61	1.68	0.10	10.10	40%	- PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023
																					- PIPE SLOPE AS PER a.m candaras associates inc. "SITE SERVICING & STORM
Existing Development	EX STM MH 9	EX STM MH 8 (OGS)	-	-	-	-	-	10.44	182.54	-	-	189.07	600	0.60	9.4	475.61	1.68	0.09	10.53	40%	WATER MANAGEMENT PLAN* DATED May 21, 2010. DESIGN INFO USED BECAUSE SURVEY CONTAINS CONFLICTING INFORMATION THROUGH THIS
																					SEGMENT. SLOPE TO BE VERIFIED DURING DETAILED DESIGN PIPE SLOPE AS PER a.m candaras associates inc. "SITE SERVICING & STORM
Existing Development	EX STM MH 8 (OGS)	EX STM MH 7	-	-	-	-	-	10.53	181.68	-	-	189.07	600	0.60	7.4	475.61	1.68	0.07	10.60	40%	WATER MANAGEMENT PLAN" DATED May 21, 2010. DESIGN INFO USED BECAUSE SURVEY CONTAINS CONFLICTING INFORMATION THROUGH THIS
																					SEGMENT. SLOPE TO BE VERIFIED DURING DETAILED DESIGN.
Existing Development	EX STM MH7	EX STM MH 6	-		-	-		10.60	181.00	-	-	189.07	600	0.39	51.1	383.45	1.36	0.63	11.23	49%	SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023 - UPSIZE EX, 600mm DIA, SEWER TO 675mm DIA. TO ACCOMMODATE FUTURE
																					PHASES
Existing Development	EX STM MH 6	Headwall	-	-	-	-	-	11.23	175.45	-	-	189.07	675	0.39	35.6	524.95	1.47	0.40	11.63	36%	- PIPE SLOPE UNKNOWN, ASSUMED SAME SLOPE AS UPSTREAM PIPE. SLOPE TO BE VERIFIED DURING DETAILED DESIGN.
Phase 2	PHASE 2 SWM TANK	STM MH 2	PH 2	1.12	0.71	-		10.00	186.69	- SOUTH SITE	63.82	63.82	300	2.00	10.2	136.76	1.93	0.09	10.09	47%	- PH2 ALLOWABLE REALEASE RATE REFER TO SWM REPORT FOR DETAILS
Phase 2	STM MH 2	EX STM MH 23	-	-	-	-		10.00	186.69		-	63.82	300	1.00	20.2	96.70	1.37	0.25	10.25	66%	
	EX STM MH 20	EX STM MH 23	EX. 2	0.29	0.95	0.77	0.77	10.00	186.69	142.99	-	142.99	525	0.35	31.2	254.43	1.18	0.44	10.44	56%	- REPER TO EX. 2 IN PHASE 2 STORM DRAINAGE PLAN - PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY J.D BARNES DATED FEB 2. 2023
																					CONSERVATIVELY ASSUMED THAT PEAK FLOW FROM PHASE 2 SWM TANK     OCCURS ALONGSIDE UNCONTROLLED PEAK FLOW     PECEP TO EX 3 IN PHASE 2 STOPM DEAINAGE PLAN
Existing Development	EX STM MH 23	EX STM MH 19	EX. 3	0.10	0.64	0.18	0.94	10.44	182.47	172.22	-	236.04	600	0.29	88.8	330.66	1.17	1.26	11.71	71%	- PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE
																					SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023
Existing Development	EX BUILDING	EX STM MH 19	EX. 4			-	-	10.00	186.69	-	43.40	43.40	250	2.00	21.0	84.10	1.71	0.20	10.20	52%	REFER TO EX. 4 IN PHASE 2 STORM DRAINAGE PLAN.     CONTROLLED RELEASE RATE AS PER a.m. candaras associates inc. "SITE     STORE AS TORENATED NAMED NAME
																					SERVICING & STORM WATER MANAGEMENT PLAN DATED May 21, 2010.
Evistics Development			<b>F</b> Y <b>F</b>	0.04	0.70	0.00	4.50	44 74	474 47	000.00		075 45	750	0.00		500.04	4.04	4.45	40.00	700/	and EX BUILDING OCCURS ALONGSIDE UNCONTROLLED PEAK FLOW - REFER TO EX. 5 IN PHASE 2 STORM DRAINAGE PLAN.
Existing Development	EX STM MH 19	EX STM MH 18	EX. 5	0.31	0.72	0.62	1.50	11.71	171.47	208.23	-	3/5.45	750	0.23	83.3	533.91	1.21	1.15	12.80	70%	- UPGRADE EX. 525mm DIA. SEWER TO 750mm DIA. - PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE
																					SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023
Existing Development	EX STM MH 18	EX STM MH 17	_				1 56	12.86	162.65	254 43	_	361 65	750	0.30	13.3	609 77	1 38	0.16	13.02	50%	CONSERVATIVELY ASSUMED THAT PEAK FLOW FROM PHASE 2 SWM TANK OCCURS ALONGSIDE UNCONTROLLED PEAK FLOW UIPGRADE EX 525mm DIA SEWER TO 750mm DIA
Existing Development		EX STWEWEIT IT	-	-	-		1.00	12.00	102.00	204.40	-	501.00	100	0.00	10.0	005.11	1.30	0.10	10.02	J3 /0	- PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023
																					- CONSERVATIVELY ASSUMED THAT PEAK FLOW FROM PHASE 2 SWM TANK OCCURS ALONGSIDE UNCONTROLLED PEAK FLOW
Existing Development	EX STM MH 17	BOX CULVERT	-	-	-	-	1.56	13.02	161.49	252.62	-	361.65	750	0.39	-	695.24	1.57	-	-	52%	- UPGRADE EX. 525mm DIA. SEWER TO 750mm DIA. - PIPE SLOPE ASSUMED BASED ON MEASURED FROM INVERT INFORMATION
																					PROVIDED IN SITE SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023, AND PROPOSED INVERT ELEVATION IN a.m candaras associates inc. "SITE SERVICING & STORMWATER MANGENER'S AND PARTICIPATION OF A
*i100=2096.425/(T_+6.485)^0.863						·	1							1			1				INCLUSING & STORM WATER MANAGEMENT PLAN DATED MAY 21, 2010
						0.05		IMPED.		RADE				0.00						No OF SUFFEE	e.
0.50 GREEN ROOF						0.95	1	IMPER\	IOUS ROOI	F				0.90						1	
NOTES																					

1) EXISTING RELEASE RATE ASSUMED TO BE EQUAL TO THE ALLOWABLE RELEASE RATE FOR PHASE 3. REFER TO COMMENTS IN THE LAST COLUMN OF THE DESIGN SHEET.

	STORM SEWER DESIGN SHEET         Z.B.           CANADA INC.         OHECKED BY:         K.K.           1101A, 1105, and 1163 KINGSTON ROAD - PHASE 3         DATE:         15-Jan-25           City of Pickering         FLE two         221-12931																			
								1101	STORM SEWER											CHECKED BY: K.K.
tor canaba inc.								1101	A, 1100, and 1100 Ki	NGSTON KOAD - P	HASE 5									LAST PRINTED: 15-Jan-25
									City of	Pickering										FILE No 221-12931
			CATCHMENT	ha	R	2.78	ACCUM	T <sub>e</sub> i	Q <sub>100</sub>	Q <sub>CON</sub>	QTOTAL	PIPE					TIME IN	TOTAL		
STREET	FROM M.H.	то м.н.	ID.	AREA	RUNOFF COEFFICIE	N A.R.	2.78 A.R.	(MIN) INTENS	ILL PEAK UNCONTROLLED FL	(L/S)	Q <sub>100</sub> + Q <sub>CON</sub> (L/S)	DIA. (mm)	(%)	(m)	(L/s)	(m/s)	( min. )	TIME (min.)	LOAD %	COMMENTS
				Mixed/Use				(mm/)	EAST SITE			-								
Phase 1	PHASE 1 SWM TANK	STM MH 8	PH1	0.93	0.80	-	-	10.00 186.6	- 99	16.93	16.93	300	0.50	9.0	68.38	0.97	0.16	10.16	25%	- PH1 CONTROLLED RELEASE RATE THROUGH SWM TANK
Phase 1	STM MH 7	STM MH 8	ROW 1	0.20	0.95		_	10.00 186.6	a _	54.98	54.99	975	_	21.5		_		_		- PH1 CONTROLLED RELEASE RATE THROUGH SUPERPIPE + PH1 ROW
Thuse T	Of WINIT?	CTM MITO	NOW 1	0.20	0.00	-	_	10.00 100.0	-	04.00	54.50	5/10	-	21.0	-	_		_		DETAILS.
Phase 1	STM MH 8	STM MH 10	-	-	-	-	-	10.00 186.6	- 99	-	54.98	975	-	38.5	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
Phase 1	STM MH 10	STM MH 1	-	-	-	-	-	10.00 186.6	i9 -	-	54.98	975	-	5.4	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
Phase 3	PHASE 3 SWM TANK	EX STM MH 1	PH3	0.60	0.79	-	-	10.00 186.6	i9 -	29.08	29.08	300	2.00	8.0	136.76	1.93	0.07	10.07	21%	- PH3 CONTROLLED RELEASE RATE THROUGH SWM TANK
111030 0	O MINIMIT I		-	-				10.00 100.0	-		23.00	510	0.00	17.2						
Existing Development	EX STM MH 29	EX STM MH 10	EX. 1	1.69	1.00	4.70	4.70	10.00 186.6	i9 -	90.89	90.89	150	-	10.0	-	-	-	-		U=Ux (2gn/U-3 WHERE: C = 0.8 (orflice tube), A = 0.0177m <sup>4</sup> 2 (150 mm DIA. ORIFICE), g = 9.81 m/s <sup>4</sup> 2, h = 85.10 (HIGH WATER LEVEL PER a.m. candaras associates inc STORWWATER MANAGEMENT REPORT DATED JANUARY, 2015) - 83.00 = 2.10m C = 0.8*0.0177m <sup>4</sup> 2(2*9.81m/s*2*2.10m) c = 0.00808m <sup>4</sup> /3/s
Existing Development	EX STM MH 10	EX STM MH 9	-	-	-	-	-	0.00 417.6		-	119.97	600	0.68	46.8	506.33	1.79	0.44	0.44	24%	CONSERVATIVELY ASSUMED THAT PEAK FLOW FROM ALL UPSTREAM TRIBUTARIES OCCURS TOGETHER. PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023
	QTM MU 40	QTM MU 0	POW/2	0.45	0.05			10.00 400 2	30	0.70	0.70	1000		11.0						
PH4 ROW	STM MH 3	STM MH 4	-	J. 10 -	- CE.U	-	-	10.00 186.0	i9 -	0.10	8.70	1200	-	98.5	-	-	•	-		- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
PH4 ROW	STM MH 4	STM MH 5	-		_	-	-	10.00 186.6	i9 -		8 70	1200	-	114.0		-		-		- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
PH4 ROW	STM MH 5	STM MH 6						10.00 186.6	iq _		8 70	1200	-	16.2				_		- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
PH4 ROW	STM MH 6	STM MH 11	-		_	_	-	10.00 186.6	i9 -	_	8.70	1200	-	6.3		_		-		- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
THERON			-	-	-			10.00 100.0	-	-	0.70	1200	-	0.0				_		
Existing Development	EX STM MH 9	EX STM MH 8 (OGS)	-	-	-	-	-	0.44 394.8	15 -	-	128.67	600	0.60	9.4	475.61	1.68	0.09	0.53	27%	CONSERVATIVELY ASSUMED THAT PEAK FLOW FROM ALL UPSTREAM TRIBUTARIES OCCURS TOGETHER PIPE SLOPE AS PER a m candaras associates inc. "SITE SERVICING & STORM WATER MANAGEMENT PLAN DATED May 1, 2010. DESIGN INFO USED BECAUSE SURVEY CONTAINS CONFLICTING INFORMATION THROUGH THIS SEGMENT. SLOPE TO BE VERIFIED DURING EDTAILED DESIGN.
Existing Development	EX STM MH 8 (OGS)	EX STM MH 7	-	-	-	-	-	0.53 390.3	.4	-	128.67	600	0.60	7.4	475.61	1.68	0.07	0.60	27%	- PIPE SLOPE AS PER a.m. candaras associates inc. "SITE SERVICING & STORM WATER MANAGEMENT PLAN DATED May 21, 2010. DESIGN INFO USED BECAUSE SURVEY CONTAINS CONFLICTING INFORMATION THROUGH THIS SEGMENT. SLOPE TO BE VERIFIED DURING DETAILED DESIGN.
Existing Development	EX STM MH7	EX STM MH 6	-	-	-	-	-	0.60 386.8	.4 -	-	128.67	600	0.39	51.1	383.45	1.36	0.63	1.23	34%	- PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023 - UPSIZE EX. 600mm DIA. SEWER TO 675mm DIA. TO ACCOMMODATE FUTURE PHASES
Existing Development	EX STM MH 6	Headwall	-	•	-	-	-	1.23 359.4	9 -	-	128.67	675	0.39	35.6	524.95	1.47	0.40	1.63	25%	- PIPE SLOPE UNKNOWN, ASSUMED SAME SLOPE AS UPSTREAM PIPE. SLOPE TO BE VERIFIED DURING DETAILED DESIGN.
Bhase 2		STM MH 2	DH 2	1 1 2	0.71			10.00 186.6	SOUTH SITE	63.82	63.83	200	2.00	10.2	126.76	1.02	0.00	10.00	479/	
Phase 2	STM MH 2	EX STM MH 23	PH 2	1.12	0.71	-	-	10.00 185.0	м <u>-</u>	03.62	63.02	300	2.00	20.2	96.70	1.93	0.09	10.09	66%	- FRZ ALLOWABLE REALEAGE RATE
FildSe 2	3110 101 2	EX STM MH 23	-		-	-	-	10.09 185.0	-	-	63.82	300	1.00	20.2	90.70	1.37	0.25	10.33	00%	
	EX STM MH 20	EX STM MH 23	EX. 2	0.29	0.95	0.77	0.77	10.00 186.6	59 142.99	-	142.99	525	0.35	31.2	254.43	1.18	0.44	10.44	56%	- REFER TO EX. 2 IN PHASE 2 STORM DRAINAGE PLAN - PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023
Existing Development	EX STM MH 23	EX STM MH 19	EX. 3	0.10	0.64	0.18	0.94	10.44 182.4	17 172.22	-	236.04	600	0.29	88.8	330.66	1.17	1.26	11.71	71%	CONSERVATIVELY ASSUMED THAT PEAK FLOW FROM PHASE 2 SWM TANK OCCURS ALONGSIDE UNCONTROLLED PEAK FLOW REFER TO EX. 31 PHASE 2 STORM DRAINAGE PLAN. - UPGRADE EX. 525mm DIA. SEWER TO 600mm DIA. - PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY JD BARNES DATED FEB 2, 2023
Existing Development	EX BUILDING	EX STM MH 19	EX. 4			-	-	10.00 186.6	9 -	43.40	43.40	250	2.00	21.0	84.10	1.71	0.20	10.20	52%	- REFER TO EX. 4 IN PHASE 2 STORM DRAINAGE PLAN. - CONTROLLED RELEASE RATE AS PER am candidate associates inc. "SITE SERVICING & STORM WATER MANAGEMENT PLAN" DATED May 21, 2010.
Existing Development	EX STM MH 19	EX STM MH 18	EX. 5	0.31	0.72	0.62	1.56	11.71 171.4	7 268.23	-	375.45	750	0.23	83.3	533.91	1.21	1.15	12.86	70%	- CONSERVATIVELY ASSUMED THAT PEAK FLOW FROM PHASE 2 SWM TANK and EX BUILDING OCCURS ALONGSIDE UNCONTROLLED PEAK FLOW - REFERT TO EX 510 PHASE 2 STORM DRAINAGE FLAN. - UPGRADE EX. 525mm DIA SEWER TO 755mm DIA. - PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY JD BANNES DATED FEB 2, 2023
Existing Development	EX STM MH 18	EX STM MH 17	-	-	-	-	1.56	12.86 162.6	5 254.43	-	361.65	750	0.30	13.3	609.77	1.38	0.16	13.02	59%	CONSERVATIVELY ASSUMED THAT PEAK FLOW FROM PHASE 2 SWM TANK OCCURS ALONGSIDE UNCONTROLLED PEAK FLOW -UPGRADE EX. 525mm DIA. SEWER TO 750mm DIA. - PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY JD BARNES DATED FEB 2, 2023
Existing Development	EX STM MH 17	BOX CULVERT	-	-	-	-	1.56	13.02 161.4	19 252.62	-	361.65	750	0.39	-	695.24	1.57	-	-	52%	- CONSERVATIVELY ASSUMED THAT PEAK FLOW FROM PHASE 2 SWM TANK OCCURS ALONGSIDE UNCONTROLLED PEAK FLOW - UPGRADE EX. Sömm DIA. SeveRT 07 35mm DIA. - PIPE SLOPE ASSUMED BASED ON MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY JD BARNES DATED FEB 2, 2023, AND PROPOSED INVERT ELEVATION IN an canadras association. "SITE SERVICING & STORM WATER MANAGEMENT PLAN* DATED May 21, 2010
100=2096.425/(Tc+6.485)^0.863 UNOFF COEFFICIENTS 25 SOFT LANDSCAPING/PARK 50 GREEN ROOF						0.95 0.95		IMPERVIOUS A	T GRADE OOF				0.90 0.90						<u>No. OF SHEET</u> 1	ž

WSP CANADA INC.								11	STORM SEWER 01A, 1105, and 1163 KIN City of P	DESIGN SHEET IGSTON ROAD - P Vickering	HASE 4									PREPARED BY:         Z.B.           CHECKED BY:         K.K.           DATE:         15-Jan-25           LAST PRINTED:         15-Jan-25           FILE No         221-12931
STREET	FROM M.H.	TO M.H.	CATCHMENT ID.	ha AREA Mixed/Use	R RUNOFF COEFFICIEN	2.78 A.R.	ACCUM 2.78 A.R. (M	T <sub>c</sub> i RAINI IIN ) INTEN (mm	C100 CALL PEAK UNCONTROLLED FLOW ISITY (L/S) (hr)	Q <sub>CON</sub> CONTROLLED FLOW (L/S)	Q <sub>TOTAL</sub> Q <sub>100</sub> + Q <sub>CON</sub> (L/S)	PIPE DIA. (mm)	SLOPE (%)	LENGTH (m)	CAPACITY (L/s)	VELOCITY (m/s)	TIME IN SECTION (min.)	TOTAL TIME ( min. )	LOAD %	COMMENTS
Phase 1	PHASE 1 SWM TANK	STM MH 8	PH1	0.93	0.80	-	- 10	.00 186	.69 -	16.93	16.93	300	0.50	9.0	68.38	0.97	0.16	10.16	25%	- PH1 CONTROLLED RELEASE RATE THROUGH SWM TANK
Phase 1	STM MH 7	STM MH 8	ROW 4	0.20	0.95	-	- 10	.00 186	.69 -	99.42	99.42	975	-	21.5	-	-	-	-	-	- PH1 CONTROLLED RELEASE RATE THROUGH SUPERPIPE + PH1 ROW RELEASE RATE. REFER TO SWM REPORT FOR DYNAMUC MODELLING DETAILS.
Phase 1	STM MH 8	STM MH 10	-		-	-	- 10	.00 186	.69 -	-	99.42	975	-	38.5	1	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
Phase 1	STM MH 10	STM MH 1	-	-	-	-	- 10	.00 186	.69 -	-	99.42	975	-	5.4	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
Phase 3	PHASE 3 SWM TANK	EX STM MH 1	PH3	0.60	0.79	-	- 10	.00 186	.69 -	29.08	29.08	300	2.00	8.0	136.76	1.93	0.07	10.07	21%	- PH3 CONTROLLED RELEASE RATE THROUGH SWM TANK
Phase 3 Phase 4	STM MH 1 EX STM MH 10	EX STM MH 10 STM MH 11	-	-	-	-	- 10	.00 186	.69 -	-	99.42 99.42	975 975	-	17.2 46.8	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS - REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
PH2 ROW	STM MH 12	STM MH 3	ROW 3	0.59	0.95	-	- 10	.00 186	.69 -	98.53	98.53	1200	-	11.3	-	-	-	-	-	RELEASE RATE INCLUDES PH1, PH3 AND PH4 17.0m R.O.W CATCHMENTS. REFER TO SWM REPORT FOR DYNAMIC MODELING DETAILS.
PH4 ROW	STM MH 3	STM MH 4	-	-	-	-	- 10	.00 186	.69 -	-	98.53	1200	-	98.5	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
PH4	PHASE 4 SWM TANK	STM MH 4	PH4	0.70	0.71	-	- 10	.00 186	.69 -	16.67	16.67	250	2.00	10.8	84.10	1.71	0.11	-	20%	- PH4 CONTROLLED RELEASE RATE THROUGH SWM TANK
PH4 ROW	STM MH 4	STM MH 5	-	-	-	-	- 10	.00 186	.69 -	-	98.53	1200	-	114.0	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
PH4 PARK	PHASE 4 SUBSURFACE STORAGE	STM MH 5	PARK	0.88	0.55	-	- 10	.00 186	.69 -	37.09	37.09	250	2.00	11.2	84.10	1.71	-	-	44%	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
PH4 ROW	STM MH 5	STM MH 6	-	-	-	-	- 10	.00 186	.69 -	-	98.53	1200	-	16.2	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
PH4 ROW	STM MH 6	STM MH 11	-	-	-	-	- 10	.00 186	.69 -	-	98.53	1200	-	6.3	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
PH4 ROW	STM MH 11	STM MH 9	-	-	-	-	- 10	.00 186	.69 -	-	196.28	600	0.60	10.4	475.61	1.68	0.10	10.10	41%	REFER TO SWM REPORT FOR DYNAMIC MODELLING INFORMATION LEADING TO TOTA RELWESSE RATE NDICATED. EXISTING 600 DIA STIM TO REMAIN - PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREARED BY J DIARNES DATED FEB 2, 2023
Existing Development	EX STM MH 9	EX STM MH 8 (OGS)	-	-	-	-	- 0	00 417	.64 -	-	196.28	600	0.60	9.4	475.61	1.68	0.09	0.09	41%	-PIPE SLOPE AS PER a.m candaras associates inc. "SITE SERVICING & STORM WATER MANAGEMENT PLAN" DATED May 21, 2010. DESIGN INFO USED BECAUSE SURVEY CONTAINS CONFLICTING INFORMATION THROUGH THIS SEGMENT. SLOPE TO BE VERIFIED DURING DETAILED DESIGN.
Existing Development	EX STM MH 8 (OGS)	EX STM MH 7	-	-	-	-	- 0	09 412	.55 -	-	196.28	600	0.60	7.4	475.61	1.68	0.07	0.17	41%	- PIPE SLOPE AS PER a.m candaras associates inc. "SITE SERVICING & STORM WATER MANAGEMENT PLAN" DATED May 21, 2010. DESIGN INFO USED BECAUSE SURVEY CONTAINS CONFLICTING INFORMATION THROUGH THIS SEGMENT. SLOPE TO BE VERIFIED DURING DETAILED DESIGN.
Existing Development	EX STM MH7	EX STM MH 6	-	-	-	-	- 0	17 408	.61 -	-	196.28	600	0.39	51.1	383.45	1.36	0.63	0.79	51%	- PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023 - UPSIZE EX. 600mm DIA. SEWER TO 675mm DIA. TO ACCOMMODATE FUTURE PHASES
Existing Development	EX STM MH 6	Headwall	-	-	-	-	- 0	79 377	.98 - SOUTH SITE	-	196.28	675	0.39	35.6	524.95	1.47	0.40	1.20	37%	- PIPE SLOPE UNKNOWN, ASSUMED SAME SLOPE AS UPSTREAM PIPE. SLOPE TO BE VERIFIED DURING DETAILED DESIGN.
Phase 2	PHASE 2 SWM TANK	STM MH 2	PH 2	1.12	0.71	-	- 10	.00 186	.69 -	63.82	63.82	300	2.00	10.2	136.76	1.93	0.09	10.09	47%	- PH2 ALLOWABLE REALEASE RATE
Phase 2	STM MH 2	EX STM MH 23	-	-	-	-	- 10	.09 185	.84 -	-	63.82	300	1.00	20.2	96.70	1.37	0.25	10.33	66%	
	EX STM MH 20	EX STM MH 23	EX. 2	0.29	0.95	0.77	0.77 10	.00 186	.69 142.99	-	142.99	525	0.35	31.2	254.43	1.18	0.44	10.44	56%	REFER TO EX. 2 IN PHASE 2 STORM DRAINAGE PLAN     PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE     SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023
Existing Development	EX STM MH 23	EX STM MH 19	EX. 3	0.10	0.64	0.18	0.94 10	.44 182	.47 172.22	-	236.04	600	0.29	88.8	330.66	1.17	1.26	11.71	71%	CONSERVATIVELY ASSUMED THAT PEAK FLOW FROM PHASE 2 SWM TANK OCCURS ALONGSIDE UNCONTROLLED PEAK FLOW REFER TO EX. 3 IM PHASE 2 STORM DRAINAGE PLAN. - UPGRADE EX. 525mm DIA. SEWER TO 600mm DIA. - PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023
Existing Development	EX BUILDING	EX STM MH 19	EX. 4			-	- 10	.00 186	.69 -	43.40	43.40	250	2.00	21.0	84.10	1.71	0.20	10.20	52%	REFER TO EX. 4 IN PHASE 2 STORM DRAINAGE PLAN.     CONTROLLED RELEASE RATE AS PER a.m. candaras associates inc. "SITE     SERVICING & STORM WATER MANAGEMENT PLAN" DATED May 21, 2010.
Existing Development	EX STM MH 19	EX STM MH 18	EX. 5	0.31	0.72	0.62	1.56 11	.71 171	.47 268.23	-	375.45	750	0.23	83.3	533.91	1.21	1.15	12.86	70%	CONSERVATIVELY ASSUMED THAT PEAK FLOW FROM PHASE 2 SWM TANK and EX BUILDING OCCURS ALONGSIDE UNCONTROLLED PEAK FLOW REFER TO EX 5 SIN PHASE 2 STORM DRAINAGE PLAN. UPCRADE EX 532mm DIA. SEWER TO 750mm DIA. PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY JD BARNES DATED FEB 2, 2023
Existing Development	EX STM MH 18	EX STM MH 17	-	-	-	-	1.56 12	.86 162	.65 254.43	-	361.65	750	0.30	13.3	609.77	1.38	0.16	13.02	59%	CONSERVATIVELY ASSUMED THAT PEAK FLOW FROM PHASE 2 SWM TANK OCCURS ALONGSIDE UNCONTROLLED PEAK FLOW UPGRADE EX. S25mm DIA. SEWER TO 750mm DIA. PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023
Existing Development	EX STM MH 17	BOX CULVERT	-	-	-	-	1.56 13	.02 161	.49 252.62	-	361.65	750	0.39	-	695.24	1.57	-	-	52%	- CONSERVATIVELY ASSUMED THAT PEAK FLOW FROM PHASE 2 SWM TANK OCCURS ALONGSIDE UNCONTROLLED PEAK FLOW - UPGRADE EX. 525mm DIA. SEWER TO 750mm DIA. - PIPE SLOPE ASSUMED BASED ON MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023. AND PROPODED INVERT ELEVATION IN a mendarias associatios inc. "SITE SERVICING & STORM WATER MANAGEMENT PLAN* DATED May 21, 2010
*i <sub>100</sub> =2096.425/(T <sub>c</sub> +6.485)^0.863																				
RUNOFF COEFFICIENTS																				
0.25 SOFT LANDSCAPING/PARK 0.50 GREEN ROOF						0.95 0.95	IMF IMF	PERVIOUS	AT GRADE ROOF				0.90 0.90						<u>No. OF SHEETS</u> 1	2

	STORM SEWER DESIGN SHEET       PREPARED BY:       Z.B.         CHECKED BY:       K.K.																				
										STORM SEWE	R DESIGN SHEET										PREPARED BY:         Z.B.           CHECKED BY:         K.K.
WSP CANADA INC.									1101A,	1105, and 1163 k	KINGSTON ROAD - F	PHASE 5									DATE: 15-Jan-25
										City of	f Pickering										LAST PRINTED:         15-Jan-25           FILE No         221-12931
			1	1	1				-rr-					-	1		T		1	1	
STREET	FROM	то	CATCHMENT ID.	AREA	R RUNOFF COEFFICI	2.78 ENT A.R.	ACCUM 2.78	1 T <sub>c</sub>	i RAINFALL PE	Q <sub>100</sub> AK UNCONTROLLED FL	Q <sub>CON</sub>	Q <sub>TOTAL</sub> Q <sub>100</sub> + Q <sub>CON</sub>	DIA.	SLOPE	LENGTH	CAPACITY	VELOCITY	TIME IN SECTION	TOTAL	LOAD	COMMENTS
	M.H.	M.H.		Mixed/Use			A.R.	( MIN )	INTENSITY (mm/hr)	(L/S)	(L/S)	(L/S)	( mm )	(%)	(m)	(L/s)	(m/s)	( min. )	( min. )	%	
Phase 1	PHASE 1 SWM TANK	STM MH 8	PH1	0.93	0.80	-	-	10.00	186.69	EAST SITE	16.93	16.93	300	0.50	9.0	68.38	0.97	0.16	10.16	25%	- PH1 CONTROLLED RELEASE RATE THROUGH SWM TANK
Phase 1	STM MH 7	STM MH 8	ROW 4	0.20	0.95	-	-	10.00	186.69	-	99.42	99.42	975	-	21.5	-	-	-	-	-	- PH1 CONTROLLED RELEASE RATE THROUGH SUPERPIPE + PH1 ROW RELEASE RATE. REFER TO SWM REPORT FOR DYNAMUC MODELLING DETAILS.
Phase 1	STM MH 8	STM MH 10	-	-	-	-	-	10.00	186.69	-	-	99.42	975	-	38.5	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
Phase 1	STM MH 10	STM MH 1	-	-	-	-	-	10.00	186.69	-	-	99.42	975	-	5.4	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
Phase 3	PHASE 3 SWM TANK	EX STM MH 1	PH3	0.60	0.79	-	-	10.00	186.69	-	29.08	29.08	300	2.00	8.0	136.76	1.93	0.07	10.07	21%	- PH3 CONTROLLED RELEASE RATE THROUGH SWM TANK
Phase 3	STM MH 1	EX STM MH 10	-	-	-	-	-	10.00	186.69	-	-	99.42	975	-	17.2	-	-	-	-	-	REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS     PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE
Phase 4	EX STM MH 10	STM MH 11	-	-	-	-	-	10.00	186.69	-	-	99.42	975	-	46.8	-	-	-	-	-	SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023
Phase 4	STM MH 11	STM MH 9	-	-	-	-	-	10.00	186.69	-	-	99.42	975	-	46.8	-	-	-	-	-	SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023
PH2 ROW	STM MH 12	STM MH 3	ROW 3	0.59	0.85	-	-	10.00	186.69	-	98.53	98.53	1200	-	11.3	-	-	-	-	-	RELEASE RATE INCLUDES PH1,PH3 AND PH4 17.0m R.O.W CATCHMENTS. REFER TO SWM REPORT FOR DYNAMIC MODELING DETAILS.
PH4 ROW	STM MH 3	STM MH 4	-	-	-	-	-	10.00	186.69	-	-	98.53	1200	-	98.5	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
PH4	PHASE 4 SWM TANK	STM MH 4	PH4	0.70	0.71	-	-	10.00	186.69	-	16.67	16.67	250	2.00	10.8	84.10	1.71	0.11	-	20%	- PH4 CONTROLLED RELEASE RATE THROUGH SWM TANK
PH4 ROW	STM MH 4	STM MH 5	-	-	-	-	-	10.00	186.69	-	-	98.53	1200	-	114.0	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
PH4 PARK	PHASE 4 SUBSURFACE STORAGE	STM MH 5	PARK	0.88	0.55	-	-	10.00	186.69	-	37.09	37.09	250	2.00	11.2	84.10	1.71	-	-	44%	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
PH4 ROW	STM MH 5	STM MH 6	-	-	-	-	-	10.00	186.69	-	-	98.53	1200	-	16.2	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
PH4 ROW	STM MH 6	STM MH 9	-	-	-	-	-	10.00	186.69	-	-	98.53	1200	-	6.3	-	-	-	-	-	- REFER TO SWM REPORT FOR SUPERPIPE MODELLING DETAILS
PH4 ROW	STM MH 11	STM MH 9	-	-	-	-	-	10.00	186.69	-	-	196.28	600	0.60	10.4	475.61	1.68	0.10	10.10	41%	- REFER TO SWM REPORT FOR DYNAMIC MODELLING INFORMATION LEADING TO TOTAL RELWESE RATE INDICATED. - EXISTING 600 DIA STM TO REMAIN - PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023
PH5	EX STM MH 9	EX STM MH 8 (OGS)	-	-	-	-	-	0.00	417.64	-	-	196.28	600	0.60	9.4	475.61	1.68	0.09	0.09	41%	-PIPE SLOPE AS PER a.m candaras associales inc. "SITE SERVICING & STORM WATER MANAGEMENT PLAN" DATED May 21, 2010. DESIGN INFO USED BECAUSE SURVEY CONTAINS CONFLICTING INFORMATION THROUGH THIS SEGMENT. SLOPE TO BE VERIFIED DURING DETAILED DESIGN.
PH5	EX STM MH 8 (OGS)	EX STM MH 7	-	-	-	-	-	0.09	412.55	-	-	196.28	600	0.60	7.4	475.61	1.68	0.07	0.17	41%	- PIPE SLOPE AS PER a.m candaras associates inc. "SITE SERVICING & STORM WATER MANAGEMENT PLAN" DATED May 21, 2010. DESIGN INFO USED BECAUSE SURVEY CONTAINS CONFLICTING INFORMATION THROUGH THIS SEGMENT, SLOPE TO BE VERIFIED DURING DETAILED DESIGN.
PH5	EX STM MH7	EX STM MH 6	-	-	-	-	-	0.17	408.61	-	-	196.28	600	0.39	51.1	383.45	1.36	0.63	0.79	51%	- PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023 - UPSIZE EX. 600mm DIA. SEWER TO 675mm DIA. TO ACCOMMODATE FUTURE PHASES
PH5	EX STM MH 6	Headwall	-	-	-	-	-	0.79	377.98	-	-	196.28	675	0.39	35.6	524.95	1.47	0.40	1.20	37%	- PIPE SLOPE UNKNOWN, ASSUMED SAME SLOPE AS UPSTREAM PIPE. SLOPE TO BE VERIFIED DURING DETAILED DESIGN.
Dhara û		STM MU S	BUIG	4.40	0.74			40.00	100.00	SOUTH SITE	C2 00	62.00	200	0.00	40.0	400.70	1.02	0.00	10.00	470/	
Phase 2	PHASE 2 SWM TANK	STM MH 2	PH 2	1.12	0.71		-	10.00	180.09	-	63.80	63.80	300	2.00	10.2	130.70	1.93	0.09	10.09	47%	- PHZ ALLOWABLE REALEASE RATE
Phase 2	STM MH 2	EX STM MH 23	-	-	-	-	-	10.09	185.84	-	-	63.80	300	1.00	20.2	96.70	1.37	0.25	10.33	66%	
PH5	EX STM MH 23	EX STM MH 19				-	-	10.33	3 183.49	-	-	63.80	600	0.29	88.8	330.66	1.17	1.26	11.60	19%	- UPGRADE EX. 525mm DIA. SEWER TO 600mm DIA. - PIPE SLOPE MEASURED FROM INVERT INFORMATION PROVIDED IN SITE SURVEY PREPARED BY J.D BARNES DATED FEB 2, 2023
PH5	PHASE 5 SWM TANK	EX STM MH 19	PH 5	1.76	0.74	-	-	10.00	) 186.69	-	88.72	88.72	300	2.00	21.0	136.76	1.93	0.18	10.18	65%	- PH5 ALLOWABLE RELEASE RATE
PH5	EX STM MH 19	EX STM MH 18				-	-	11.60	) 172.36	-	-	152.52	750	0.23	83.3	533.91	1.21	1.15	12.75	29%	- CONSERVATIVELY ASSUMED THAT PEAK FLOW FROM ALL UPSTREAM TRIBUTARIES OCCURS TOGETHER.
PH5	EX STM MH 18	EX STM MH 17	-	-	-	-	-	12.75	5 163.44	-	-	152.52	750	0.30	13.3	609.77	1.38	0.16	12.91	25%	- CONSERVATIVELY ASSUMED THAT PEAK FLOW FROM ALL UPSTREAM TRIBUTARIES OCCURS TOGETHER.
PH5	EX STM MH 17	BOX CULVERT	-	-	-	-	-	12.91	162.27	-	-	152.52	750	0.39	-	695.24	1.57	-	-	22%	- CONSERVATIVELY ASSUMED THAT PEAK FLOW FROM ALL UPSTREAM TRIBUTARIES OCCURS TOGETHER.
*i100=2096.425/(T_+6.485)^0.863			<u>u</u>	1	1				<u> </u>						1	1	1	1	1	1	·
	ADK					0.00	5	IMOCO		ADE				0.00							÷
0.20 SUFT LANDSCAPING/P 0.50 GREEN ROOF						0.95	95	IMPER	VIOUS AT GR	NUC				0.90	)					NO. OF SHEET	<u>2</u>
NOTES																					

![](_page_70_Picture_0.jpeg)

![](_page_70_Picture_1.jpeg)

![](_page_71_Picture_0.jpeg)
TOPOGRAPHIC INFORMATION SHOWN AS PER J.D BARNES SURVEY 22-25-073-00 DATED 2/2/2023. ELEVATIONS HEREON ARE GEODETIC AND ARE REFERRED TO CITY OF PICKERING BENCHMARK No. 1-059, HAVING A PUBLISHED ELEVATION OF 84.111m (CGVD-1928: 1978)







Ruce and Cardination of the additional of the second of th	And You Poerson And Yo	And rest Control Decision Control Decision Co							
KEY PLAN		N.T.S.							
	PROPERTY LINE PROPOSED UND PROPOSED WAT PROPOSED SAN PROPOSED TEM PROPOSED TEM PROPOSED WAT IN PREVIOUS PH PROPOSED SAN IN PREVIOUS PH EXISTING STORM EXISTING STORM EXISTING STORM EXISTING WATED PHASE 1 PHASE 2 PHASE 3	Y LINE 9 UNDERGROUND LIMITS 9 WATERMAIN 9 STORM 9 SANITARY 9 TEMPORARY WATERMAIN 9 WATERMAIN INSTALLED 9 STORM INSTALLED 9 SANITARY INSTALLED 9 SANITARY INSTALLED 9 SANITARY SEWER TO REMAIN 6 ANITARY SEWER TO WATERMAIN TO REMAIN							
	PHASE 4								
2. ISSUED F 1. ISSUED F No. REVISION ALL PREVIOUS IS CLIENT TRIBU	2. ISSUED FOR ZBA & OPA 1. ISSUED FOR ZBA & OPA No. REVISIONS TO DRAWING ALL PREVIOUS ISSUES OF THIS DRAWIN CLIENT								
PROJECT TITLE 1101A, 1105, and 1163 KINGSTON ROAD									
SHEET TITLE SITE SERVICING PLAN PHASE 4									
STAMP Stamp K. KYRIOPOULO 100149502 Jan. 24, 2025 Rohnce of ONT	APPRO	VAL							
DESIGNED Z.B. SCALE 1:75 JOB NUMBER 221-12	CHECKED K.K. DATE OCTOBER 2023 SHEET NUMBER SS4								



+											
Bill Re/Mac Hall	Group-O	ube + Tires	Master Mechanic Pickering								
	Am	TT	SITI								
Sabbr 3 House		1	15	01898							
	And The Control of Con	V	ores Nacional	a for rey							
Tasca Rokering	Mode Yogs Pickering	Ontailo All F	Bayly	Family Practice							
Khel-Badminton / Volleyball / Pickeball	Constant Providence			San Francisc By The Bay							
			IN.I	.8.							
LEGEND											
PROPERTY LINE     PROPOSED UNDERGROUND LIMITS											
	PROPOSED WAT	ERMAI RM	N								
	PROPOSED SAN	ITARY									
	PROPOSED TEM	PORAF ERMAI	RY WATER	MAIN .ED							
	IN PREVIOUS PHASES										
	IN PREVIOUS PH. PROPOSED SANI	ASES	INSTALLE								
	IN PREVIOUS PH	ASES									
	EXISTING SANITA	ARY SE	WER TO								
	REMAIN	ρμαινί	το βεμαι	N							
	EXISTING WATERMAIN TO REMAIN										
	PHASE 1										
	PHASE 2										
	PHASE 3										
	PHASE 4										
	PHASE 5										
2. ISSUED	FOR ZBA & OPA	кк	25-01-24								
1. ISSUED	FOR ZBA & OPA	кк	23-10-27								
No. REVISIO	NS TO DRAWING	BY G ARE SI	DATE JPERSEDED	APPR.							
	TE (BROC	)KD	ALE)								
	OF PICK	ERI	NG								
PROJECT TITLE 1101A, 1105, and 1163											
	NGSTON R										
SILE	PHASE 5	6 P 5	LAN								
CONSULTANT	<b>\\</b> \ \										
STAMP	APPRO	/AL									
DPROFESSIONA											
S K. KYRIOPOULOS											
Jan. 24, 2025											
DESIGNED	DRAWN		FCKFD								
DESIGNED     DRAWN     CHECKED       Z.B.     CAD 20     K.K.       SCALE     DATE											
JOB NUMBER		O		UZ3							
221-12	SS5										











































TRCA EROSION AND SEDIMENT CONTROL NOTES:

- 1. EROSION AND SEDIMENT CONTROL (ESC) MEASURES WILL BE IMPLEMENTED PRIOR TO, AND MAINTAINED DURING THE CONSTRUCTION PHASES, TO PREVENT ENTRY OF SEDIMENT INTO THE WATER. ALL DAMAGED EROSION AND SEDIMENT CONTROL MEASURES SHOULD BE REPAIRED AND/OR REPLACED WITHIN 48 HOURS OF THE INSPECTION.
- 2. DISTURBED AREAS WILL BE MINIMIZED TO THE EXTENT POSSIBLE, AND TEMPORARILY OR PERMANENTLY STABILIZED OR RESTORED AS THE WORK PROGRESSES.
- ALL IN-WATER AND NEAR-WATER WORKS WILL BE CONDUCTED IN THE DRY AND 3. APPROPRIATE EROSION AND SEDIMENT CONTROLS
- 4. THE EROSION AND SEDIMENT CONTROL STRATEGIES OUTLINED ON THE PLANS ARE NOT STATIC AND MAY NEED TO BE UPGRADED/AMENDED AS SITE CONDITIONS CHANGE TO MINIMIZE SEDIMENT LADEN RUNOFF FROM LEAVING THE WORK AREAS. IF THE PRESCRIBED MEASURES ON THE PLANS ARE NOT EFFECTIVE IN PREVENTING THE RELEASE OF A DELETERIOUS SUBSTANCE, INCLUDING SEDIMENT, THEN ALTERNATIVE MEASURES MUST BE IMPLEMENTED IMMEDIATELY TO MINIMIZE POTENTIAL ECOLOGICAL IMPACTS. TRCA ENFORCEMENT OFFICER SHOULD BE IMMEDIATELY CONTACTED. ADDITIONAL ESC MEASURES TO BE KEPT ON SITE AND USED, AS NECESSARY.
- AN ENVIRONMENTAL MONITOR WILL ATTEND THE SITE TO INSPECT ALL NEW CONTROLS IMMEDIATELY AFTER INSTALLATION. INSPECTION OF ESC MEASURES TO BE WILL OCCUR, AT MINIMUM:
- 5.1. ON A WEEKLY BASIS; 5.2. PRIOR TO SIGNIFICANT RAINFALL EVENTS (MINIMUM PREDICTED 25MM OVER 24 HOURS);
- 5.3. AFTER EVERY RAINFALL/SNOWMELT EVENT; AND
- 5.4. DAILY DURING EXTENDED RAINFALL PERIODS.

INSPECTIONS WILL FOCUS ON MEASURES RELATED TO EROSION AND SEDIMENT CONTROLS, DEWATERING OR UNWATERING, RESTORATION AND IN- OR NEAR- WATER WORKS. SHOULD CONCERNS ARISE ON SITE THE ENVIRONMENTAL MONITOR WILL CONTACT THE TRCA ENFORCEMENT OFFICER AS WELL AS THE PROPONENT.

- 6. ALL ACTIVITIES, INCLUDING MAINTENANCE PROCEDURES, WILL BE CONTROLLED TO PREVENT THE ENTRY OF PETROLEUM PRODUCTS, DEBRIS, RUBBLE, CONCRETE OR OTHER DELETERIOUS SUBSTANCES INTO THE WATER. VEHICULAR REFUELING AND MAINTENANCE WILL BE CONDUCTED A MINIMUM OF 30 METRES FROM THE WATER
- ALL GRADES WITHIN THE REGULATORY FLOOD PLAIN WILL BE MAINTAINED OR 7. MATCHED.
- THE PROPONENT/CONTRACTOR SHALL MONITOR THE WEATHER SEVERAL DAYS IN 8. ADVANCE OF THE ONSET OF THE PROJECT TO ENSURE THAT THE WORKS WILL BE CONDUCTED DURING FAVOURABLE WEATHER CONDITIONS. SHOULD AN UNEXPECTED STORM ARISE, THE CONTRACTOR WILL REMOVE ALL UNFIXED ITEMS FROM THE REGIONAL STORM FLOOD PLAIN THAT WOULD HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTRUCTION TO FLOW, E.G., FUEL TANKS, PORTA-POTTIES, MACHINERY, EQUIPMENT, CONSTRUCTION MATERIALS, ETC.
- ALL DEWATERING/UNWATERING SHALL BE TREATED AND RELEASED TO THE 9. ENVIRONMENT AT LEAST 30 METRES FROM A WATERCOURSE OR WETLAND AND ALLOWED TO DRAIN THROUGH A WELL VEGETATED AREA. NO DEWATERING EFFLUENT SHALL BE SENT DIRECTLY TO ANY WATERCOURSE, WETLAND OR FOREST, OR ALLOWED TO DRAIN ONTO DISTURBED SOILS WITHIN THE WORK AREA. THESE CONTROL MEASURES SHALL BE MONITORED FOR EFFECTIVENESS AND MAINTAINED OR REVISED TO MEET THE OBJECTIVE OF PREVENTING THE RELEASE OF SEDIMENT LADEN WATER.
- 10. ALL ACCESS TO THE WORK SITE SHALL BE FROM EITHER SIDE OF THE WATERCOURSE. NO EQUIPMENT OR VEHICLES ARE PERMITTED TO CROSS THROUGH THE WATERCOURSE UNLESS APPROVED BY TRCA.

- Prior to commencement of any on-site work/topsoil stripping, erosion and sediment

- construction period.

- has accumulated to a depth greater than 50% of all the upstream check dams.







N.T.S

KEY PLAN LEGEND



2.	ISSUED FO	OR ZBA & OPA	КК	25-01-24						
1.	ISSUED FO	OR ZBA & OPA	A	КК	23-10-27					
No.	REVISIONS	S TO DRAWING	3	BY	DATE	APPR.				
CLI	ALL PREVIOUS ISSUES OF THIS DRAWING ARE SUPERSEDED									
	TRIBUTE (BROOKDALE) LIMITED									
MUI	MUNICIPALITY CITY OF PICKERING									
PRC	PROJECT TITLE 1101A, 1105, and 1163 KINGSTON ROAD									
SHE	SHEET TITLE EROSION AND SEDIMENT CONTROL STANDARD NOTES & DETAILS									
CON	CONSULTANT									
STA	MP SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL SPROFESSIONAL	WIGINEER OCT	APPROV	'AL						
DES	BIGNED		20	СН	ECKED					
SCA	LE.		20			023				
JOE	NUMBER			SHEET	NUMBER	020				
	221-12	931			ESC6					



## SUPPORTING DOCUMENTS

SEWE	R IN	IVER1		TA TA		NOTES	мн/св	DIRECTION	DIAMETER	INVERT	TOP OF LID/ GRATE FI FV		NOTES	
CB#1	N	200	1.31	85.54	84.23		STM MH#7	N SE	600 600	2.30 2.33	84.89	82.59 82.56		
CB#2	SE	200	1.23	85.54	84.31		STM MH#8 STM	NW S N	<i>*600</i> <i>*600</i> 600	±2.50 ±2.50	84.99 84.98	±82.49 ±82.49 82.68 82.65	OIL GRIT SEPARATOR	
СВ#4	N	300	1.25	84.89	83.52		MH#9 STM MH#10	SE SW NW N NE	300 300 450 450	2.33 1.94 1.92 N/A 1.94	85.06	83.04 83.14 N/A 83.12	1.95TO DEBRIS	
CB#5	NE	300	1.09	84.95	83.86		STM MH#11	S E W	*150 300 300	<i>*2.06</i> 1.90 1.84	85.06	* <i>83.00</i> 83.16 83.22	REDUCED PIPE	
DCB#6	NE	300	1.26	84.32	83.06		STM MH#12	N E SW N	450 300 450 450	2.34 ±2.07 ±2.02 2.65	85.86	83.52 ±83.79 ±83.84 83.48		
DCB#7 CB#8	SE w	300	1.17	84.28	83.11		STM MH#13 STM	NE S SW	450 450 150	2.70 2.62 1.80 2.19	85.51	83.43 83.51 84.33 83.32		
св#9	w	250	1.30	84.91	83.61		STM MH#15	SW N NE	450 450 <i>*450</i> 450	2.17 1.83 1.74 1.85	85.56	83.34 83.73 83.82 83.71	NE-RECESSED	
CB#10	w	300	1.43	85.38	83.95		STM MH#16	NW N SE	300 150 450	1.40 1.31 2.15	86.32	84.92 85.01 84.17		
CB#11	S	450	1.52	85.24	83.72		STM MH#17	*// NE *S	<i>*525</i> *525 <i>*525</i>	N/A 2.00 N/A	84.02	N/A 82.02 N/A	OIL GRIT SEPARATOR	
CB#12	SE NW	300 450	1.30	85.41 85.62	84.11		STM MH#18	NE SW NW	250 525 250 525	1.97 1.98 3.75	84.04 86.18	82.07 82.06 82.43 82.28	NE-W/ ORIFICE PIPE	
CB#14	S NW	450 250	1.86	85.26	83.76 84.19		мн#19 STM MH#20	NW NW NE SE	525 525 450 300 525	2.19 1.84 2.20	84.88	82.26 82.69 83.04 82.68		
CB#15	NE	250	0.96	85.44	84.48		STM MH#21	SW NE SE SW	250 250 250 250	2.17 1.36 1.15 1.40	84.48	82.71 83.12 83.33 83.08		
CB#16	SE	300	0.78	85.71	84.93		STM MH#22	NW SE	100 600	2.08 2.10	84.54	82.46 82.44	NW-REDUCED PIPE	_
CB#17	SE SW	300 250 250	1.29 1.27	85.65	84.36 84.38 84.34		STM MH#23 STM	NW SW NF	525 525 450	4.70 4.73 2.20 2.18	87.27 85.15	82.57 82.54 82.95 82.95		
CB#19	SSE	250	1.44	84.69	83.25		мн#24 STM MH#25	SE NW NW NE	450 450 100 450	2.18 2.22 1.57 1.76 1.62	85.16	82.93 83.59 83.40 83.54		
CB#20	SE	250	1.49	84.81	83.32		STM MH#26	S *S	450 <i>*250</i>	1.87 N/A	N/A	83.29 N/A	UNABLE TO ACCESS	
CB#21	SE	250	1.58	84.77	83.19		STM MH#27	NW NE	300 450	2.31 ±2.32	86.26	83.95 ±83.94		
CB#22	*NW NW	*250 250 300	N/A 1.30 1 31	84.19 84.19	N/A 82.89 82.88	PARKED TRUCK	STM MH#28	NE SW	450 450 450	1.60	84.94	84.12 84.11 83.34		
CB#24	SE	250 250	1.30 N/A	N/A	82.89 N/A	1.10 TO DEBRIS	мн#29 STM MH#30	SW NW E SW	450 450 300 450	1.62 1.03 1.06 1.10	84.98	83.32 83.95 83.92 83.88		
DCB#25	SW	300	1.35	84.88	83.53		STM MH#31	NW SE	450 450	1.14 1.20	85.17	84.03 83.97		JR-16
CB#26	NW NE SE W	450 150 450 250	2.14 1.71 2.15 1.88	85.03	82.89 83.32 82.88 83.15		STM MH#32	*N *SW	*250 *250	N/A N/A	86.72	N/A N/A	BOLTED SHUT	R/W
CB#27 CB#28	N/A SW	N/A 250	N/A 1.20	84.77	N/A 83.24	NO PIPE	MH#1 SAN	NE SW NW NW	1050 1050 150 150	5.80 5.77 1.37 2.62	85.10	79.30 79.33 83.69 82.44	NW'-DROP	
DCB#29	SE	250	1.24	84.83	83.59		SAN MH#3	SE SE W	200 150 150	2.63 2.81 2.77	84.50	82.43 81.69 81.73		PART 1, PLAN 40R-16455
CB#30	SE SW	250 450	1.27 1.32	84.74	83.47 83.42		SAN MH#4	NW NE SW	200 1050 1050	4.38 5.13 5.10	84.29	79.91 79.16 79.19		
CB#31	NW	250	1.14	84.95	83.81		SAN MH#5 SAN	N SE	200 200	4.23 4.25	84.45	80.22 80.20		- PAR
CB#32 CB#33	W NE	300 300	1.57	85.53 85.24	83.96		MH#6 SAN MH#7	S N NE	200 200 200 200	4.22 3.56 3.40	84.94	80.31 81.38 81.54		
DCB#34	NW	250	1.0	84.77	83.77		SAN MH#8	SE NW NE S SW	200 150 200 200 150	3.60 2.74 3.02 3.04 2.97	85.06	81.34 82.32 82.04 82.02 82.09		PART 6, PLAN 40R-16455
DCB#35	NW	250	0.70	84.84	84.14		SAN MH#9	NE SW	150 150 150	3.09 3.08	85.23	82.14 82.09		PART 2, PLAN 40R-16455
DCB#36	W	300	0.72	84.78	84.06		SAN MH#10 SAN	SE W	150 150 150	2.00 1.98 2.17	85.29 85.94	83.29 83.31 83.77		PART 3, PLAN 40R-16455 PART 7, PLAN- 40R-16455
CB#38	*£	∠əu *250	*1.50	*85.25	04.06 *83.75		MH#11 SAN MH#12	SW N S	150 200 200	2.10 2.07 1.96	87.91	83.84 85.84 85.95		PART 4, PLAN 40R-16455
CB#39	*NE	*250	*1.50	*85.25	*83.75		SAN MH#13	NE SW	*1050 *1050	6.50 6.40	85.27	78.77 78.87	W/ PLATFORM	
STM MH#1	NW NE SW	450 525 400 825	1.87 1.97 1.90 2 27	85.77	83.90 83.80 83.87 82.77		SAN MH#14	NE SW	200 200 <i>*150</i>	1.81 2.30 <i>*3.95</i>	84.91 * <i>±86.56</i>	83.10 82.61 *±82.61		PART 8,
MH#2 STM	E W NE SW	825 300 825 <i>*900</i>	2.44 1.90 2.38 <i>*2.37</i>	84.82	82.60 83.14 82.44 82.45		MH#15	*NW *NE *SW *NE	*150 *1050 *1050 *200	*6.54 *7.41 *7.41 *2.90	*86.80	*±79.02 *±79.15 *±79.15 *83.90	UNABLE TO	- - - - - - - - - - - - - - - - - - -
STM MH#4	W NW E SW	*525 600 900 900	<i>*2.33</i> ±1.98 2.34 2.14	84.41	82.49 ±82.43 82.07 82.27		SAN MH#17	*3 *SE	*200	*2.30 N/A	N/A	+04.3U N/A	UNABLE TO FOUND	
STM MH#5	NW SE	600 100	2.26 2.29	84.76	82.50 82.47	SE - REDUCED PIPE	MH#1	NW SE	±1000 ±1000	2.50 2.50	86.34	83.84 83.84	POSSIBLY STORM MANHOLE	
STM MH#6 <i>*INFORMATI</i>	NW S	600 675	2.23 2.26	84.59 FROM_CLIENT,	82.36 82.33 <i>REGION_OF_DURH</i>	IAM	MH#2 <i>*INF.ORM/</i>	NW SE	±1000 ±1000	2.90 2.92 <i>RECORDS</i>	85.62	82.72 82.70 <i>REGION OF DURI</i>	POSSIBLY STORM MANHOLE	
AND CITY (	OF PICKEI	RING; NOT F	IELD VERIF	IED BY ONSIT	E LOCATES INC.		AND CIT	Y OF PICKE	RING; NOT I	IELD VERIF	 	E LOCATES INC.		-1191
							/		~	,	/			LOT 24, $4$
							/		-01		/			PART 1, PLAN 40R-12678
										/				PIN 26317 -0070
							/	D 75	ר` ע					331025
						, 		A AN		/				Ď N V
						/		S S S	/	1				572, 572,
						/		LIV L(	/					D2885
						/	IS C ETWER	26317	/					
						/	$\sum_{CE} A$	۰V	 					57'20"W
							0 MAN	/	/					, AS
							ALL,	/			- <i></i>	\] <b>A</b> • ·		O ART S. T.E.
				PA	ART 2, F 40R-11⊿	, PLAN- 83 ~ ~	740	/		- PAR 4C	1, P )R-1148	'LAN 83		
				(	(P1,P5&SET) R (MEAS) A	2=18.50 =28.02	-	/ \ / \	PAGE			PIN SUB	BJECT TO	26317 EASEMENT AND RIGHT-OF-WAY AS IN D331029
				(P1,	(P1,P5) / (MEAS) <b>C</b> (P1,P5) ( P5&MEAS) <b>N8</b>	x=28.08 = <b>25.42</b> C=25.46 <b>*31'15"E</b>	/ \		CURB		N58.02'40"	, Ê <u>(</u> (P9)	PART (rpe)	8, PLAN 40R-12678
					/		/	A500 STM	3#2 () () () () () () () () () ()		13759'30' 27.39(P1, 	Е (Р1,́Р5&МЕ, ,Р5,Р9&МЕАЅ с	AS)	SIGNAL G G G G G G G G G G G G G G G G G G G
					/ N44* / (P5/	C=5.07 08'00''E &MEAS)	$\langle \rangle$	ST 20	WV DØ M			100¢ WS	6.2₩ <u> </u>	
					/ <u>N5</u>	4.94 1*46'25"E	40			SAN	EDGE BC 0.7 S	STM		OF LS
				/	· (P1, /	BACK OF	IB (RP (RPE)	С РЕ)св #1			EDGE BACK			$\frac{1}{26317} \xrightarrow{\text{SAN}} \frac{1}{26317} \xrightarrow{\text{SAN}} \frac{1}{26317} \xrightarrow{\text{SAN}} \frac{1}{84.89} \text{ OF}$
				/	F CC	ENCE RNER 0.1 N 0.8 E SSIB		×	PED 1.2 N			UT - ·	UT	_ABANDONEDUT - FENCE_UT UT UT UT
								$\sim L$			CHAIŃ	N57 <b>*</b> 59'3	0"E (P1,P5&M	IEAS)

•**39′00″E**(CALC1&MEAS

S.T.E. AS IN C0144390

`♠ SCP 00919680467

PART 6, PLAN-40R-6179 *s.t.e. as in-c0144390* 

40R-25448 Ó EASEMENT AS IN D288571, D338631, D347349 AND DR746227 -SUBJECT \_\_\_\_\_PART 47, PLAN 40R-25448

PLAN



PLOTTED: 2/2/2023

G: \22-25-073\00\22-25-073-00.dgn



