



# Traffic Impact Study

**720 Granite Court**

1334281 Ontario Ltd.

25 April 2023

# Executive summary

GHD Limited was retained to prepare a Traffic Impact Study report for the proposed residential development located at 720 Granite Court in the City of Pickering.

This report determines the site related traffic and subsequent traffic related impacts on the adjacent road network during the weekday a.m. and p.m. peak hours. These impacts are based on the projected future background traffic and road network conditions derived for a 2027, 2032, and 2037 planning horizon year.

The proposed site plan consists of a 12-storey high-rise building with a total of 262 dwelling units.

Access to the subject site is proposed via a single full-moves driveway onto Granite Court located approximately 75 metres from the intersection of Whites Road and Granite Court/Oklahoma Drive.

The proposed new development is expected to generate a total of 76 new two-way trips consisting of 20 inbound and 56 outbound trips during weekday a.m. peak hour and 91 new two-way trips consisting of 56 inbound and 35 outbound trips during the weekday p.m. peak hour.

Under existing, future background, and future total conditions, all study intersections are operating within capacity.

Application of the current City of Pickering's By-Law parking rates to the subject site results in a requirement of 457 vehicle parking spaces, shared between residents and visitors.

The subject site provides a total of 393 parking spaces for vehicles (1.25 spaces per unit for residents, 0.25 spaces per unit for visitors), a shortfall of 64 parking spaces from the By-law requirement.

The proposed rates for the subject site match the required minimum parking rates found in the City's Draft Comprehensive Zoning By-law. The provision of 1.25 spaces per unit for residents and 0.25 spaces per unit for visitors is also consistent with recently updated parking rates found in adjacent municipalities such as Ajax, Whitby, and Whitchurch-Stouffville.

A series of Transportation Demand Management (TDM) measures are proposed for the site to reduce dependency on single-occupancy vehicle trips by encouraging residents to explore alternative modes of transportation. These measures include:

- Improved pedestrian and cycling connectivity to the municipal networks, to make it easy and safe for people to walk or bike to their destination
- One time Presto Pass for residents upon purchase of a unit
- The provision of bicycle parking for both residents and visitors
- Unbundled vehicle parking
- Communication strategy and information packages

These measures will not only help reduce traffic congestion and air pollution, but also promote a healthier and more active lifestyle for the residents.

The City of Pickering's Standard for accesses is found in Drawing P-605, Medium to high density residential, commercial, and industrial driveway access and states that the minimum and maximum access width requirement for two-way residential driveways ranges from 6.5 to 12 metres and the radius is required to be between 7.5 and 9 metres. The proposed site access has a width of 7.3 metres with an inbound and outbound radius of 7.5 metres, meeting the City's requirement.

A Vehicle Swept Path Analysis was undertaken to assess the site's ability to accommodate the required turning movements of a waste collection truck, an MSU Truck and a Passenger vehicle as per TAC design guidelines and confirmed that the site can sufficiently accommodate the aforementioned design vehicles.

A sightline assessment of the proposed location of the site access confirmed that sufficient sightlines are provided to satisfy intersection sight distances for a 40 km/h posted speed limit along Granite Court.

The traffic study concludes that the proposed development can be adequately accommodated by the existing and/or planned transportation network.

We trust that this satisfies your requirements, but do not hesitate to contact the undersigned if you have any questions.

Sincerely,

GHD

William Maria, P. Eng.

Transportation Planning Lead



# Contents

<b>1. Introduction</b>	<b>7</b>
1.1 Retainer and Objective	7
1.2 Study Team	7
<b>2. Site Characteristics</b>	<b>8</b>
2.1 Study Area	8
2.2 Proposed Development Content	8
<b>3. Existing Conditions</b>	<b>10</b>
3.1 Existing Road Network	10
3.2 Pedestrian and Bicycle Routes	11
3.3 Transit Services	11
3.4 Existing Traffic Data	12
<b>4. Future Background Traffic</b>	<b>13</b>
4.1 Study Horizon Year	13
4.2 Corridor Growth	14
4.3 Background Development Traffic	14
4.4 Future Background Traffic Volumes	17
<b>5. Site Generated Traffic</b>	<b>19</b>
5.1 Site Traffic Generation	19
5.2 Site Traffic Distribution and Assignment	20
<b>6. Future Total Traffic</b>	<b>21</b>
<b>7. Capacity Analysis</b>	<b>24</b>
7.1 Whites Road and Bayly Street	25
7.2 Whites Road and Granite Court/Oklahoma Drive	27
7.3 Granite Court and the Site Access	29
<b>8. Parking Review</b>	<b>30</b>
8.1 Existing City of Pickering Zoning By-law	30
8.1.1 Vehicular Parking	30
8.2 Parking Provision	30
8.2.1 Draft Pickering Zoning By-law	30
8.2.2 2016 Transportation Tomorrow Survey Data	31
8.3 Parking Assessment	31
<b>9. Travel Demand Management</b>	<b>32</b>
9.1 Travel Demand Management	32
9.2 Existing TDM Opportunities	32
9.2.1 Walking	32
9.2.2 Transit	32
9.3 Recommended TDM Measures	33
<b>10. Site Plan Review</b>	<b>34</b>

<b>11. Vehicle Swept Path Analysis</b>	<b>34</b>
<b>12. Sightline Review</b>	<b>34</b>
<b>13. Conclusion</b>	<b>38</b>

## Table Index

Table 1	Background Development Traffic .....	15
Table 2	Estimated Site Trips.....	20
Table 3	Directional Trip Distribution of Site Traffic .....	20
Table 4	Capacity analysis of Whites Road and Bayly Street.....	25
Table 5	Capacity analysis of Whites Road and Granite Court/Oklahoma Drive .....	27
Table 6	Capacity analysis of Granite Court and the Site Access .....	30
Table 7	Parking Requirements in Surrounding Municipalities).....	31
Table 8	Pickering Vehicle Ownership TTS Data for Apartments.....	31
Table 9	Recommended TDM Strategies .....	33
Table 10	Intersection Sight Distance Requirement .....	35

## Figure Index

Figure 1	Site Location .....	8
Figure 2	Site Plan.....	9
Figure 3	Existing Lane Configurations .....	10
Figure 4	Existing Sidewalks and Bicycle Routes .....	11
Figure 5	Existing Transit Routes and Transit Stops .....	12
Figure 6	Baseline 2023 Traffic Volumes .....	13
Figure 7	Background Development Locations .....	14
Figure 8	Total Background Development Site Traffic.....	16
Figure 9	2027 Future Background Traffic Volumes .....	17
Figure 10	2032 Future Background Traffic Volumes .....	18
Figure 11	2037 Future Background Traffic Volumes .....	19
Figure 12	Total Site Trips.....	21
Figure 13	2027 Future Total Traffic Volumes .....	22
Figure 14	2032 Future Total Traffic Volumes .....	23
Figure 15	2037 Future Total Traffic Volumes .....	24
Figure 16	Available Intersection Sight Distance .....	35
Figure 17	Sightline Assessment Field Observation (105 metres).....	36
Figure 18	Sightline Assessment Field Observation (110 metres).....	37
Figure 19	Sightline Assessment Field Observation (115 metres).....	38

## Appendices

Appendix A	Terms of Reference
Appendix B	Traffic Data
Appendix C	Background Developments
Appendix D	Transportation Tomorrow Survey 2016
Appendix E	Synchro Outputs
Appendix F	AutoTURN Circulation Review

# 1. Introduction

## 1.1 Retainer and Objective

GHD Limited was retained to prepare a Transportation Impact Study in support of a proposed residential development located on lands with the municipal address 720 Granite Court in the City of Pickering.

The site location is illustrated in **Figure 1**.

The purpose of this study is to:

- Establish baseline traffic conditions for the study area in 2023 and determine future background operating conditions for a future planning horizon in 2027, 2032, and 2037.
- Utilizing Institute of Transportation Engineer's (ITE) Trip Generation data and first principles to estimate the site trips generated by the proposed development and distribute the traffic to the adjacent road network.
- Determine future operating traffic conditions during the weekday peak periods through intersection capacity analysis.
- Review the number of proposed parking spaces in accordance with the City of Pickering's Zoning By-law.
- Provide Travel Demand Management (TDM) measures to encourage residents to reduce dependencies on single occupancy vehicle trips.
- Complete a sightline assessment of the proposed driveway location.
- Review the swept path of the expected design vehicles for the subject site.

The scope of work and terms of reference for the traffic study were confirmed with the City of Pickering and Durham Region via email correspondence. A copy of the correspondence is provided in **Appendix A**.

## 1.2 Study Team

The GHD team involved in the preparation of the study are:

- William Maria, P. Eng., Transportation Planning Lead
- Rafael Andrenacci, B.Eng., Transportation Planner
- James Emerson, B. Eng., Transportation Planner



Figure 1 Site Location

## 2. Site Characteristics

### 2.1 Study Area

The study intersections reflect the agreed terms of reference for the study and include:

- Whites Road and Bayly Street
- Whites Road and Granite Court/Oklahoma Drive
- Granite Court and the site access

### 2.2 Proposed Development Content

A site plan prepared was by onespace unlimited inc. and consists of a 12-storey high-rise building with a total of 261 dwelling units and both surface and underground parking.



Access to the subject site is proposed via a full-moves access on Granite Court.




Figure 2 Site Plan

### 3. Existing Conditions

#### 3.1 Existing Road Network

**Whites Road** is a north/south Type A arterial road under the jurisdiction of the Region of Durham with a four-lane cross-section from the north of the study area to the intersections of Granite Court/Oklahoma Drive. Whites Road is then reduced to a two-lane collector road under the jurisdiction of the City of Pickering south of Granite Court/Oklahoma Drive. Its intersection with Bayly Street is a signalized T-intersection with an auxiliary left-turn lane in the southbound direction and an auxiliary right-turn lane in the northbound direction. Its intersection with Granite Court/Oklahoma Drive is also signalized with an auxiliary left-turn lane in both the northbound and southbound directions and a right-turn lane in the southbound direction to transition to its two-lane cross-section. The posted speed limit along Whites Road is 60 km/h north of its intersection with Granite Court/Oklahoma Drive and 50 km/h south of it.

**Bayly Street** is an east/west Type A arterial road under the jurisdiction of the Region of Durham with a four-lane cross-section within the study area. The signalized T-intersection with Whites Road is signalized, with a left-turn lane and a right-turn lane in the westbound direction. The posted speed limit along Bayly Street is 60 km/h.

**Granite Court** is an east/west collector road under the jurisdiction of the City of Pickering with a two-lane cross-section within the study area. Its intersection with Whites Road is signalized with an auxiliary left-turn lane in the eastbound direction. East of Whites Road, Granite Court continues as Oklahoma Drive. The posted speed limit along Granite Court is 40 km/h.

**Oklahoma Drive** is an east/west collector road under the jurisdiction of the City of Pickering with a two-lane cross-section within the study area. Its intersection with Whites Road is signalized with auxiliary left-turn and right-turn lanes in the eastbound and westbound directions. The posted speed limit along Oklahoma Drive is 40 km/h.

The existing lane configurations at the study intersections is provided in the figure below.




Figure 3 Existing Lane Configurations

## 3.2 Pedestrian and Bicycle Routes

Sidewalks are provided on at least one side of the road throughout the study area, and include the south side of Bayly Street, the east side of Whites Road, the north side of Granite Court and along both sides of Oklahoma Drive.

Bike lanes are provided on both sides of the road along Granite Court.

The existing pedestrian and cycling amenities are illustrated in the following figure.



Figure 4 Existing Sidewalks and Bicycle Routes

## 3.3 Transit Services

Durham Region Transit (DRT) currently offers service along Route 120 (Whites) within the study area. The route operates between the Pickering GO Station in the east, towards the west along Bayly Street, south along West Shore Boulevard, west along Oklahoma Drive, and north along Whites Road towards Sunbird Trail. The route operates with a 30-minute headway throughout the week and weekends from 6:00 a.m. to 10:00 p.m..

The nearest transit stop is located at just east of the intersection of Whites Road and Granite Court/Oklahoma Drive for both directions approximately 160 and 220 metre walking distance from the lobby.

The existing transit routes and their associated bus stops are shown in **Figure 5**.



**Figure 5** Existing Transit Routes and Transit Stops

### 3.4 Existing Traffic Data

GHD contracted Ontario Traffic Inc. to collect updated turning movement counts at the existing study intersections. The baseline 2023 traffic volumes for the a.m. and p.m. peak hours are summarized in **Figure 6** with the updated counts conducted by Ontario Traffic Inc. provided in **Appendix B**. Signal timing plans also obtained from the Region of Durham and are provided in **Appendix B**.




Figure 6 Baseline 2023 Traffic Volumes

## 4. Future Background Traffic

### 4.1 Study Horizon Year

Future horizon years of 2027, 2032 and 2037 were selected for the analysis of future traffic conditions, generally corresponding with the MTO's Transportation Impact Study Guidelines of the year of full build-out, a period of five years post build-out, and a period of ten years post build-out. The horizon years were agreed and confirmed in the terms of reference with City and Region staff, while MTO staff were contacted but did not provide comments.

## 4.2 Corridor Growth

GHD applied a 1% growth rate along the study area roadways up to the year of full build-out and a 0.5% growth rate for 5 and 10-year post build-out. This growth rate was confirmed with Region of Durham staff.

## 4.3 Background Development Traffic

City staff requested that the following three background developments located near the subject site and would contribute additional traffic volumes to the study intersections be included in the study:

- 14-storey apartment building on the east side of Whites Road north of Kingston Road
- Stacked townhouse development located on the north side of Kingston Road west of Whites Road
- The new Shell service station at the northwest corner of Whites Road and Kingston Road.
- Development in the southwest corner of Whites Road and Kingston Road (603-643 & 645-699 Kingston Road)

The location of the four background developments are identified in **Figure 7** below.



**Figure 7** Background Development Locations


The proposed development at 603-643 & 645-699 Kingston Road results in a negative net trip generation along the study intersections as are result of the change in land use. As a conservative measure, the negative trip assignment from this development was not included in this study.

The Shell service station was not included as a background development as it has been constructed and site traffic from this development has been captured in the updated turning movement counts at the study intersections.

The proposed trip generation from each remaining background development is summarized in the table below, with the trip distribution for each site provided in **Appendix C**. The total site trips from each of the three background developments are provided in **Figure 8** and **Table 1**.

**Table 1** Background Development Traffic

Background Development	GFA/Unit Count	Peak Hour Trips					
		Weekday AM			Weekday PM		
		In	Out	Total	In	Out	Total
East side of Whites Road, north of Kingston Road	227 high-rise dwelling units (LUC 222)	18	51	69	51	31	82
North side of Kingston Road, west of Whites Road	88 townhouse dwelling units (LUC 220)	12	38	50	37	21	58
<b>Total</b>		<b>30</b>	<b>89</b>	<b>119</b>	<b>88</b>	<b>52</b>	<b>140</b>



**Figure 8 Total Background Development Site Traffic**



# 4.4 Future Background Traffic Volumes

The background traffic volumes for the 2027, 2032, and 2037 horizon years were derived by applying the respective growth rates to the study area road network and adding the total background development site traffic from **Figure 8**. The resulting 2027, 2032, and 2037 future background traffic volumes are summarized in **Figure 9**, **Figure 10**, and **Figure 11**.




Figure 9 2027 Future Background Traffic Volumes




Figure 10 2032 Future Background Traffic Volumes




Figure 11 2037 Future Background Traffic Volumes

## 5. Site Generated Traffic

### 5.1 Site Traffic Generation

The proposed redevelopment consists of a 12-storey high-rise building with a total of 261 dwelling units.

Trip generation for the residential and retail components were calculated using rates provided in the Institute of Transportation Engineer’s (ITE) Trip Generation Manual, 11th Edition using Land Use Code (LUC) 222 (Multifamily Housing – High-Rise) for the high-rise dwelling units.

As directed by Region staff, no additional reduction will be applied to the trip generation as an appropriate transit modal split is already included in the ITE Trip Generation rates.

**Table 2** below summarizes the estimated trip generation for the proposed development.

**Table 2** *Estimated Site Trips*

Land Uses	GFA (Dwelling Units)	Parameters	Peak Hour					
			Weekday AM			Weekday PM		
			In	Out	Total	In	Out	Total
High-Rise Residential (LUC 222)	261 units	Trip Ratio	26%	74%	100%	62%	38%	100%
		Gross Trips	20	56	76	56	35	91
<b>Total Primary Trips</b>			<b>20</b>	<b>56</b>	<b>76</b>	<b>56</b>	<b>35</b>	<b>91</b>

The proposed development is expected to generate a total of 76 new two-way trips consisting of 20 inbound and 56 outbound trips during weekday a.m. peak hour and 91 new two-way trips consisting of 56 inbound and 35 outbound trips during the weekday p.m. peak hour.

## 5.2 Site Traffic Distribution and Assignment

Site generated traffic for the residential development was distributed based on a review of the existing travel patterns and the 2016 Transportation Tomorrow Survey (TTS) data for residential trips along the Highway 7 corridor. We assigned trips to the study area intersections based on the most reasonable routes for vehicles, considering factors such as travel time and distance.

The directional split for the site traffic is provided in **Table 3** with the full 2016 TTS data calculation sheets provided in **Appendix D**.

The site generated traffic assignment to the study area road network for the weekday a.m. and p.m. peak hours provided in **Figure 12**.

**Table 3** *Directional Trip Distribution of Site Traffic*

Peak Period	Direction	North (Whites)	South (Whites)	East (Bayly)	East (Oklahoma)	West (Granite)
AM	Inbound	65%	5%	15%	5%	10%
	Outbound	70%	5%	10%	5%	10%
PM	Inbound	65%	5%	15%	5%	10%
	Outbound	55%	5%	20%	10%	10%




Figure 12 Total Site Trips

## 6. Future Total Traffic

The future total traffic conditions in the weekday a.m. and p.m. peak hours for the 2027, 2032, and 2037 planning horizon was derived by combining the projected future background traffic with the corresponding estimated site generated traffic. The resulting traffic volumes are presented in **Figure 13**, **Figure 14**, and **Figure 15**.




Figure 13 2027 Future Total Traffic Volumes




Figure 14 2032 Future Total Traffic Volumes




Figure 15 2037 Future Total Traffic Volumes

## 7. Capacity Analysis

The capacity analysis identifies how well the intersections and driveways are operating. The analysis contained within this report utilized the Highway Capacity Manual (HCM) 2000 procedure within the Synchro Version 10 Software package. The reported intersection volume-to-capacity ratios (v/c) are a measure of the saturation volume for each turning movement, while the levels-of-service (LOS) are a measure of the average delay for each turning movement. Queuing characteristics are reported as the predicted 95th percentile queue for each turning movement.

Both pedestrian crossing volumes and heavy vehicle proportions are included in the analyses. The peak hour factors from the historic counts were used to analyze existing and future traffic conditions.



The analysis includes identification and required modifications and improvements (if any) at intersections where the addition of background growth or background growth plus site-generated traffic volumes causes the following:

'Critical' intersections and movements for a signalized intersection include:

- V/C ratios for overall intersections operations, through movements, or shared through/turning movements increase to 0.85 or above;
- V/C ratios for exclusive movements increase to 0.95 or above; or
- 95<sup>th</sup> percentile queue length for individual movements that are projected to, or exceed, the storage length.

'Critical' intersections and movements for an unsignalized intersection include:

- Level of Services (LOS), based on average delay per vehicle, on individual movements greater than LOS "E"; or
- Queue length for individual movements that exceeds the lesser of 5 vehicles or the available queue storage.

The following tables summarize the HCM capacity results for the study intersections during the weekday a.m. and p.m. peak hours under existing (2023), future background (2027, 2032 and 2037) and future total (2027, 2032 and 2037) traffic conditions. The detailed calculation sheets are provided in **Appendix E**.

## 7.1 Whites Road and Bayly Street

Capacity analysis at this intersection during the weekday a.m. and p.m. peak hours for the existing, future background, and future total traffic conditions are summarized in the following table.

**Table 4 Capacity analysis of Whites Road and Bayly Street**

Scenario	AM Peak Hour		PM Peak Hour	
	V/C (LOS) seconds	95 <sup>th</sup> % Que.	V/C (LOS) seconds	95 <sup>th</sup> % Que
Existing 2023	<u>Overall: 0.55 (C) 25</u> WBL = 0.59 (D) 50 WBR = 0.29 (B) 12 NBT = 0.74 (C) 35 NBR = 0.08 (B) 19 SBL = 0.44 (C) 22 SBTL = 0.43 (C) 21	WBL = 40 m WBR = 35 m NBT = 75 m NBR = 5 m SBL = 85 m SBTL = 75 m	<u>Overall: 0.58 (C) 33</u> WBL = 0.62 (D) 51 WBR = 0.29 (B) 11 NBT = 0.69 (D) 51 NBR = 0.17 (F) 87 SBL = 0.52 (C) 23 SBTL = 0.52 (C) 21	WBL = 45 m WBR = 35 m NBT = 80 m NBR = 35 m SBL = 115 m SBTL = 105 m
Future Background 2027	<u>Overall: 0.57 (C) 26</u> WBL = 0.60 (D) 50 WBR = 0.31 (B) 12 NBT = 0.74 (C) 35 NBR = 0.09 (B) 19 SBL = 0.47 (C) 23 SBTL = 0.47 (C) 22	WBL = 40 m WBR = 35 m NBT = 75 m NBR = 5 m SBL = 90 m SBTL = 85 m	<u>Overall: 0.61 (D) 37</u> WBL = 0.62 (D) 51 WBR = 0.31 (B) 12 NBT = 0.70 (E) 58 NBR = 0.20 (F) 107 SBL = 0.55 (C) 24 SBTL = 0.56 (C) 23	WBL = 50 m WBR = 40 m NBT = 80 m NBR = 30 m SBL = 125 m SBTL = 110 m
Future Total 2027	<u>Overall: 0.59 (C) 27</u> WBL = 0.60 (D) 51 WBR = 0.33 (B) 13 NBT = 0.76 (C) 34 NBR = 0.10 (B) 20 SBL = 0.50 (C) 25 SBTL = 0.49 (C) 23	WBL = 40 m WBR = 40 m NBT = 75 m NBR = 5 m SBL = 95 m SBTL = 85 m	<u>Overall: 0.63 (D) 38</u> WBL = 0.64 (D) 51 WBR = 0.32 (B) 12 NBT = 0.71 (E) 58 NBR = 0.21 (F) 106 SBL = 0.59 (C) 26 SBTL = 0.58 (C) 24	WBL = 50 m WBR = 40 m NBT = 80 m NBR = 30 m SBL = 135 m SBTL = 120 m

Scenario	AM Peak Hour		PM Peak Hour	
	V/C (LOS) seconds	95 <sup>th</sup> % Que.	V/C (LOS) seconds	95 <sup>th</sup> % Que
Future Background 2032	<u>Overall: 0.59 (C) 26</u> WBL = 0.60 (D) 51 WBR = 0.33 (B) 13 NBT = 0.75 (C) 35 NBR = 0.09 (B) 19 SBL = 0.49 (C) 24 SBTL = 0.49 (C) 23	WBL = 40 m WBR = 40 m NBT = 80 m NBR = 5 m SBL = 95 m SBTL = 85 m	<u>Overall: 0.63 (D) 38</u> WBL = 0.63 (D) 51 WBR = 0.33 (B) 12 NBT = 0.71 (E) 58 NBR = 0.21 (F) 102 SBL = 0.58 (C) 26 SBTL = 0.58 (C) 24	WBL = 50 m WBR = 45 m NBT = 85 m NBR = 35 m SBL = 130 m SBTL = 120 m
Future Total 2032	<u>Overall: 0.61 (C) 27</u> WBL = 0.61 (D) 51 WBR = 0.34 (B) 14 NBT = 0.76 (C) 34 NBR = 0.11 (B) 20 SBL = 0.52 (C) 26 SBTL = 0.52 (C) 25	WBL = 40 m WBR = 45 m NBT = 75 m NBR = 5 m SBL = 100 m SBTL = 90 m	<u>Overall: 0.65 (D) 38</u> WBL = 0.64 (D) 51 WBR = 0.34 (B) 12 NBT = 0.72 (E) 58 NBR = 0.23 (F) 99 SBL = 0.61 (C) 27 SBTL = 0.61 (C) 25	WBL = 50 m WBR = 45 m NBT = 85 m NBR = 35 m SBL = 150 m SBTL = 125 m
Future Background 2037	<u>Overall: 0.60 (C) 27</u> WBL = 0.61 (D) 51 WBR = 0.34 (B) 13 NBT = 0.75 (C) 34 NBR = 0.10 (B) 19 SBL = 0.51 (C) 25 SBTL = 0.51 (C) 24	WBL = 40 m WBR = 45 m NBT = 80 m NBR = 5 m SBL = 100 m SBTL = 90 m	<u>Overall: 0.64 (D) 38</u> WBL = 0.64 (D) 51 WBR = 0.34 (B) 12 NBT = 0.72 (E) 58 NBR = 0.22 (F) 99 SBL = 0.60 (C) 27 SBTL = 0.60 (C) 25	WBL = 50 m WBR = 45 m NBT = 85 m NBR = 35 m SBL = 145 m SBTL = 125 m
Future Total 2037	<u>Overall: 0.62 (C) 28</u> WBL = 0.61 (D) 51 WBR = 0.36 (B) 14 NBT = 0.76 (C) 34 NBR = 0.11 (B) 20 SBL = 0.54 (C) 27 SBTL = 0.54 (C) 25	WBL = 45 m WBR = 45 m NBT = 75 m NBR = 10 m SBL = 105 m SBTL = 95 m	<u>Overall: 0.66 (D) 39</u> WBL = 0.65 (D) 51 WBR = 0.35 (B) 13 NBT = 0.72 (E) 58 NBR = 0.24 (F) 96 SBL = 0.64 (C) 29 SBTL = 0.64 (C) 26	WBL = 55 m WBR = 50 m NBT = 85 m NBR = 35 m SBL = 160 m SBTL = 140 m

Under existing traffic conditions, the overall intersection has a reported v/c ratio of 0.55 LOS C and 0.58 LOS C during the a.m. and p.m. peak hours respectively. The intersection operates without any critical movements during the a.m. and p.m. peak hours.

With the addition of corridor growth and the background development site traffic under the 2027 future background horizon period, the overall reported v/c of the intersection is expected to increase to 0.57 LOS C and 0.62 LOS D during the a.m. and p.m. peak hours, respectively. The intersection continues to operate without any critical movements during the a.m. and p.m. peak hours.

Under the 2027 future total traffic condition, with the addition of site traffic, the overall v/c ratio of the intersection increases slightly to 0.59 LOS C and 0.63 LOS D during the a.m. and p.m. peak hours, respectively. The intersection continues to operate without any critical movements during the a.m. and p.m. peak hours with the proposed site traffic having a minimal impact on the operation of the intersection.

With continued corridor growth and the background development site traffic at the 2032 future background traffic scenario, the overall reported v/c of the intersection is expected to increase to 0.59 LOS C and 0.63 LOS D during the a.m. and p.m. peak hours, respectively, in comparison the 2027 future background condition.

Under the 2032 future total traffic condition, with the addition of site traffic, the intersection continues to operate at acceptable levels during both peak hours with the overall v/c ratios increasing slightly to 0.61 LOS C and 0.65 LOS D during the a.m. and p.m. peak hours, and with no reported critical movements.

With corridor growth and the background development site traffic under the 2037 future background traffic scenario, the overall reported v/c of the intersection is expected to increase to 0.60 LOS C during the a.m. peak hours and 0.64 LOS D during the p.m. peak hour in comparison to the 2032 future background condition. No critical movements are expected.

Under the 2037 future total traffic condition, with the addition of site traffic, the intersection continues to operate at acceptable levels of service during both peak hours with the overall intersection v/c at 0.62 LOS C and 0.66 LOS D during the a.m. and p.m. peak hours, and again with no reported critical movements.

No geometric improvements were identified at this intersection to accommodate the proposed development.

## 7.2 Whites Road and Granite Court/Oklahoma Drive

Capacity analysis for this intersection during the weekday a.m. and p.m. peak hours for the existing, future background, and future total traffic conditions are summarized in the following table.

**Table 5 Capacity analysis of Whites Road and Granite Court/Oklahoma Drive**

Scenario	AM Peak Hour		PM Peak Hour	
	V/C (LOS) seconds	95 <sup>th</sup> % Que.	V/C (LOS) seconds	95 <sup>th</sup> % Que
Existing 2023	<u>Overall: 0.39 (C) 28</u>		<u>Overall: 0.66 (C) 26</u>	
	EBL = 0.76 (D) 53	EBL = 50 m	EBL = 0.70 (C) 24	EBL = 110 m
	EBT = 0.13 (D) 36	EBT = 15 m	EBT = 0.08 (B) 14	EBT = 20 m
	WBL = 0.03 (C) 35	WBL = 5 m	WBL = 0.02 (B) 16	WBL = 5 m
	WBT = 0.16 (D) 36	WBT = 20 m	WBT = 0.07 (B) 16	WBT = 15 m
	WBR = 0.22 (D) 37	WBR = 15 m	WBR = 0.13 (B) 17	WBR = 15 m
	NBL = 0.02 (A) 6	NBL = 5 m	NBL = 0.03 (C) 21	NBL = 5 m
	NBT = 0.14 (A) 6	NBT = 25 m	NBT = 0.17 (C) 23	NBT = 30 m
	SBL = 0.27 (A) 9	SBL = 35 m	SBL = 0.56 (C) 29	SBL = 90 m
	SBT = 0.07 (A) 8	SBT = 20 m	SBT = 0.26 (B) 20	SBT = 40 m
SBR = 0.25 (C) 31	SBR = 40 m	SBR = 0.12 (D) 51	SBR = 20 m	
Future Background 2027	<u>Overall: 0.40 (C) 30</u>		<u>Overall: 0.60 (C) 26</u>	
	EBL = 0.76 (D) 53	EBL = 55 m	EBL = 0.86 (D) 46	EBL = 105 m
	EBT = 0.14 (D) 35	EBT = 15 m	EBT = 0.12 (C) 25	EBT = 25 m
	WBL = 0.03 (C) 34	WBL = 5 m	WBL = 0.10 (D) 46	WBL = 10 m
	WBT = 0.16 (D) 35	WBT = 20 m	WBT = 0.36 (D) 48	WBT = 25 m
	WBR = 0.23 (D) 36	WBR = 15 m	WBR = 0.13 (D) 47	WBR = 20 m
	NBL = 0.02 (A) 6	NBL = 5 m	NBL = 0.02 (B) 12	NBL = 5 m
	NBT = 0.15 (A) 7	NBT = 25 m	NBT = 0.12 (B) 12	NBT = 25 m
	SBL = 0.29 (B) 11	SBL = 40 m	SBL = 0.40 (A) 8	SBL = 20 m
	SBT = 0.08 (A) 10	SBT = 20 m	SBT = 0.19 (A) 5	SBT = 15 m
SBR = 0.26 (D) 38	SBR = 50 m	SBR = 0.13 (B) 11	SBR = 5 m	

<p>Future Total 2027</p>	<p><u>Overall: 0.45 (C) 34</u>            EBL = 0.80 (D) 51            EBT = 0.12 (C) 31            WBL = 0.03 (C) 30            WBT = 0.14 (C) 31            WBR = 0.23 (C) 32            NBL = 0.03 (A) 8            NBT = 0.16 (A) 9            SBL = 0.31 (B) 14            SBT = 0.09 (B) 13            SBR = 0.28 (D) 53</p>	<p>EBL = 65 m            EBT = 15 m            WBL = 5 m            WBT = 20 m            WBR = 10 m            NBL = 5 m            NBT = 30 m            SBL = 45 m            SBT = 25 m            SBR = 60 m</p>	<p><u>Overall: 0.62 (C) 28</u>            EBL = 0.91 (D) 54            EBT = 0.13 (C) 25            WBL = 0.10 (D) 46            WBT = 0.38 (D) 48            WBR = 0.13 (D) 46            NBL = 0.03 (B) 12            NBT = 0.12 (B) 13            SBL = 0.40 (A) 7            SBT = 0.19 (A) 5            SBR = 0.16 (B) 11</p>	<p>EBL = 125 m            EBT = 25 m            WBL = 10 m            WBT = 30 m            WBR = 20 m            NBL = 5 m            NBT = 25 m            SBL = 20 m            SBT = 15 m            SBR = 10 m</p>
<p>Future Background 2032</p>	<p><u>Overall: 0.41 (C) 31</u>            EBL = 0.76 (D) 52            EBT = 0.14 (C) 35            WBL = 0.03 (C) 34            WBT = 0.16 (D) 35            WBR = 0.24 (D) 36            NBL = 0.03 (A) 6            NBT = 0.16 (A) 7            SBL = 0.30 (B) 12            SBT = 0.09 (B) 10            SBR = 0.27 (D) 43</p>	<p>EBL = 55 m            EBT = 15 m            WBL = 5 m            WBT = 20 m            WBR = 15 m            NBL = 5 m            NBT = 25 m            SBL = 45 m            SBT = 25 m            SBR = 55 m</p>	<p><u>Overall: 0.61 (C) 26</u>            EBL = 0.87 (D) 47            EBT = 0.13 (C) 25            WBL = 0.10 (D) 46            WBT = 0.36 (D) 48            WBR = 0.13 (D) 47            NBL = 0.03 (B) 12            NBT = 0.13 (B) 13            SBL = 0.42 (A) 7            SBT = 0.20 (A) 5            SBR = 0.13 (B) 10</p>	<p>EBL = 110 m            EBT = 25 m            WBL = 10 m            WBT = 25 m            WBR = 20 m            NBL = 5 m            NBT = 25 m            SBL = 20 m            SBT = 15 m            SBR = 5 m</p>
<p>Future Total 2032</p>	<p><u>Overall: 0.46 (D) 35</u>            EBL = 0.80 (D) 51            EBT = 0.13 (C) 31            WBL = 0.03 (C) 30            WBT = 0.14 (C) 31            WBR = 0.24 (C) 32            NBL = 0.03 (A) 8            NBT = 0.17 (A) 9            SBL = 0.32 (B) 15            SBT = 0.10 (B) 14            SBR = 0.28 (E) 58</p>	<p>EBL = 65 m            EBT = 15 m            WBL = 5 m            WBT = 20 m            WBR = 15 m            NBL = 5 m            NBT = 30 m            SBL = 50 m            SBT = 30 m            SBR = 60 m</p>	<p><u>Overall: 0.63 (C) 28</u>            EBL = 0.92 (D) 55            EBT = 0.13 (C) 24            WBL = 0.10 (D) 46            WBT = 0.38 (D) 48            WBR = 0.13 (D) 46            NBL = 0.03 (B) 12            NBT = 0.13 (B) 13            SBL = 0.42 (A) 7            SBT = 0.20 (A) 4            SBR = 0.16 (B) 11</p>	<p>EBL = 125 m            EBT = 25 m            WBL = 10 m            WBT = 25 m            WBR = 20 m            NBL = 5 m            NBT = 25 m            SBL = 20 m            SBT = 15 m            SBR = 10 m</p>
<p>Future Background 2037</p>	<p><u>Overall: 0.42 (C) 33</u>            EBL = 0.77 (D) 53            EBT = 0.14 (C) 34            WBL = 0.03 (C) 34            WBT = 0.16 (C) 35            WBR = 0.24 (D) 36            NBL = 0.03 (A) 6            NBT = 0.16 (A) 7            SBL = 0.31 (B) 13            SBT = 0.09 (B) 11            SBR = 0.28 (D) 49</p>	<p>EBL = 55 m            EBT = 15 m            WBL = 5 m            WBT = 20 m            WBR = 15 m            NBL = 5 m            NBT = 25 m            SBL = 50 m            SBT = 25 m            SBR = 60 m</p>	<p><u>Overall: 0.63 (C) 26</u>            EBL = 0.87 (D) 46            EBT = 0.13 (C) 24            WBL = 0.10 (D) 46            WBT = 0.37 (D) 48            WBR = 0.14 (D) 46            NBL = 0.03 (B) 12            NBT = 0.13 (B) 13            SBL = 0.44 (A) 7            SBT = 0.21 (A) 5            SBR = 0.13 (A) 10</p>	<p>EBL = 110 m            EBT = 25 m            WBL = 10 m            WBT = 25 m            WBR = 20 m            NBL = 5 m            NBT = 25 m            SBL = 25 m            SBT = 15 m            SBR = 5 m</p>

Future Total 2037	<u>Overall: 0.48 (D) 37</u>		<u>Overall: 0.65 (C) 28</u>	
	EBL = 0.8 (D) 51	EBL = 65 m	EBL = 0.93 (E) 55	EBL = 130 m
	EBT = 0.13 (C) 31	EBT = 15 m	EBT = 0.13 (C) 24	EBT = 25 m
	WBL = 0.02 (C) 30	WBL = 5 m	WBL = 0.10 (D) 46	WBL = 10 m
	WBT = 0.14 (C) 31	WBT = 20 m	WBT = 0.38 (D) 48	WBT = 30 m
	WBR = 0.24 (C) 32	WBR = 10 m	WBR = 0.14 (D) 46	WBR = 20 m
	NBL = 0.03 (A) 8	NBL = 5 m	NBL = 0.03 (B) 12	NBL = 10 m
	NBT = 0.17 (A) 9	NBT = 30 m	NBT = 0.13 (B) 13	NBT = 25 m
	SBL = 0.33 (B) 16	SBL = 55 m	SBL = 0.44 (A) 6	SBL = 25 m
	SBT = 0.1 (B) 14	SBT = 30 m	SBT = 0.21 (A) 4	SBT = 15 m
SBR = 0.29 (E) 64	SBR = 65 m	SBR = 0.16 (B) 10	SBR = 10 m	

Under existing traffic conditions, the overall intersection has a reported v/c ratio of 0.39 LOS C and 0.66 LOS C during the a.m. and p.m. peak hours respectively. The intersection is operating with acceptable levels of delay for all individual movements during both peak hours.

With the addition of corridor growth and the background development site traffic at the 2027 future background horizon scenario, the overall reported v/c of the intersection is expected to increase to 0.40 LOS C during the a.m. peak hour and to 0.60 LOS C during the p.m. peak hour. No critical movements are reported in either peak hour.

Under the 2027 future total traffic condition, with the addition of site traffic, the intersection continues to operate at satisfactory levels with the overall v/c ratio of the intersection increasing to 0.45 LOS C during the a.m. peak hour and to 0.62 LOS C during the p.m. peak hour. The intersection continues to operate without any critical movements.

With continued corridor growth and background development site traffic, the overall reported v/c of the intersection increases to 0.41 LOS C during the a.m. peak hour and to 0.61 LOS C during the p.m. peak hour.

Under the 2032 future total traffic condition, with the addition of site traffic, the intersection continues to operate acceptable v/c ratios and delays during both peak hours with the a.m. peak hour increasing from 0.41 to 0.46 LOS D and the p.m. peak hour from 0.61 to 0.63 LOS C. No critical movements were reported in the analysis for either peak hour.

With corridor growth and the background development site traffic under the 2037 future background traffic scenario, the overall reported v/c of the intersection is expected to increase to 0.42 LOS C during the a.m. peak hour and 0.63 LOS C during the p.m. peak hour in comparison to the 2032 future background condition. No critical movements were reported.

Under the 2037 future total traffic condition, with the addition of site traffic, the intersection continues to operate at acceptable levels of service during both peak hours with the overall intersection v/c at 0.48 LOS D and 0.65 LOS C during the a.m. and p.m. peak hours, and again with no reported critical movements.

The existing westbound left turn 95<sup>th</sup> percentile queue length is reported at 110 metres during the p.m. peak under existing conditions based on a volume of 387 vehicles. This queue is currently extending beyond the location of the proposed access from the subject site to Granite Court. This is an existing condition and based on the available frontage along Granite Court and sightline issues on Granite Court due to the bridge over the rail line, the driveway cannot be located further west to be located beyond the queue. The subject site is expected to add an additional two vehicle lengths to the 95<sup>th</sup> percentile queue length or 15 metres during p.m. peak hour which is the design condition.

What the software does not account for is courtesy gaps as vehicles travelling on Granite Court approach Whites Road which will provide additional opportunities for vehicles exiting the site to enter the traffic flow on Granite Court.

No geometric improvements were identified at this intersection to accommodate the proposed development.

## 7.3 Granite Court and the Site Access

Capacity analysis at this intersection during the weekday a.m. and p.m. peak hours for the future total traffic conditions are summarized in the following table.

**Table 6 Capacity analysis of Granite Court and the Site Access**

Scenario	AM Peak Hour		PM Peak Hour	
	V/C (LOS) seconds	95 <sup>th</sup> % Que.	V/C (LOS) seconds	95 <sup>th</sup> % Que
Future Total 2027	EBTL = 0 (A) 0 WBTR = 0.28 (A) 0 SBLR = 0.14 (C) 15	EBTL = 0 m WBTR = 0 m SBLR = 5 m	EBTL = 0 (A) 0 WBTR = 0.20 (A) 0 SBLR = 0.11 (C) 17	EBTL = 5 m WBTR = 0 m SBLR = 5 m
Future Total 2032	EBTL = 0 (A) 0 WBTR = 0.28 (A) 0 SBLR = 0.14 (C) 15	EBTL = 0 m WBTR = 0 m SBLR = 5 m	EBTL = 0 (A) 0 WBTR = 0.20 (A) 0 SBLR = 0.11 (C) 17	EBTL = 5 m WBTR = 0 m SBLR = 5 m
Future Total 2037	EBTL = 0 (A) 0 WBTR = 0.29 (A) 0 SBLR = 0.15 (C) 16	EBTL = 0 m WBTR = 0 m SBLR = 5 m	EBTL = 0 (A) 0 WBTR = 0.20 (A) 0 SBLR = 0.11 (C) 17	EBTL = 5 m WBTR = 0 m SBLR = 5 m

Under future total conditions, the proposed unsignalized site access on Granite Court is expected to operate with a maximum delay of 16 seconds during the a.m. peak hour for the outbound approach and a maximum delay of 17 seconds during the p.m. peak hour. The 95<sup>th</sup> percentile queue length for the outbound movement is reported at one vehicle however, due to the eastbound queues on Granite Court at Whites Road, the queues and delays exiting the site may be longer depending on the availability of gaps on Granite Court.

It is suggested that signage be provided on Granite Court ahead of the proposed driveway to advise drivers not to block the driveway.

## 8. Parking Review

### 8.1 Existing City of Pickering Zoning By-law

#### 8.1.1 Vehicular Parking

The subject site is governed by the City of Pickering’s Zoning By-law 2511, with the minimum parking requirement found in Section 5.21.1. The minimum By-law requirement for the subject site is as follows:

- Apartment dwellings:
  - 1.75 spaces per unit for residents and visitors

The minimum parking required for the proposed development is as follow:

- Apartment dwellings:
  - 1.75 parking space per unit x 261 units = 457 spaces

In total, 457 vehicle parking spaces are required under the City’s current Zoning By-law for both residents and visitors.

### 8.2 Parking Provision

The subject site proposes to provide a total of 393 vehicle parking spaces, consisting of 327 resident parking spaces and 66 visitor parking spaces, a shortfall of 64 spaces from the current Zoning By-law requirement.

#### 8.2.1 Draft Pickering Zoning By-law

The City of Pickering has published a first draft of the Comprehensive Zoning By-law, dated May 2022, and included update parking requirements. The updated parking space requirements are found in Section 5.2, Table 5.1. of the

draft report and requires a minimum of 1.25 resident spaces per unit plus 0.25 visitor spaces per unit for apartment dwellings located outside of the City Centre.

The proposed parking requirement rates will bring the City’s parking rates in line with surrounding municipalities including Ajax, Whitby, and Whitchurch-Stouffville, as summarized in the table below.

**Table 7 Parking Requirements in Surrounding Municipalities)**

Municipality	Resident Requirement (spaces per dwelling unit)	Visitor Requirement (spaces per dwelling unit)	Total Rate (spaces per dwelling unit)	Source
Ajax	1.25	0.25	1.5	Zoning By-law 95-2003, Section 5.10.1 Downtown Central Area Zones and Village Core Mixed Use Zones
Whitby	1.25	0.25	1.5	Zoning By-law 1784, Section 4A, Table 4A(1)
Whitchurch-Stouffville	1.25	0.25	1.5	By-law 2010-001-ZO, Section 3.23.1

## 8.2.2 2016 Transportation Tomorrow Survey Data

GHD has also reviewed the 2016 TTS data of vehicle ownership per apartment dwelling units in the City of Pickering. The data is summarized in the table below and indicates that the average vehicle ownership within the city is 1.05 vehicles per apartment unit.

**Table 8 Pickering Vehicle Ownership TTS Data for Apartments**

Vehicles per Household	Number of Households	Total number of vehicles
0 vehicles	675	0
1 vehicle	2555	2555
2 vehicles	829	1658
3 vehicles	32	4309
<b>Total</b>	<b>4091</b>	<b>4309</b> <b>(1.05 vehicles per household)</b>

The 2016 TTS data confirms that the proposed residential rate of 1.25 spaces per unit is more in line with more recent demand for parking with the city which for 2016 was surveyed at 1.05 vehicles per apartment unit.

## 8.3 Parking Assessment

Providing off-street residential parking influences a commuter choice on whether to drive or choose alternate forms of transportation. Providing more parking in general leads to a higher percentage of auto ownership and auto usage as well. Changing travel behaviour is best done when a prospective buyer is looking to purchase a unit and providing the opportunity for a prospective buyer to easily purchase a parking space either through making it affordable, at no additional cost, or having an excess in number of spaces available to purchase can introduce travel behaviour into an area that once established is hard to change.

Accordingly, the subject site proposes to provide parking at a rate that is in line with the draft Pickering Zoning By-Law and supported by the current parking demand trends of residents in the city and considering that reducing parking and vehicle ownership is a crucial component of achieving climate change adaption and environmental protection goals and reducing traffic related air pollutant and greenhouse gas emissions.

The proposed Travel Demand Management (TDM), as outlined in Section 9 of the report including planning and design, walking and cycling, transit, parking and education and promotion to make alternatives more competitive to

driving, are expected to reduce the dependency on auto trips and meet the anticipated demand for resident parking and avoid providing an excessive supply of parking for the site.

Considering that the site is isolated from the surrounding residential neighbourhoods and available on-street parking, it is unlikely that in the event parking is not available on-site, that it will result in overflow onto local area streets.

## **9. Travel Demand Management**

### **9.1 Travel Demand Management**

Travel Demand Management (TDM) refers to a variety of strategies to reduce congestion, minimize the number of single-occupant vehicles, encourage non-auto modes of travel, and reduce vehicle dependency to create a sustainable transportation system. TDM strategies have multiple benefits including the following:

- Reduced auto-related emissions to improve air quality;
- Decreased traffic congestion to reduce travel time;
- Increased travel options for businesses and commuters;
- Reduced personal transportation costs and energy consumptions; and
- Support Provincial smart growth objectives.

The combined benefits listed above will assist in creating a more active and livable community through improvements to overall active transportation standards for the local businesses and surrounding community.

### **9.2 Existing TDM Opportunities**

#### **9.2.1 Walking**

Sidewalks are currently provided throughout the study area along at least one side of all roadways. Signalized pedestrian crosswalks are currently provided on all legs of the intersections of Whites Road at Bayly Street and at Whites Road and Granite Court/Oklahoma Drive and provides access to the transit stops located east of the subject site and the intersection.

#### **9.2.2 Transit**

Transit service is currently provided within the study area by Durham Region Transit's (DRT) Route 120 (Whites) with 30-minute headways. The route operates between the Pickering GO and the intersection of Whites Road at Sunbird Trail. The nearest transit stop is located at just east of the intersection of Whites Road and Granite Court/Oklahoma Drive for both directions.



## 9.3 Recommended TDM Measures

The table below summarizes the recommended TDM strategies for the subject site.

**Table 9 Recommended TDM Strategies**

TDM Measure	Responsibility	Cost	Note
<b>Hard Measures</b>			
Pedestrian connections	Applicant	Integrated into the overall development cost	Site plan includes a walkway system providing a connection to the municipal sidewalks.  Enhanced pedestrian amenities will also be provided on-site, including but not limited to benches, landscaping and lighting.
Public Transit Access	Applicant	Integrated into the overall development cost	The subject site is located within walking distance of the transit stops east of Whites Road and Granite Court/Oklahoma Drive
<b>Soft Measures</b>			
Transit incentives (i.e. PRESTO cards)	Applicant	Provide a suggested fare card value of \$150.00 per unit.	To be provided with the purchase of each unit.
Information packages (DRT, GO schedules, cycling maps)	Applicant	To be determined.	Distributed at the sales office with Purchase and Sales Agreement
Communication strategy and physical location to deliver PRESTO cards and information packages	Applicant	To be determined.	At 50% occupancy, the applicant is responsible for assisting with distribution of information flyers to residents; for the coordination and for providing a venue for the distribution of Information Packets and PRESTO cards.
Unbundled vehicle parking sales	Applicant	Integrated into the overall development cost	Proposed to unbundle the sales of the parking space and unit to provide residents with the true cost of the parking space.

## 10. Site Plan Review

The City of Pickering's Standard for accesses is found in Drawing P-605, Medium to high density residential, commercial, and industrial driveway access. The City's standards provide a minimum and maximum access width and radius requirement for two-way residential driveways. Driveways are required to be designed with a minimum width of 6.5 metres and a maximum of 12 metres and the radius is required to be a minimum of 7.5 metres and a maximum of 9 metres.

The proposed site access has a width of 7.3 metres with an inbound and outbound radius of 7.5 metres, meeting the City's requirement.

## 11. Vehicle Swept Path Analysis

GHD undertook a Vehicle Swept Path Analysis to assess the proposed site plan's ability to accommodate the required turning movements of a waste collection vehicle, a Medium Sized Unit (MSU) Truck, and a TAC Passenger Vehicle. The results of the analysis, which are provided in **Appendix F**, illustrate that the site can sufficiently accommodate the aforementioned design vehicles.

## 12. Sightline Review

Adjacent to the proposed site, Granite Court has a posted speed limit of 40 km/h and with a slight change in the vertical profile of the road due to the crest of a bridge located to the west of the proposed site access location. For the purpose of Stopping Sight Distance requirements a design speed of 50 km/h was used for the assessment on Granite Court based on the 40 km/h posted speed limit.

Per Transportation Association of Canada's Geometric Design Guide for Canadian Roads (TAC GDGCR) Table 2.5.2, the minimum stopping sight-distance for level roadways with a design speed of 50 km/h is 65 metres for level roadways.

Section 9.9 of the TAC GDCR provides intersection sight distances for different scenarios, with the following scenarios used to complete the intersection sight distance analysis:

- Case B1 – Left turn from the minor road
- Case B2 – Right turn from the minor road
- Case F – Left turns from the major road

For the purpose of the assessment, the minor road is assumed to be the site driveway.

A vehicle entering the major road (Granite Court) from the site access is assumed to stop a distance of approximately 4.5 to 5.4 metres to the pavement edge of Granite Court as recommended by TAC. In this stopped position, the driver will be required to look left and right in order to perceive and react to approaching vehicles prior to initiating a turning movement onto the intersecting drive aisle.

The required intersection sight distances are provided in TAC GDGCR Tables 9.9.4, 9.9.6 and 9.9.12 for passenger vehicles turning left from stop, turning right from stop, or turning left from the major road, respectively, and are summarized in the following table. GHD conducted a field study of the available sight distances along Granite Court towards the vertical crest on the road due to the existing bridge. The sightline was measured from a point 4.5 meters back from the edge of the road at the location of the proposed driveway in order for a driver to see an approaching object 1.3 metres in height representing a vehicle. The required intersection sight distances summarized in the table below are based on a 50 km/h design speed along the major road.

**Table 10** *Intersection Sight Distance Requirement*

Case (Design Speed of 50 km/h)	Required Intersection Sight Distance for Passenger Cars (TAC 2017)	Available Intersection Sight Distance (Horizontal)	TAC Reference
B1: Vehicles turning left from stop	105 m	>105 m	Table 9.9.4
B2: Vehicles turning right from stop	95 m	>105 m	Table 9.9.6
F: Left turns from the major road	80 m	>105 m	Table 9.9.12

The available sight distances along Granite Court to the east and the west of the proposed site access meet the minimum required stopping sight distance for a 50 km/h design speed.

The sightline for a vehicle exiting the site and turning left is illustrated in **Figure 16**. Taking into consideration that sightline distance requirements for a left-turn (Case B1) has the greatest required intersection sight distance, if the available sight distance provided meets the minimum requirement for Case B1, the minimum requirement for Case B2 and F are also met.



**Figure 16** *Available Intersection Sight Distance*

The results from the field study are provided in **Figure 17**, **Figure 18**, and **Figure 19**. The study confirms that an approaching object 1.3 metres in height (the centre of the top circle) can be seen at a distance of 105 metres from a vehicle in a stopped position in the driveway (**Figure 17**). The sightline assessment was also completed at a distance of 110 and 115 metres, **Figure 18** and **Figure 19** respectively, and confirms that an oncoming vehicle can also be observed from those distances.



**Figure 17** *Sightline Assessment Field Observation (105 metres)*



**Figure 18** *Sightline Assessment Field Observation (110 metres)*



**Figure 19** *Sightline Assessment Field Observation (115 metres)*

The proposed location of the site driveway provides the required vertical and horizontal sightlines for a 50 km/h design speed and 40 km/h posted speed limit.

## **13. Conclusion**

The site plan, prepared by onespace unlimited inc., consists of a 12-storey high-rise building with a total of 262 dwelling units.

Access to the subject site is proposed via a single full-moves driveway onto Granite Court located west of the intersection of Whites Road and Granite Court/Oklahoma Drive.

The proposed new development is expected to generate a total of 76 new two-way trips consisting of 20 inbound and 56 outbound trips during weekday a.m. peak hour and 91 new two-way trips consisting of 56 inbound and 35 outbound trips during the weekday p.m. peak hour.

Under existing, future background, and future total conditions, all study intersections are operating within capacity.

Application of the current City of Pickering's By-Law parking rates to the subject site results in a requirement of 457 vehicle parking spaces, shared between residents and visitors.

The subject site provides a total of 393 parking spaces for vehicles (1.25 spaces per unit for residents, 0.25 spaces per unit for visitors), a shortfall of 64 parking spaces from the By-law requirement. The proposed rates for the subject site are in line with the City's Draft Comprehensive Zoning By-law rates found in adjacent municipalities.

A series of Transportation Demand Management (TDM) measures are proposed for the site to reduce dependency on single-occupancy vehicle trips by encouraging residents to explore alternative modes of transportation. These measures include:

- Improved pedestrian and cycling connectivity to the municipal networks, to make it easy and safe for people to walk or bike to their destination.
- Bicycle parking for both residents and visitors
- Unbundled vehicle parking
- Transit Incentives through Presto Passes
- Communication strategy and information packages

These measures will not only help reduce traffic congestion and air pollution, but also promote a healthier and more active lifestyle for the residents.

The City of Pickering's Standard for accesses is found in Drawing P-605, Medium to high density residential, commercial, and industrial driveway access and states that the minimum and maximum access width requirement for two-way residential driveways ranges from 6.5 to 12 metres and the radius is required to be between 7.5 and 9 metres. The proposed site access has a width of 7.3 metres with an inbound and outbound radius of 7.5 metres, meeting the City's requirement.

A Vehicle Swept Path Analysis was undertaken to assess the site's ability to accommodate the required turning movements of a waste collection truck, an MSU Truck and a Passenger vehicle as per TAC design guidelines and confirmed that the site can sufficiently accommodate the aforementioned design vehicles.

A sightline assessment at the proposed driveway location confirmed that sufficient sightlines are available to satisfy the requirements for a 50 km/h design speed and a 40 km/h posted speed.

# Appendices



# **Appendix A**

**Terms of Reference**

## Raf Andrenacci

---

**From:** Zahoor, Nadeem <nzahoor@pickering.ca>  
**Sent:** Wednesday, September 28, 2022 9:17 AM  
**To:** Glyn Reedman (InTouch); Raf Andrenacci  
**Cc:** Will Maria  
**Subject:** RE: 720 Granite Court - Terms of Reference

Hi Raf,

Overall I am good with the proposed terms of reference. I have couple of comments below;

- Please include a sight line review at the proposed access in the TIS.
- For the future background developments, please contact Nilesh Surti, Manager Urban Design. His email address is [nsurti@pickering.ca](mailto:nsurti@pickering.ca)

Thank you  
Nadeem

---

**From:** Glyn Reedman <Glyn.Reedman@Durham.ca>  
**Sent:** Tuesday, September 27, 2022 3:29 PM  
**To:** Raf Andrenacci <Raf.Andrenacci@ghd.com>; Zahoor, Nadeem <nzahoor@pickering.ca>; Lawrence, Morgan (MTO) <Morgan.Lawrence@ontario.ca>  
**Cc:** Will Maria <William.Maria@ghd.com>  
**Subject:** RE: 720 Granite Court - Terms of Reference

Hi Raf.

Our comments are as follows on your proposed Terms of Reference:

1. The TIS should follow the Region's TIS guidelines. Please advise me if you require a copy of the Region's Traffic Impact Study Guidelines, including the requirements for Synchro analysis (Chapter 9 in the [Design Specifications for Traffic Control Devices, Pavement Marking, Signage and Roadside Protection](#)).
2. The most current intersection turning movement counts on the Regional roads (as well as ATR counts and AADT data) can be downloaded from our web site through the interactive [traffic counts map](#). Traffic Signal timings are available for purchase from our Traffic Engineering & Operations Division ([traffic@durham.ca](mailto:traffic@durham.ca) 905-666-8116).
3. The City of Pickering will be able to advise on background developments that need to be included in the TIS.
4. As noted, please use the ITE Trip Generation Manual 11<sup>th</sup> Edition for trip generation rates. Please note that no additional reduction should be made for modal splits for this site, as these are already built into the ITE rates.

5. Please include the intersection of Whites Road and Bayly St in the TIS.
6. The opening year of 2027 with 5 and 10 year horizons are acceptable to the Region.
7. Background annual traffic growth rates should be agreed before they are used in the TIS.
8. Existing conditions for all travel modes should be noted by way of a site visit and any observations noted in the TIS. Observations of existing traffic operations, including queue lengths, should be used to validate the existing conditions Synchro analysis.
9. As noted, please include transit, active transportation, and TDM discussions in the TIS. Recommendations should include infrastructure, network and program improvements to support non-auto travel, as well as a commitment to provide the TDM measures. Responsibilities for initial implementation and on-going operation of TDM measures (as applicable) should be identified.

Regards



Glyn Reedman | Senior Project Coordinator  
Works Department  
The Regional Municipality of Durham

[Glyn.Reedman@durham.ca](mailto:Glyn.Reedman@durham.ca) | 905-668-7711 extension 3476 | [durham.ca](http://durham.ca)



---

**From:** Raf Andrenacci <[Raf.Andrenacci@ghd.com](mailto:Raf.Andrenacci@ghd.com)>

**Sent:** September 27, 2022 12:50 PM

**To:** Zahoor, Nadeem <[nzahoor@pickering.ca](mailto:nzahoor@pickering.ca)>; Glyn Reedman <[Glyn.Reedman@Durham.ca](mailto:Glyn.Reedman@Durham.ca)>; Lawrence, Morgan (MTO) <[Morgan.Lawrence@ontario.ca](mailto:Morgan.Lawrence@ontario.ca)>

**Cc:** Will Maria <[William.Maria@ghd.com](mailto:William.Maria@ghd.com)>

**Subject:** Re: 720 Granite Court - Terms of Reference

Good afternoon,

I would like to follow up on this Terms of Reference that was sent out on September 9th, 2022.

Thanks,

Raf

---

**From:** Raf Andrenacci <[Raf.Andrenacci@ghd.com](mailto:Raf.Andrenacci@ghd.com)>

**Sent:** Friday, September 9, 2022 2:43 PM

**To:** Zahoor, Nadeem <[nzahoor@pickering.ca](mailto:nzahoor@pickering.ca)>; Glyn Reedman (InTouch) <[glyn.reedman@durham.ca](mailto:glyn.reedman@durham.ca)>; Lawrence, Morgan (MTO) <[Morgan.Lawrence@ontario.ca](mailto:Morgan.Lawrence@ontario.ca)>

**Cc:** Will Maria <[William.Maria@ghd.com](mailto:William.Maria@ghd.com)>


**Subject:** 720 Granite Court - Terms of Reference

Hello,

GHD Inc. has been retained to prepare a Transportation Impact Study for a proposed residential development located on lands municipally known as 720 Granite Court in the City of Pickering.

The subject site will consist of a 10-storey residential building that fronts Whites Road and stepping down to a 5-storey building fronting onto Granite Court. A total of 247 dwelling units are proposed, which includes 11 townhouse units.

Access to the subject site is proposed via a full moves driveway along Granite Court





In order to properly scope this project, we ask that the City review and provide comments on the following scope and confirm if there are any additional items required as part of the study.

**Study intersections**

- Whites Road and Granite Court/Oklahoma Drive
- Granite Court and the site access

**Traffic Data**

Updated traffic counts at the existing study intersections will be undertaken during the a.m. and p.m. peak hours.

**Study Peak Hours**

Weekday a.m. and p.m. peak hours

**Study Horizon Year**

2022 (existing), 2027 (build-out), 2032 (5-years post build-out), and 2037 (10-years post build-out), consistent with MTO TIS Guidelines.

**Background Growth Rate**

GHD will consult with City and Region staff to determine the growth rates to be used along study area roads

**Background Development Traffic**

Future background traffic volumes will include other developments (under construction or planned). GHD has identified the site at 755 Oklahoma Drive that would generate additional traffic along the study intersections that has a Traffic Impact Study available. City to confirm if there are any additional developments to include and where the corresponding Traffic Impact Studies can be found

### **Trip Generation**

Will be completed using rates published by the ITE Trip Generation 11<sup>th</sup> Edition, LUC 221 (multifamily housing – mid-rise) for the mid-rise component and LUC 215 (single-family attached housing) for the townhouse component

The directional distribution of traffic approaching and departing the site will be determined based on TTS 2016 data, existing local patterns and first principles.

The analysis will identify the transportation system requirements and other measures required to ensure the acceptable operation of the study intersections, including auxiliary turning lanes and other transportation infrastructure improvements.

Modal splits to be confirmed with City staff.

TAC, MTO, Region, and City guidelines will be reviewed in order to complete an access management.

Review for the site access for corner clearance, driveway spacing, auxiliary lanes, corner radii, and clear throat distance.

Existing TDM opportunities will be identified and future TDM opportunities will be recommended for the site.

The parking supply will be reviewed in accordance with the City's Zoning By-law

If the above scope is acceptable to the MTO, Region, and City, it will form the basis of our scope of work.

Thank you,  
Raf

CONFIDENTIALITY NOTICE: This email, including any attachments, is confidential and may be privileged. If you are not the intended recipient please notify the sender immediately, and please delete it; you should not copy it or use it for any purpose or disclose its contents to any other person. GHD and its affiliates reserve the right to monitor and modify all email communications through their networks.

THIS MESSAGE IS FOR THE USE OF THE INTENDED RECIPIENT(S) ONLY AND MAY CONTAIN INFORMATION THAT IS PRIVILEGED, PROPRIETARY, CONFIDENTIAL, AND/OR EXEMPT FROM DISCLOSURE UNDER ANY RELEVANT PRIVACY LEGISLATION. No rights to any privilege have been waived. If you are not the intended recipient, you are hereby notified that any review, re-transmission, dissemination, distribution, copying, conversion to hard copy, taking of action in reliance on or other use of this communication is strictly prohibited. If you are not the intended recipient and have received this message in error, please notify me by return e-mail and delete or destroy all copies of this message.

# Appendix B

Traffic Data



## Project #22-378 - GHD


### Intersection Count Report

**Intersection:** Whites Rd & Bayly St  
**Municipality:** Pickering  
**Count Date:** Tuesday, Nov 01, 2022  
**Site Code:** 2237800001  
**Count Categories:** Cars, Trucks, Bicycles, Pedestrians  
**Count Period:** 07:00-09:00, 16:00-18:00  
**Weather:** Clear  
**Comments:**



## Traffic Count Map

Intersection: Whites Rd & Bayly St  
Site Code: 2237800001  
Municipality: Pickering  
Count Date: Nov 01, 2022



## Traffic Count Summary

Intersection: Whites Rd & Bayly St  
 Site Code: 2237800001  
 Municipality: Pickering  
 Count Date: Nov 01, 2022

### Whites Rd - Traffic Summary

Hour	North Approach Totals						South Approach Totals						Total
	Includes Cars, Trucks, Bicycles						Includes Cars, Trucks, Bicycles						
	Left	Thru	Right	U-Turn	Total	Peds	Left	Thru	Right	U-Turn	Total	Peds	
<b>07:00 - 08:00</b>	272	385	0	0	657	0	1	370	43	0	414	0	1071
<b>08:00 - 09:00</b>	349	388	1	0	738	0	3	512	83	0	598	0	1336
BREAK													
<b>16:00 - 17:00</b>	689	470	0	0	1159	0	0	503	178	0	681	0	1840
<b>17:00 - 18:00</b>	676	426	1	0	1103	0	0	410	132	0	542	3	1645
<b>GRAND TOTAL</b>	<b>1986</b>	<b>1669</b>	<b>2</b>	<b>0</b>	<b>3657</b>	<b>0</b>	<b>4</b>	<b>1795</b>	<b>436</b>	<b>0</b>	<b>2235</b>	<b>3</b>	<b>5892</b>

## Traffic Count Summary

Intersection: Whites Rd & Bayly St  
 Site Code: 2237800001  
 Municipality: Pickering  
 Count Date: Nov 01, 2022

### Bayly St - Traffic Summary

Hour	East Approach Totals						West Approach Totals						Total
	Includes Cars, Trucks, Bicycles						Includes Cars, Trucks, Bicycles						
	Left	Thru	Right	U-Turn	Total	Peds	Left	Thru	Right	U-Turn	Total	Peds	
<b>07:00 - 08:00</b>	73	10	175	0	258	8	0	0	5	0	5	0	263
<b>08:00 - 09:00</b>	83	0	263	0	346	6	0	0	2	0	2	0	348
BREAK													
<b>16:00 - 17:00</b>	131	0	317	0	448	18	0	0	3	0	3	0	451
<b>17:00 - 18:00</b>	148	1	250	0	399	5	0	0	1	0	1	0	400
<b>GRAND TOTAL</b>	<b>435</b>	<b>11</b>	<b>1005</b>	<b>0</b>	<b>1451</b>	<b>37</b>	<b>0</b>	<b>0</b>	<b>11</b>	<b>0</b>	<b>11</b>	<b>0</b>	<b>1462</b>



## Traffic Count Data

Intersection: Whites Rd & Bayly St  
 Site Code: 2237800001  
 Municipality: Pickering  
 Count Date: Nov 01, 2022

### North Approach - Whites Rd

Start Time	Cars					Trucks					Bicycles					Total Peds
	←	↑	→	↻	Total	←	↑	→	↻	Total	←	↑	→	↻	Total	
07:00	53	61	0	0	114	0	2	0	0	2	0	0	0	0	0	0
07:15	50	71	0	0	121	1	1	0	0	2	0	0	0	0	0	0
07:30	50	61	0	0	111	4	8	0	0	12	0	0	0	0	0	0
07:45	110	178	0	0	288	4	3	0	0	7	0	0	0	0	0	0
08:00	82	89	0	0	171	1	3	0	0	4	0	0	0	0	0	0
08:15	68	109	0	0	177	2	2	0	0	4	0	0	0	0	0	0
08:30	89	92	1	0	182	4	4	0	0	8	0	0	0	0	0	0
08:45	98	84	0	0	182	5	5	0	0	10	0	0	0	0	0	0
<b>SUBTOTAL</b>	600	745	1	0	1346	21	28	0	0	49	0	0	0	0	0	0



## Traffic Count Data

Intersection: Whites Rd & Bayly St  
 Site Code: 2237800001  
 Municipality: Pickering  
 Count Date: Nov 01, 2022

### North Approach - Whites Rd

Start Time	Cars					Trucks					Bicycles					Total Peds
	←	↑	→	↻	Total	←	↑	→	↻	Total	←	↑	→	↻	Total	
16:00	172	120	0	0	292	3	2	0	0	5	0	0	0	0	0	0
16:15	158	110	0	0	268	4	5	0	0	9	0	0	0	0	0	0
16:30	169	125	0	0	294	1	2	0	0	3	0	0	0	0	0	0
16:45	180	106	0	0	286	2	0	0	0	2	0	0	0	0	0	0
17:00	151	107	0	0	258	5	3	0	0	8	0	0	0	0	0	0
17:15	190	99	1	0	290	3	2	0	0	5	0	0	0	0	0	0
17:30	161	105	0	0	266	0	4	0	0	4	0	0	0	0	0	0
17:45	164	103	0	0	267	2	3	0	0	5	0	0	0	0	0	0
<b>SUBTOTAL</b>	1345	875	1	0	2221	20	21	0	0	41	0	0	0	0	0	0
<b>GRAND TOTAL</b>	1945	1620	2	0	3567	41	49	0	0	90	0	0	0	0	0	0



## Traffic Count Data

Intersection: Whites Rd & Bayly St  
 Site Code: 2237800001  
 Municipality: Pickering  
 Count Date: Nov 01, 2022

### South Approach - Whites Rd

Start Time	Cars					Trucks					Bicycles					Total Peds
	←	↑	→	↻	Total	←	↑	→	↻	Total	←	↑	→	↻	Total	
07:00	0	73	14	0	87	0	5	0	0	5	0	0	0	0	0	0
07:15	0	60	8	0	68	0	1	0	0	1	0	0	0	0	0	0
07:30	0	97	6	0	103	0	3	0	0	3	0	0	0	0	0	0
07:45	1	126	14	0	141	0	5	1	0	6	0	0	0	0	0	0
08:00	1	137	13	0	151	0	8	0	0	8	0	0	0	0	0	0
08:15	1	116	12	0	129	0	4	0	0	4	0	0	0	0	0	0
08:30	1	112	26	0	139	0	3	0	0	3	0	0	0	0	0	0
08:45	0	123	30	0	153	0	9	2	0	11	0	0	0	0	0	0
<b>SUBTOTAL</b>	4	844	123	0	971	0	38	3	0	41	0	0	0	0	0	0



## Traffic Count Data

Intersection: Whites Rd & Bayly St  
 Site Code: 2237800001  
 Municipality: Pickering  
 Count Date: Nov 01, 2022

### South Approach - Whites Rd

Start Time	Cars					Trucks					Bicycles					Total Peds
	←	↑	→	↻	Total	←	↑	→	↻	Total	←	↑	→	↻	Total	
16:00	0	137	52	0	189	0	6	2	0	8	0	0	0	0	0	0
16:15	0	106	23	0	129	0	3	1	0	4	0	0	0	0	0	0
16:30	0	136	53	0	189	0	2	2	0	4	0	0	0	0	0	0
16:45	0	110	44	0	154	0	3	1	0	4	0	0	0	0	0	0
17:00	0	138	45	0	183	0	2	1	0	3	0	0	0	0	0	1
17:15	0	97	28	0	125	0	0	0	0	0	0	0	0	0	0	1
17:30	0	94	28	0	122	0	2	1	0	3	0	0	0	0	0	0
17:45	0	75	29	0	104	0	2	0	0	2	0	0	0	0	0	1
<b>SUBTOTAL</b>	0	893	302	0	1195	0	20	8	0	28	0	0	0	0	0	3
<b>GRAND TOTAL</b>	4	1737	425	0	2166	0	58	11	0	69	0	0	0	0	0	3



## Traffic Count Data

Intersection: Whites Rd & Bayly St  
 Site Code: 2237800001  
 Municipality: Pickering  
 Count Date: Nov 01, 2022

### East Approach - Bayly St

Start Time	Cars					Trucks					Bicycles					Total Peds
	←	↑	→	↻	Total	←	↑	→	↻	Total	←	↑	→	↻	Total	
07:00	14	1	43	0	58	1	0	4	0	5	0	0	0	0	0	3
07:15	17	6	30	0	53	0	0	2	0	2	0	0	0	0	0	0
07:30	12	0	39	0	51	1	0	0	0	1	0	0	0	0	0	0
07:45	27	3	53	0	83	1	0	4	0	5	0	0	0	0	0	5
08:00	21	0	84	0	105	1	0	1	0	2	0	0	0	0	0	2
08:15	25	0	57	0	82	3	0	1	0	4	0	0	0	0	0	1
08:30	20	0	57	0	77	1	0	5	0	6	0	0	0	0	0	2
08:45	11	0	55	0	66	1	0	3	0	4	0	0	0	0	0	1
<b>SUBTOTAL</b>	147	10	418	0	575	9	0	20	0	29	0	0	0	0	0	14





## Traffic Count Data

Intersection: Whites Rd & Bayly St  
 Site Code: 2237800001  
 Municipality: Pickering  
 Count Date: Nov 01, 2022

### East Approach - Bayly St

Start Time	Cars					Trucks					Bicycles					Total Peds
	←	↑	→	↻	Total	←	↑	→	↻	Total	←	↑	→	↻	Total	
16:00	31	0	79	0	110	0	0	0	0	0	0	0	0	0	0	4
16:15	37	0	77	0	114	1	0	3	0	4	0	0	0	0	0	5
16:30	28	0	71	0	99	1	0	0	0	1	0	0	0	0	0	8
16:45	33	0	87	0	120	0	0	0	0	0	0	0	0	0	0	1
17:00	36	0	72	0	108	0	0	0	0	0	0	0	0	0	0	1
17:15	44	0	73	0	117	0	0	3	0	3	0	0	0	0	0	1
17:30	35	1	53	0	89	0	0	0	0	0	0	0	0	0	0	1
17:45	33	0	49	0	82	0	0	0	0	0	0	0	0	0	0	2
<b>SUBTOTAL</b>	277	1	561	0	839	2	0	6	0	8	0	0	0	0	0	23
<b>GRAND TOTAL</b>	424	11	979	0	1414	11	0	26	0	37	0	0	0	0	0	37



## Traffic Count Data

Intersection: Whites Rd & Bayly St  
 Site Code: 2237800001  
 Municipality: Pickering  
 Count Date: Nov 01, 2022

### West Approach - Bayly St

Start Time	Cars					Trucks					Bicycles					Total Peds	
	←	↑	→	↻	Total	←	↑	→	↻	Total	←	↑	→	↻	Total		
07:00	0	0	2	0	2	0	0	0	0	0	0	0	0	0	0	0	0
07:15	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
07:30	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
07:45	0	0	0	0	0	0	0	3	0	3	0	0	0	0	0	0	0
08:00	0	0	1	0	1	0	0	1	0	1	0	0	0	0	0	0	0
08:15	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
08:30	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
08:45	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
<b>SUBTOTAL</b>	0	0	3	0	3	0	0	4	0	4	0	0	0	0	0	0	0



## Traffic Count Data

Intersection: Whites Rd & Bayly St  
 Site Code: 2237800001  
 Municipality: Pickering  
 Count Date: Nov 01, 2022

### West Approach - Bayly St

Start Time	Cars					Trucks					Bicycles					Total Peds
	←	↑	→	↻	Total	←	↑	→	↻	Total	←	↑	→	↻	Total	
16:00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
16:15	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
16:30	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0	0
16:45	0	0	2	0	2	0	0	0	0	0	0	0	0	0	0	0
17:00	0	0	0	0	0	0	0	1	0	1	0	0	0	0	0	0
17:15	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
17:30	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
17:45	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
<b>SUBTOTAL</b>	0	0	3	0	3	0	0	1	0	1	0	0	0	0	0	0
<b>GRAND TOTAL</b>	0	0	6	0	6	0	0	5	0	5	0	0	0	0	0	0

## Peak Hour Diagram

### Specified Period

From: 07:00:00  
To: 09:00:00

### One Hour Peak

From: 07:45:00  
To: 08:45:00

**Intersection:** Whites Rd & Bayly St  
**Site Code:** 2237800001  
**Count Date:** Nov 01, 2022

**Weather conditions:** Clear

**\*\* Signalized Intersection \*\***

**Major Road:** Whites Rd runs N/S

### North Approach

	Out	In	Total
	818	742	1560
	23	31	54
	0	0	0
<b>Totals</b>	<b>841</b>	<b>773</b>	<b>1614</b>

### Whites Rd

	0	0	0	0
	0	12	11	0
	1	468	349	0
<b>Totals</b>	<b>1</b>	<b>480</b>	<b>360</b>	<b>0</b>

### East Approach

	Out	In	Total
	347	414	761
	17	12	29
	0	0	0
<b>Totals</b>	<b>364</b>	<b>426</b>	<b>790</b>

### Bayly St

	Out	In	Total
	0	0	0
	0	0	0
	0	0	0
<b>Totals</b>	<b>0</b>	<b>0</b>	<b>0</b>

Peds: 0

Peds: 0



Peds: 10

### Bayly St

Totals	Out	In	Total
	0	0	0
	262	251	11
	3	3	0
<b>Totals</b>	<b>99</b>	<b>93</b>	<b>6</b>

Peds: 0

### West Approach

	Out	In	Total
	1	8	9
	4	0	4
	0	0	0
<b>Totals</b>	<b>5</b>	<b>8</b>	<b>13</b>

Totals	Out	In	Total
	4	491	65
	0	20	1
	0	0	0
<b>Totals</b>	<b>4</b>	<b>511</b>	<b>66</b>

Whites Rd

### South Approach

	Out	In	Total
	560	562	1122
	21	22	43
	0	0	0
<b>Totals</b>	<b>581</b>	<b>584</b>	<b>1165</b>

- Cars

- Trucks

- Bicycles

### Comments



## Peak Hour Summary

Intersection: Whites Rd & Bayly St  
 Site Code: 2237800001  
 Count Date: Nov 01, 2022  
 Period: 07:00 - 09:00

### Peak Hour Data (07:45 - 08:45)

Start Time	North Approach Whites Rd						South Approach Whites Rd						East Approach Bayly St						West Approach Bayly St						Total Vehicles
	←	↑	→	↻	Peds	Total	←	↑	→	↻	Peds	Total	←	↑	→	↻	Peds	Total	←	↑	→	↻	Peds	Total	
07:45	114	181	0	0	0	295	1	131	15	0	0	147	28	3	57	0	5	88	0	0	3	0	0	3	533
08:00	83	92	0	0	0	175	1	145	13	0	0	159	22	0	85	0	2	107	0	0	2	0	0	2	443
08:15	70	111	0	0	0	181	1	120	12	0	0	133	28	0	58	0	1	86	0	0	0	0	0	0	400
08:30	93	96	1	0	0	190	1	115	26	0	0	142	21	0	62	0	2	83	0	0	0	0	0	0	415
<b>Grand Total</b>	<b>360</b>	<b>480</b>	<b>1</b>	<b>0</b>	<b>0</b>	<b>841</b>	<b>4</b>	<b>511</b>	<b>66</b>	<b>0</b>	<b>0</b>	<b>581</b>	<b>99</b>	<b>3</b>	<b>262</b>	<b>0</b>	<b>10</b>	<b>364</b>	<b>0</b>	<b>0</b>	<b>5</b>	<b>0</b>	<b>0</b>	<b>5</b>	<b>1791</b>
Approach %	42.8	57.1	0.1	0	-	-	0.7	88	11.4	0	-	-	27.2	0.8	72	0	-	-	0	0	100	0	-	-	-
Totals %	20.1	26.8	0.1	0	47	32.4	0.2	28.5	3.7	0	32.4	5.5	0.2	14.6	0	20.3	0	0	0.3	0	0.3	0	0.3	0.3	0.3
<b>PHF</b>	<b>0.79</b>	<b>0.66</b>	<b>0.25</b>	<b>0</b>	<b>0.71</b>	<b>0.91</b>	<b>1</b>	<b>0.88</b>	<b>0.63</b>	<b>0</b>	<b>0.91</b>	<b>0.88</b>	<b>0.25</b>	<b>0.77</b>	<b>0</b>	<b>0.85</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0.42</b>	<b>0</b>	<b>0.42</b>	<b>0.42</b>	<b>0.84</b>	<b>0.84</b>
Cars	349	468	1	0	0	818	4	491	65	0	0	560	93	3	251	0	0	347	0	0	1	0	0	1	1726
% Cars	96.9	97.5	100	0	0	97.3	100	96.1	98.5	0	0	96.4	93.9	100	95.8	0	0	95.3	0	0	20	0	0	20	96.4
Trucks	11	12	0	0	0	23	0	20	1	0	0	21	6	0	11	0	0	17	0	0	4	0	0	4	65
% Trucks	3.1	2.5	0	0	0	2.7	0	3.9	1.5	0	0	3.6	6.1	0	4.2	0	0	4.7	0	0	80	0	0	80	3.6
Bicycles	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
% Bicycles	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Peds					0	-					0	-					10	-					0	-	10
% Peds					0	-					0	-					100	-					0	-	0

## Peak Hour Diagram

### Specified Period

From: 16:00:00  
To: 18:00:00

### One Hour Peak

From: 16:00:00  
To: 17:00:00

**Intersection:** Whites Rd & Bayly St  
**Site Code:** 2237800001  
**Count Date:** Nov 01, 2022

**Weather conditions:** Clear

**\*\* Signalized Intersection \*\***

**Major Road:** Whites Rd runs N/S

### North Approach

	Out	In	Total
	1140	803	1943
	19	17	36
	0	0	0
<b>Totals</b>	<b>1159</b>	<b>820</b>	<b>1979</b>

### Whites Rd

	0	0	0	0
	0	9	10	0
	0	461	679	0
<b>Totals</b>	<b>0</b>	<b>470</b>	<b>689</b>	<b>0</b>

### East Approach

	Out	In	Total
	443	851	1294
	5	16	21
	0	0	0
<b>Totals</b>	<b>448</b>	<b>867</b>	<b>1315</b>

### Bayly St

				Totals
	0	0	0	0
	0	0	0	0
	0	0	0	0
	0	0	3	3

Peds: 0

Peds: 0



Peds: 18

Peds: 0

### Bayly St

Totals			
0	0	0	0
317	314	3	0
0	0	0	0
131	129	2	0

### West Approach

	Out	In	Total
	3	0	3
	0	0	0
	0	0	0
<b>Totals</b>	<b>3</b>	<b>0</b>	<b>3</b>

Totals				
0	503	178	0	
	0	489	172	0
	0	14	6	0
	0	0	0	0

Whites Rd

### South Approach

	Out	In	Total
	661	593	1254
	20	11	31
	0	0	0
<b>Totals</b>	<b>681</b>	<b>604</b>	<b>1285</b>

- Cars

- Trucks

- Bicycles

### Comments



## Peak Hour Summary

Intersection: Whites Rd & Bayly St  
 Site Code: 2237800001  
 Count Date: Nov 01, 2022  
 Period: 16:00 - 18:00

### Peak Hour Data (16:00 - 17:00)

Start Time	North Approach Whites Rd						South Approach Whites Rd						East Approach Bayly St						West Approach Bayly St						Total Vehicles
	←	↑	→	↻	Peds	Total	←	↑	→	↻	Peds	Total	←	↑	→	↻	Peds	Total	←	↑	→	↻	Peds	Total	
16:00	175	122	0	0	0	297	0	143	54	0	0	197	31	0	79	0	4	110	0	0	0	0	0	0	604
16:15	162	115	0	0	0	277	0	109	24	0	0	133	38	0	80	0	5	118	0	0	0	0	0	0	528
16:30	170	127	0	0	0	297	0	138	55	0	0	193	29	0	71	0	8	100	0	0	1	0	0	1	591
16:45	182	106	0	0	0	288	0	113	45	0	0	158	33	0	87	0	1	120	0	0	2	0	0	2	568
<b>Grand Total</b>	<b>689</b>	<b>470</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>1159</b>	<b>0</b>	<b>503</b>	<b>178</b>	<b>0</b>	<b>0</b>	<b>681</b>	<b>131</b>	<b>0</b>	<b>317</b>	<b>0</b>	<b>18</b>	<b>448</b>	<b>0</b>	<b>0</b>	<b>3</b>	<b>0</b>	<b>0</b>	<b>3</b>	<b>2291</b>
<b>Approach %</b>	59.4	40.6	0	0	-	-	0	73.9	26.1	0	-	-	29.2	0	70.8	0	-	-	0	0	100	0	-	-	-
<b>Totals %</b>	30.1	20.5	0	0	50.6	-	0	22	7.8	0	29.7	-	5.7	0	13.8	0	19.6	-	0	0	0.1	0	-	0.1	-
<b>PHF</b>	<b>0.95</b>	<b>0.93</b>	<b>0</b>	<b>0</b>	<b>0.98</b>	-	<b>0</b>	<b>0.88</b>	<b>0.81</b>	<b>0</b>	<b>0.86</b>	-	<b>0.86</b>	<b>0</b>	<b>0.91</b>	<b>0</b>	<b>0.93</b>	-	<b>0</b>	<b>0</b>	<b>0.38</b>	<b>0</b>	-	<b>0.38</b>	<b>0.95</b>
<b>Cars</b>	679	461	0	0	0	1140	0	489	172	0	661	129	0	314	0	443	0	443	0	0	3	0	0	3	2247
<b>% Cars</b>	98.5	98.1	0	0	98.4	-	0	97.2	96.6	0	97.1	-	98.5	0	99.1	0	98.9	-	0	0	100	0	0	100	98.1
<b>Trucks</b>	10	9	0	0	0	19	0	14	6	0	20	2	0	3	0	5	0	5	0	0	0	0	0	0	44
<b>% Trucks</b>	1.5	1.9	0	0	1.6	-	0	2.8	3.4	0	2.9	-	1.5	0	0.9	0	1.1	-	0	0	0	0	0	0	1.9
<b>Bicycles</b>	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
<b>% Bicycles</b>	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
<b>Peds</b>					0	-				0	-					18	-				0	-	0	-	18
<b>% Peds</b>					0	-				0	-					100	-				0	-	0	-	0



## Project #22-378 - GHD


### Intersection Count Report

**Intersection:** Whites Rd & Granite Court-Oklahoma Dr  
**Municipality:** Pickering  
**Count Date:** Tuesday, Nov 01, 2022  
**Site Code:** 2237800002  
**Count Categories:** Cars, Trucks, Bicycles, Pedestrians  
**Count Period:** 07:00-09:00, 16:00-18:00  
**Weather:** Clear  
**Comments:**



## Traffic Count Map

Intersection: Whites Rd & Granite Court-Oklahoma Dr  
Site Code: 2237800002  
Municipality: Pickering  
Count Date: Nov 01, 2022



## Traffic Count Summary

Intersection: Whites Rd & Granite Court-Oklahoma Dr  
 Site Code: 2237800002  
 Municipality: Pickering  
 Count Date: Nov 01, 2022

### Whites Rd - Traffic Summary

Hour	North Approach Totals						South Approach Totals						Total
	Includes Cars, Trucks, Bicycles						Includes Cars, Trucks, Bicycles						
	Left	Thru	Right	U-Turn	Total	Peds	Left	Thru	Right	U-Turn	Total	Peds	
<b>07:00 - 08:00</b>	123	43	296	0	462	7	4	107	11	0	122	4	584
<b>08:00 - 09:00</b>	135	69	269	0	473	4	16	132	26	0	174	1	647
BREAK													
<b>16:00 - 17:00</b>	251	172	177	0	600	7	15	102	13	0	130	4	730
<b>17:00 - 18:00</b>	259	163	150	0	572	3	14	109	11	0	134	7	706
<b>GRAND TOTAL</b>	<b>768</b>	<b>447</b>	<b>892</b>	<b>0</b>	<b>2107</b>	<b>21</b>	<b>49</b>	<b>450</b>	<b>61</b>	<b>0</b>	<b>560</b>	<b>16</b>	<b>2667</b>

## Traffic Count Summary

Intersection: Whites Rd & Granite Court-Oklahoma Dr  
 Site Code: 2237800002  
 Municipality: Pickering  
 Count Date: Nov 01, 2022

### Oklahoma Dr - Traffic Summary

Hour	East Approach Totals						West Approach Totals						Total
	Includes Cars, Trucks, Bicycles						Includes Cars, Trucks, Bicycles						
	Left	Thru	Right	U-Turn	Total	Peds	Left	Thru	Right	U-Turn	Total	Peds	
<b>07:00 - 08:00</b>	1	34	201	0	236	1	107	41	4	0	152	2	388
<b>08:00 - 09:00</b>	14	37	282	0	333	5	175	39	7	0	221	0	554
BREAK													
<b>16:00 - 17:00</b>	10	55	186	0	251	4	387	68	11	0	466	3	717
<b>17:00 - 18:00</b>	11	33	166	0	210	2	263	56	18	0	337	3	547
<b>GRAND TOTAL</b>	<b>36</b>	<b>159</b>	<b>835</b>	<b>0</b>	<b>1030</b>	<b>12</b>	<b>932</b>	<b>204</b>	<b>40</b>	<b>0</b>	<b>1176</b>	<b>8</b>	<b>2206</b>



## Traffic Count Data

Intersection: Whites Rd & Granite Court-Oklahoma Dr  
 Site Code: 2237800002  
 Municipality: Pickering  
 Count Date: Nov 01, 2022

### North Approach - Whites Rd

Start Time	Cars					Trucks					Bicycles					Total Peds
	←	↑	→	↻	Total	←	↑	→	↻	Total	←	↑	→	↻	Total	
07:00	8	12	56	0	76	0	1	2	0	3	0	0	0	0	0	2
07:15	10	6	72	0	88	1	0	0	0	1	0	0	0	0	0	3
07:30	20	6	51	0	77	7	2	3	0	12	0	0	0	0	0	2
07:45	76	14	111	0	201	1	2	1	0	4	0	0	0	0	0	0
08:00	24	16	68	0	108	1	1	3	0	5	0	0	0	0	0	2
08:15	39	17	80	0	136	1	1	1	0	3	0	0	0	0	0	1
08:30	32	13	64	0	109	4	2	1	0	7	0	0	0	0	0	0
08:45	33	19	47	0	99	1	0	5	0	6	0	0	0	0	0	1
<b>SUBTOTAL</b>	242	103	549	0	894	16	9	16	0	41	0	0	0	0	0	11





## Traffic Count Data

Intersection: Whites Rd & Granite Court-Oklahoma Dr  
 Site Code: 2237800002  
 Municipality: Pickering  
 Count Date: Nov 01, 2022

### South Approach - Whites Rd

Start Time	Cars					Trucks					Bicycles					Total Peds
	←	↑	→	↻	Total	←	↑	→	↻	Total	←	↑	→	↻	Total	
07:00	0	21	0	0	21	0	2	0	0	2	0	0	0	0	0	0
07:15	1	27	3	0	31	0	0	0	0	0	0	0	0	0	0	1
07:30	0	27	2	0	29	0	0	0	0	0	0	0	0	0	0	2
07:45	2	30	6	0	38	1	0	0	0	1	0	0	0	0	0	1
08:00	3	34	5	0	42	0	0	0	0	0	0	0	0	0	0	0
08:15	7	34	4	0	45	0	1	0	0	1	0	0	0	0	0	1
08:30	3	25	9	0	37	0	0	0	0	0	0	0	0	0	0	0
08:45	2	37	8	0	47	1	1	0	0	2	0	0	0	0	0	0
<b>SUBTOTAL</b>	18	235	37	0	290	2	4	0	0	6	0	0	0	0	0	5



## Traffic Count Data

Intersection: Whites Rd & Granite Court-Oklahoma Dr  
 Site Code: 2237800002  
 Municipality: Pickering  
 Count Date: Nov 01, 2022

### South Approach - Whites Rd

Start Time	Cars					Trucks					Bicycles					Total Peds
	←	↑	→	↻	Total	←	↑	→	↻	Total	←	↑	→	↻	Total	
16:00	1	24	3	0	28	0	1	0	0	1	1	0	0	0	1	1
16:15	5	23	4	0	32	0	1	0	0	1	0	0	0	0	0	1
16:30	6	26	3	0	35	0	0	0	0	0	0	0	0	0	0	2
16:45	2	27	3	0	32	0	0	0	0	0	0	0	0	0	0	0
17:00	2	25	3	0	30	0	0	0	0	0	0	0	0	0	0	5
17:15	5	25	3	0	33	0	0	0	0	0	0	0	0	0	0	0
17:30	4	25	1	0	30	0	0	1	0	1	1	0	0	0	1	0
17:45	2	33	3	0	38	0	1	0	0	1	0	0	0	0	0	2
<b>SUBTOTAL</b>	27	208	23	0	258	0	3	1	0	4	2	0	0	0	2	11
<b>GRAND TOTAL</b>	45	443	60	0	548	2	7	1	0	10	2	0	0	0	2	16



## Traffic Count Data

Intersection: Whites Rd & Granite Court-Oklahoma Dr  
 Site Code: 2237800002  
 Municipality: Pickering  
 Count Date: Nov 01, 2022

### East Approach - Oklahoma Dr

Start Time	Cars					Trucks					Bicycles					Total Peds
	←	↑	→	↻	Total	←	↑	→	↻	Total	←	↑	→	↻	Total	
07:00	0	2	32	0	34	0	1	2	0	3	0	0	0	0	0	0
07:15	0	5	42	0	47	0	0	0	0	0	0	0	0	0	0	0
07:30	0	3	53	0	56	0	0	2	0	2	0	0	0	0	0	0
07:45	1	23	68	0	92	0	0	2	0	2	0	0	0	0	0	1
08:00	2	11	90	0	103	0	0	1	0	1	0	0	0	0	0	1
08:15	2	7	55	0	64	0	0	2	0	2	0	0	0	0	0	1
08:30	2	11	66	0	79	0	0	2	0	2	0	0	0	0	0	2
08:45	7	8	63	0	78	1	0	3	0	4	0	0	0	0	0	1
<b>SUBTOTAL</b>	14	70	469	0	553	1	1	14	0	16	0	0	0	0	0	6







## Traffic Count Data

Intersection: Whites Rd & Granite Court-Oklahoma Dr  
 Site Code: 2237800002  
 Municipality: Pickering  
 Count Date: Nov 01, 2022

### West Approach - Granite Court

Start Time	Cars					Trucks					Bicycles					Total Peds
	←	↑	→	↻	Total	←	↑	→	↻	Total	←	↑	→	↻	Total	
07:00	24	1	0	0	25	2	0	0	0	2	0	0	0	0	0	0
07:15	17	2	1	0	20	0	1	0	0	1	0	0	0	0	0	0
07:30	23	16	1	0	40	3	0	0	0	3	0	0	0	0	0	1
07:45	36	21	1	0	58	2	0	1	0	3	0	0	0	0	0	1
08:00	25	6	0	0	31	6	0	0	0	6	0	0	0	0	0	0
08:15	41	6	4	0	51	2	0	0	0	2	0	0	0	0	0	0
08:30	45	7	2	0	54	1	0	0	0	1	0	0	0	0	0	0
08:45	48	19	1	0	68	7	1	0	0	8	0	0	0	0	0	0
<b>SUBTOTAL</b>	259	78	10	0	347	23	2	1	0	26	0	0	0	0	0	2



## Traffic Count Data

Intersection: Whites Rd & Granite Court-Oklahoma Dr  
 Site Code: 2237800002  
 Municipality: Pickering  
 Count Date: Nov 01, 2022

### West Approach - Granite Court

Start Time	Cars					Trucks					Bicycles					Total Peds
	←	↑	→	↻	Total	←	↑	→	↻	Total	←	↑	→	↻	Total	
16:00	116	19	3	0	138	5	0	0	0	5	0	0	0	0	0	1
16:15	70	17	1	0	88	3	0	0	0	3	0	0	0	0	0	0
16:30	111	17	3	0	131	3	0	0	0	3	0	0	0	0	0	2
16:45	76	15	4	0	95	3	0	0	0	3	0	0	0	0	0	0
17:00	118	24	4	0	146	2	0	0	0	2	0	1	0	0	1	1
17:15	50	11	4	0	65	0	0	0	0	0	0	0	0	0	0	0
17:30	54	13	6	0	73	2	0	0	0	2	0	0	0	0	0	2
17:45	37	7	4	0	48	0	0	0	0	0	0	0	0	0	0	0
<b>SUBTOTAL</b>	632	123	29	0	784	18	0	0	0	18	0	1	0	0	1	6
<b>GRAND TOTAL</b>	<b>891</b>	<b>201</b>	<b>39</b>	<b>0</b>	<b>1131</b>	<b>41</b>	<b>2</b>	<b>1</b>	<b>0</b>	<b>44</b>	<b>0</b>	<b>1</b>	<b>0</b>	<b>0</b>	<b>1</b>	<b>8</b>

## Peak Hour Diagram

### Specified Period

From: 07:00:00  
To: 09:00:00

### One Hour Peak

From: 07:45:00  
To: 08:45:00

**Intersection:** Whites Rd & Granite Court-Oklahoma Dr  
**Site Code:** 2237800002  
**Count Date:** Nov 01, 2022

**Weather conditions:** Clear

**\*\* Signalized Intersection \*\***

**Major Road:** Whites Rd runs N/S

### North Approach

	Out	In	Total
	554	549	1103
	19	19	38
	0	0	0
<b>Totals</b>	<b>573</b>	<b>568</b>	<b>1141</b>

### Whites Rd

	0	0	0	0
	6	6	7	0
	323	60	171	0
<b>Totals</b>	<b>329</b>	<b>66</b>	<b>178</b>	<b>0</b>

### East Approach

	Out	In	Total
	338	235	573
	7	7	14
	0	0	0
<b>Totals</b>	<b>345</b>	<b>242</b>	<b>587</b>

### Granite Court

			Totals	
0	0	0	0	
0	11	147	158	
0	0	40	40	
0	1	7	8	

Peds: 3



Peds: 1

Peds: 5

Peds: 2

### Oklahoma Dr

Totals			
0	0	0	0
286	279	7	0
52	52	0	0
7	7	0	0

### West Approach

	Out	In	Total
	194	390	584
	12	7	19
	0	0	0
<b>Totals</b>	<b>206</b>	<b>397</b>	<b>603</b>

Totals				
<b>16</b>	<b>124</b>	<b>24</b>	<b>0</b>	
	15	123	24	0
	1	1	0	0
	0	0	0	0

### Whites Rd

### South Approach

	Out	In	Total
	162	74	236
	2	7	9
	0	0	0
<b>Totals</b>	<b>164</b>	<b>81</b>	<b>245</b>

- Cars

- Trucks

- Bicycles

### Comments



## Peak Hour Summary

Intersection: Whites Rd & Granite Court-Oklahoma Dr  
 Site Code: 2237800002  
 Count Date: Nov 01, 2022  
 Period: 07:00 - 09:00

### Peak Hour Data (07:45 - 08:45)

Start Time	North Approach Whites Rd						South Approach Whites Rd						East Approach Oklahoma Dr						West Approach Granite Court						Total Vehicles
	←	↑	→	↻	Peds	Total	←	↑	→	↻	Peds	Total	←	↑	→	↻	Peds	Total	←	↑	→	↻	Peds	Total	
07:45	77	16	112	0	0	205	3	30	6	0	1	39	1	23	70	0	1	94	38	21	2	0	1	61	399
08:00	25	17	71	0	2	113	3	34	5	0	0	42	2	11	91	0	1	104	31	6	0	0	0	37	296
08:15	40	18	81	0	1	139	7	35	4	0	1	46	2	7	57	0	1	66	43	6	4	0	0	53	304
08:30	36	15	65	0	0	116	3	25	9	0	0	37	2	11	68	0	2	81	46	7	2	0	0	55	289
<b>Grand Total</b>	<b>178</b>	<b>66</b>	<b>329</b>	<b>0</b>	<b>3</b>	<b>573</b>	<b>16</b>	<b>124</b>	<b>24</b>	<b>0</b>	<b>2</b>	<b>164</b>	<b>7</b>	<b>52</b>	<b>286</b>	<b>0</b>	<b>5</b>	<b>345</b>	<b>158</b>	<b>40</b>	<b>8</b>	<b>0</b>	<b>1</b>	<b>206</b>	<b>1288</b>
Approach %	31.1	11.5	57.4	0	-	-	9.8	75.6	14.6	0	-	-	2	15.1	82.9	0	-	-	76.7	19.4	3.9	0	-	-	-
Totals %	13.8	5.1	25.5	0	44.5	12.7	1.2	9.6	1.9	0	12.7	0.5	4	22.2	0	26.8	12.3	3.1	0.6	0	16	16	16		
<b>PHF</b>	<b>0.58</b>	<b>0.92</b>	<b>0.73</b>	<b>0</b>	<b>0.7</b>	<b>0.89</b>	<b>0.57</b>	<b>0.89</b>	<b>0.67</b>	<b>0</b>	<b>0.89</b>	<b>0.88</b>	<b>0.57</b>	<b>0.79</b>	<b>0</b>	<b>0.83</b>	<b>0.86</b>	<b>0.48</b>	<b>0.5</b>	<b>0</b>	<b>0.84</b>	<b>0.81</b>	<b>0.81</b>		
Cars	171	60	323	0	554	162	15	123	24	0	162	7	52	279	0	338	147	40	7	0	194	1248			
% Cars	96.1	90.9	98.2	0	96.7	98.8	93.8	99.2	100	0	98.8	100	100	97.6	0	98	93	100	87.5	0	94.2	96.9			
Trucks	7	6	6	0	19	2	1	1	0	0	2	0	0	7	0	7	11	0	1	0	12	40			
% Trucks	3.9	9.1	1.8	0	3.3	1.2	6.3	0.8	0	0	1.2	0	0	2.4	0	2	7	0	12.5	0	5.8	3.1			
Bicycles	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
% Bicycles	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
Peds					3	-					2	-					5	-					1	-	11
% Peds					27.3	-					18.2	-					45.5	-					9.1	-	-

## Peak Hour Diagram

### Specified Period

From: 16:00:00  
To: 18:00:00

### One Hour Peak

From: 16:00:00  
To: 17:00:00

**Intersection:** Whites Rd & Granite Court-Oklahoma Dr  
**Site Code:** 2237800002  
**Count Date:** Nov 01, 2022

**Weather conditions:** Clear

**\*\* Signalized Intersection \*\***

**Major Road:** Whites Rd runs N/S

### North Approach

	Out	In	Total
	589	655	1244
	11	20	31
	0	0	0
<b>Totals</b>	<b>600</b>	<b>675</b>	<b>1275</b>

### Whites Rd

	0	0	0	0
	7	2	2	0
	170	170	249	0
<b>Totals</b>	<b>177</b>	<b>172</b>	<b>251</b>	<b>0</b>

### East Approach

	Out	In	Total
	246	330	576
	5	2	7
	0	0	0
<b>Totals</b>	<b>251</b>	<b>332</b>	<b>583</b>

### Granite Court

			Totals	
0	0	0	0	
0	14	373	387	
0	0	68	68	
0	0	11	11	

Peds: 7

Peds: 3



Peds: 4

### Oklahoma Dr

Totals			
0	0	0	0
186	182	4	0
55	55	0	0
10	9	1	0

Peds: 4

### West Approach

	Out	In	Total
	452	239	691
	14	7	21
	0	1	1
<b>Totals</b>	<b>466</b>	<b>247</b>	<b>713</b>

Totals				
15	102	13	0	
	14	100	13	0
	0	2	0	0
	1	0	0	0

Whites Rd

### South Approach

Out	In	Total	
	127	190	317
	2	3	5
	1	0	1
<b>Totals</b>	<b>130</b>	<b>193</b>	<b>323</b>

- Cars

- Trucks

- Bicycles

### Comments



## Peak Hour Summary

Intersection: Whites Rd & Granite Court-Oklahoma Dr  
 Site Code: 2237800002  
 Count Date: Nov 01, 2022  
 Period: 16:00 - 18:00

### Peak Hour Data (16:00 - 17:00)

Start Time	North Approach Whites Rd						South Approach Whites Rd						East Approach Oklahoma Dr						West Approach Granite Court						Total Vehicles
	←	↑	→	↻	Peds	Total	←	↑	→	↻	Peds	Total	←	↑	→	↻	Peds	Total	←	↑	→	↻	Peds	Total	
16:00	60	44	45	0	2	149	2	25	3	0	1	30	1	18	48	0	3	67	121	19	3	0	1	143	389
16:15	55	50	51	0	0	156	5	24	4	0	1	33	3	12	44	0	1	59	73	17	1	0	0	91	339
16:30	69	43	46	0	4	158	6	26	3	0	2	35	2	16	43	0	0	61	114	17	3	0	2	134	388
16:45	67	35	35	0	1	137	2	27	3	0	0	32	4	9	51	0	0	64	79	15	4	0	0	98	331
<b>Grand Total</b>	<b>251</b>	<b>172</b>	<b>177</b>	<b>0</b>	<b>7</b>	<b>600</b>	<b>15</b>	<b>102</b>	<b>13</b>	<b>0</b>	<b>4</b>	<b>130</b>	<b>10</b>	<b>55</b>	<b>186</b>	<b>0</b>	<b>4</b>	<b>251</b>	<b>387</b>	<b>68</b>	<b>11</b>	<b>0</b>	<b>3</b>	<b>466</b>	<b>1447</b>
<b>Approach %</b>	41.8	28.7	29.5	0	-	-	11.5	78.5	10	0	-	-	4	21.9	74.1	0	-	-	83	14.6	2.4	0	-	-	-
<b>Totals %</b>	17.3	11.9	12.2	0	41.5	-	1	7	0.9	0	9	-	0.7	3.8	12.9	0	17.3	-	26.7	4.7	0.8	0	-	32.2	-
<b>PHF</b>	<b>0.91</b>	<b>0.86</b>	<b>0.87</b>	<b>0</b>	<b>0.95</b>	<b>0.63</b>	<b>0.94</b>	<b>0.81</b>	<b>0</b>	<b>0.93</b>	<b>0.63</b>	<b>0.76</b>	<b>0.91</b>	<b>0</b>	<b>0.94</b>	<b>0.8</b>	<b>0.89</b>	<b>0.69</b>	<b>0</b>	<b>0.81</b>	<b>0.93</b>	<b>0.93</b>	<b>0.93</b>		
<b>Cars</b>	249	170	170	0	589	14	100	13	0	127	9	55	182	0	246	373	68	11	0	452	1414	1414			
<b>% Cars</b>	99.2	98.8	96	0	98.2	93.3	98	100	0	97.7	90	100	97.8	0	98	96.4	100	100	0	97	97.7	97.7			
<b>Trucks</b>	2	2	7	0	11	0	2	0	0	2	1	0	4	0	5	14	0	0	0	14	32	32			
<b>% Trucks</b>	0.8	1.2	4	0	1.8	0	2	0	0	1.5	10	0	2.2	0	2	3.6	0	0	0	3	2.2	2.2			
<b>Bicycles</b>	0	0	0	0	0	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	1	1			
<b>% Bicycles</b>	0	0	0	0	0	6.7	0	0	0	0.8	0	0	0	0	0	0	0	0	0	0	0.1	0.1			
<b>Peds</b>					7	-				4	-				4	-				3	-	18	-		
<b>% Peds</b>					38.9	-				22.2	-				22.2	-				16.7	-	-	-		



## INTERSECTION SIGNAL TIMING REPORT

Location	Whites Rd. (RR 38) and Oklahoma Dr./Granite Ct.		
Date	January 27, 2023	C&E No.	41544125
Prepared for	GHD	Prepared by	M.A

### AM Peak 06:15-09:15




Phase Number	2	4	6	8
Movement	NBTL	EBTL	SBTL	WBTL
Lead/Lag				
Lead-Lag Optimize				
Recall Mode	C-Max	None	C-Max	None
Maximum Split (s)	61.6	48.4	61.6	48.4
Maximum Split (%)	56.0%	44.0%	56.0%	44.0%
Minimum Split (s)	32	36	32	36
Yellow Time (s)	4.2	3.3	4.2	3.3
All-Red Time (s)	2.1	2.9	2.1	2.9
Minimum Initial (s)	20	8	20	8
Vehicle Extension (s)	3	3	3	3
Minimum Gap (s)	3	3	3	3
Time Before Reduce (s)	0	0	0	0
Time To Reduce (s)	0	0	0	0
Walk Time (s)	7	7	7	7
Flash Dont Walk (s)	18	22	18	22

#### Intersection Summary

Cycle Length	110
Control Type	Actuated-Coordinated
Natural Cycle	70
Offset: 83.6 (76%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green	

Splits and Phases: 252: RR 38 (WHITES ROAD) & GRANITE CT/OKLAHOMA DR



### PM Peak 14:30-19:00




Phase Number	2	4	6	7	8
Movement	NBTL	EBTL	SBTL	EBL	WBTL
Lead/Lag				Lead	Lag
Lead-Lag Optimize				Yes	Yes
Recall Mode	C-Max	None	C-Max	None	None
Maximum Split (s)	49.5	60.5	49.5	25.3	35.2
Maximum Split (%)	45.0%	55.0%	45.0%	23.0%	32.0%
Minimum Split (s)	32	36	32	8	36
Yellow Time (s)	4.2	3.3	4.2	3	3.3
All-Red Time (s)	2.1	2.9	2.1	0	2.9
Minimum Initial (s)	20	8	20	5	8
Vehicle Extension (s)	3	3	3	3	3
Minimum Gap (s)	3	3	3	3	3
Time Before Reduce (s)	0	0	0	0	0
Time To Reduce (s)	0	0	0	0	0
Walk Time (s)	7	7	7	7	7
Flash Dont Walk (s)	18	22	18	22	22

#### Intersection Summary

Cycle Length	110
Control Type	Actuated-Coordinated
Natural Cycle	80
Offset: 40.7 (37%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green	

Splits and Phases: 252: RR 38 (WHITES ROAD) & GRANITE CT/OKLAHOMA DR



### Weekend Peak 08:00 - 21:00




Phase Number	2	4	6	8
Movement	NBTL	EBTL	SBTL	WBTL
Lead/Lag				
Lead-Lag Optimize				
Recall Mode	C-Max	None	C-Max	None
Maximum Split (s)	37.6	42.4	37.6	42.4
Maximum Split (%)	47.0%	53.0%	47.0%	53.0%
Minimum Split (s)	32	36	32	36
Yellow Time (s)	4.2	3.3	4.2	3.3
All-Red Time (s)	2.1	2.9	2.1	2.9
Minimum Initial (s)	20	8	20	8
Vehicle Extension (s)	3	3	3	3
Minimum Gap (s)	3	3	3	3
Time Before Reduce (s)	0	0	0	0
Time To Reduce (s)	0	0	0	0
Walk Time (s)	7	7	7	7
Flash Dont Walk (s)	18	22	18	22

#### Intersection Summary

Cycle Length	80
Control Type	Actuated-Coordinated
Natural Cycle	70
Offset: 41.6 (52%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green	

Splits and Phases: 252: RR 38 (WHITES ROAD)/RR 38 (WHITES RD) & GRANITE CT/OKLAHOMA DR



*\*Please note a concerted effort has been made to ensure the accuracy and completeness of the data provided, however, inadvertent errors or omissions can still occur. Please bring any errors or omissions to the Region's attention.*





## INTERSECTION SIGNAL TIMING REPORT

Location	Whites Rd. (RR38) & Bayly St. (RR22)		
Date	2023-01-27	C&E No. 41544125	Prepared by M.A
Prepared for	GHD		

### AM Peak 06:15-09:15



Phase Number	2	5	8
Movement	SBTL	NBT	WBL
Lead/Lag			
Lead-Lag Optimize			
Recall Mode	C-Max	None	None
Maximum Split (s)	28.6	46.2	35.2
Maximum Split (%)	26.0%	42.0%	32.0%
Minimum Split (s)	27	39	32
Yellow Time (s)	4.4	4.4	4.2
All-Red Time (s)	2.6	2.6	2.2
Minimum Initial (s)	20	20	8
Vehicle Extension (s)	3	3	3
Minimum Gap (s)	3	3	3
Time Before Reduce (s)	0	0	0
Time To Reduce (s)	0	0	0
Walk Time (s)	5	7	7
Flash Dont Walk (s)	5	25	18

Intersection Summary	
Cycle Length	110
Control Type	Actuated-Coordinated
Natural Cycle	100
Offset: 24.2 (22%), Referenced to phase 2:SBTL, Start of Green	

Splits and Phases: 253: RR 38 (WHITES ROAD) & RR 22 (BAYLY ST)




### PM Peak 14:30-19:00



Phase Number	2	5	8
Movement	SBTL	NBT	WBL
Lead/Lag			
Lead-Lag Optimize			
Recall Mode	C-Max	None	None
Maximum Split (s)	30.8	44	35.2
Maximum Split (%)	28.0%	40.0%	32.0%
Minimum Split (s)	27	39	32
Yellow Time (s)	4.4	4.4	4.2
All-Red Time (s)	2.6	2.6	2.2
Minimum Initial (s)	20	20	8
Vehicle Extension (s)	3	3	3
Minimum Gap (s)	3	3	3
Time Before Reduce (s)	0	0	0
Time To Reduce (s)	0	0	0
Walk Time (s)	5	7	7
Flash Dont Walk (s)	5	25	18

Intersection Summary	
Cycle Length	110
Control Type	Actuated-Coordinated
Natural Cycle	110
Offset: 33 (30%), Referenced to phase 2:SBTL, Start of Green	

Splits and Phases: 253: RR 38 (WHITES ROAD) & RR 22 (BAYLY ST)




### Weekend Peak 08:00-21:00



Phase Number	2	5	8
Movement	SBTL	NBT	WBL
Lead/Lag			
Lead-Lag Optimize			
Recall Mode	C-Max	None	None
Maximum Split (s)	28	27.2	24.8
Maximum Split (%)	35.0%	34.0%	31.0%
Minimum Split (s)	27	39	32
Yellow Time (s)	4.4	4.4	4.2
All-Red Time (s)	2.6	2.6	2.2
Minimum Initial (s)	20	20	8
Vehicle Extension (s)	3	3	3
Minimum Gap (s)	3	3	3
Time Before Reduce (s)	0	0	0
Time To Reduce (s)	0	0	0
Walk Time (s)	5	7	7
Flash Dont Walk (s)	5	25	18

Intersection Summary	
Cycle Length	80
Control Type	Actuated-Coordinated
Natural Cycle	110
Offset: 37.6 (47%), Referenced to phase 2:SBTL, Start of Green	

Splits and Phases: 253: RR 38 (WHITES RD) & RR 22 (BAYLY ST)



*\*Please note a concerted effort has been made to ensure the accuracy and completeness of the data provided, however, inadvertent errors or omissions can still occur. Please bring any errors or omissions to the Region's attention.*

# **Appendix C**

## **Background Developments**

## 9.4 SITE TRAFFIC VOLUMES

Site traffic was developed for two scenarios: an intensification study condition and a proposed condition.

The intensification study condition is based on the increase in density within this Whites Precinct that is recommended in the *Kingston Road Corridor and Specialty Retailing Node Intensification Study*. It is our understanding that the proposed intensification would yield approximately 7,622 residents and 2,536 jobs, or approximately 2,077 residential units and 7,933 m<sup>2</sup> GFA of retail space on-site.

The as proposed trip generation forecast is associated with the planned uses on the Site in accordance with the current site plan.

The comparison of these two rates provides an indication of the relative change between the proposed and currently permitted uses on the Site.

### 9.4.1 Intensification Study Site Traffic Generation

The intensification study generation for the Site was calculated based upon the current residential and retail trip generated rates used for the proposed development.

**TABLE 23 INTENSIFICATION STUDY SITE VEHICLE TRAFFIC**

Land Use	AM Peak Hour			PM Peak Hour		
	In	Out	2-Way	In	Out	2-Way
Residential	115	430	545	375	255	630
Retail	80	80	160	110	110	220
<b>Total</b>	<b>195</b>	<b>510</b>	<b>705</b>	<b>485</b>	<b>365</b>	<b>850</b>

Notes:

1. All trips rounded to the nearest 5.

The intensification study condition is anticipated to generate approximately 705 and 850 two-way trips during the weekday morning and afternoon peak hours, respectively.



### 9.4.2 As Proposed Site Traffic Generation

Multi-modal travel forecasts were generated for the proposed development in **Section 8.0**. The resultant vehicular site traffic is summarized in **Table 24**.

**TABLE 24 PROPOSED SITE VEHICLE TRAFFIC**

	AM Peak Hour			PM Peak Hour		
	In	Out	2-Way	In	Out	2-Way
Residential	160	600	760	520	355	875
Office	60	10	70	5	50	55
Retail	25	25	50	35	35	70
<b>Total</b>	<b>245</b>	<b>635</b>	<b>880</b>	<b>560</b>	<b>440</b>	<b>1,000</b>

Notes:

1. All trips rounded to the nearest 5.

The Site is forecasted to generate a total of 880 and 1,000 two-way vehicle trips during the weekday morning and afternoon peak hours, respectively. Note these trips will include trips made to / from the proposed parking and pick-up / drop-off facilities.

### 9.4.3 Intensification Study Condition to Proposed Condition Comparison

A comparison of the intensification study condition to the proposed condition trip generation of the Site is provided in **Table 25**.

**TABLE 25 “AS-OF-RIGHT” TRIP GENERATION COMPARISON**

	AM Peak Hour			PM Peak Hour		
	In	Out	2-Way	In	Out	2-Way
As-Of-Right	195	510	705	485	365	850
As Proposed	245	635	880	560	440	1,000
<b>Total</b>	<b>50</b>	<b>125</b>	<b>175</b>	<b>75</b>	<b>75</b>	<b>150</b>

Notes:

1. All trips rounded to the nearest 5.

The results demonstrate that the proposed development plan would generate additional two-way trips during the weekday morning and afternoon peak hours than the intensification study condition. The new development plan would generate approximately 175 and 150 additional two-way trips during the weekday morning and afternoon peak hours, respectively. This indicates that the development plan would have a slightly greater traffic impact than the intensification study condition.



#### 9.4.4 Overall Site Traffic Generation

The resultant vehicle trip generation for the overall proposed development is summarized in **Table 26**.

Based on the foregoing, the Site is anticipated to generate in the order of 800 and 705 two-way net-new vehicle trips during the weekday morning and afternoon peak hours, respectively.

**TABLE 26 PROPOSED SITE VEHICLE TRAFFIC**

	AM Peak Hour			PM Peak Hour		
	In	Out	2-Way	In	Out	2-Way
Existing Site Traffic <sup>1</sup>	55	25	80	145	150	295
<b>Forecast Site Traffic</b>						
New Residential-Related Site Traffic (2,884 units)	160	600	760	520	355	875
New Office-Related Site Traffic (4,448 m <sup>2</sup> )	60	10	70	5	50	55
New Retail-Related Site Traffic (2,232 m <sup>2</sup> )	25	25	50	35	35	70
Total New Site Traffic	245	635	880	560	440	1,000
<b>Forecast Net New Site Traffic</b>						
<b>Forecast Net-New Site Traffic</b>	<b>190</b>	<b>610</b>	<b>800</b>	<b>415</b>	<b>290</b>	<b>705</b>

Notes:

1. Based upon traffic counts conducted at existing site access driveways by Spectrum Data on behalf of BA Group on March 26, 2019.
2. All trips rounded to the nearest 5.



## 9.4.5 Site Traffic Distribution and Assignment

### Residential Use

The trip distribution pattern for the residential use was established based upon a review of 2016 Transportation Tomorrow Survey (TTS) for home-based trips to / from the surrounding area during the weekday morning and afternoon peak periods. General direction of approach and routing is summarized in **Table 27**.

### Office Use

The trip distribution pattern for the office use was established based upon a review of 2016 Transportation Tomorrow Survey (TTS) for work-based trips to / from the surrounding area during the weekday morning and afternoon peak periods. General direction of approach and routing is summarized in **Table 27**.

### Retail Use

As previously discussed, given the size and ancillary nature of the proposed retail, it is expected to primarily serve the residents internal and external to the Site. As such, the majority of travel to / from the retail is expected to be pass-by trips.

The trip distribution pattern for the retail component of the Site was established based upon a review of existing area traffic patterns during the weekday morning and afternoon peak periods. The proposed directional distribution of site related traffic considers the orientation and configuration of the area street system, local access characteristics and movement restrictions.

The directional distribution of vehicle trips made to and from the Site has been based upon a review of information obtained from the 2016 Transportation Tomorrow Survey (TTS).

**TABLE 27 SITE TRAFFIC ASSIGNMENT**

To / From	Orientation to / from Site	Inbound	Outbound
<i>Residential Traffic Distribution</i>			
Whites Road	North	5%	5%
Whites Road	South	0%	0%
Highway 401	East	0%	15%
Highway 401	West	40%	50%
Kingston Road	East	35%	5%
Kingston Road	West	30%	20%
Bayly Street	East	0%	5%
<b>Total</b>		<b>100%</b>	<b>100%</b>
<i>Office Traffic Distribution</i>			
Whites Road	North	10%	10%
Whites Road	South	0%	0%
Highway 401	East	0%	45%
Highway 401	West	15%	20%
Kingston Road	East	60%	10%
Kingston Road	West	10%	10%
Bayly Street	East	5%	5%
<b>Total</b>		<b>100%</b>	<b>100%</b>

Notes:

1. Residential (home-based trips) and office (work-related trips) trip distribution is based on 2016 TTS data for vehicle trips to and from 2006 TTS traffic zones 10476-1049 and 1051 during the morning and afternoon peak hours.

The net-new site traffic assignment of the proposed development for the weekday morning and afternoon peak hours is shown in **Figure 25**.



## 9.5 FUTURE TOTAL TRAFFIC VOLUMES

Future total traffic volumes, which is the sum of background traffic volumes and forecast net-new site traffic volumes, are illustrated in **Figure 26** through **Figure 28**.



Date Plotted: March 30, 2020 File name: P:\58183\41\Graphics\CAD\Fig25-00-Net-New Site.dwg








FIGURE 25 FORECAST NET-NEW SITE TRAFFIC VOLUMES







# **Appendix D**

**Transportation Tomorrow Survey 2016**

**AM Inbound**

Thu Mar 02 2023 09:03:43 GMT-0500 (Eastern Standard Time) - Run Time: 2606ms

Cross Tabulation Query Form - Trip - 2016 v1.1

Row: Planning district of origin - pd\_orig  
 Column: 2006 GTA zone of destination - gta06\_dest

RowID:  
 ColG: (1046,1047,1048,1049)  
 TabG:

Filters:  
 Start time of trip - start\_time In 600-900  
 and  
 Trip purpose of destination - purp\_dest In H.

Trip 2016  
 Table:

.1  
 PD 1 of Toronto,82  
 PD 4 of Toronto,31  
 PD 13 of Toronto,26  
 Pickering,268  
 Ajax,20  
 Whitby,52  
 Whitchurch-Stouffville,30

**AM Outbound**

Thu Mar 02 2023 09:09:23 GMT-0500 (Eastern Standard Time) - Run Time: 2626ms

Cross Tabulation Query Form - Trip - 2016 v1.1

Row: Planning district of destination - pd\_dest  
 Column: 2006 GTA zone of origin - gta06\_orig

RowID:  
 ColG: (1046,1047,1048,1049)  
 TabG:

Filters:  
 Start time of trip - start\_time In 600-900  
 and  
 Trip purpose of origin - purp\_orig In H.

Trip 2016  
 Table:

	N	E	N Trips	E Trips
PD 1 of Toronto	1091	1	1091	0
PD 2 of Toronto	24	1	24	0
PD 3 of Toronto	100	1	100	0
PD 4 of Toronto	125	1	125	0
PD 5 of Toronto	236	1	236	0
PD 6 of Toronto	108	1	108	0
PD 8 of Toronto	42	1	42	0
PD 10 of Toron	48	1	48	0
PD 11 of Toron	52	1	52	0
PD 12 of Toron	161	1	161	0
PD 13 of Toron	551	1	551	0
PD 15 of Toron	230	0.5	115	115
PD 16 of Toron	252	0.5	126	126
Unbridge	7	1	7	0
Scouge	69	1	69	0
Pickering	1919	1	1919	0
Ajax	517	1	517	0
Whitby	131	1	131	0
Oshawa	224	1	224	0
Carrington	50	1	50	0
Richmond Hill	46	1	46	0
Whitchurch-Sto	30	0.5	15	15
Markham	336	1	336	0
King	54	1	54	0
Vaughan	55	1	55	0
Mississauga	105	1	105	0
Cambridge	19	1	19	0
Barrie	15	1	15	0
Peterborough	31	1	31	0
Hastings	29	1	29	0
<b>Sum</b>	<b>6657</b>		<b>6401</b>	<b>256</b>
			96%	4%

**PM Inbound**

Thu Mar 02 2023 09:07:44 GMT-0500 (Eastern Standard Time) - Run Time: 2363ms

Cross Tabulation Query Form - Trip - 2016 v1.1

Row: Planning district of origin - pd\_orig  
 Column: 2006 GTA zone of destination - gta06\_dest

RowID:  
 ColG: (1046,1047,1048,1049)  
 TabG:

Filters:  
 Start time of trip - start\_time In 1600-1900  
 and  
 Trip purpose of destination - purp\_dest In H.

Trip 2016  
 Table:

.1  
 PD 1 of Toronto,890  
 PD 2 of Toronto,24  
 PD 3 of Toronto,62  
 PD 4 of Toronto,40  
 PD 5 of Toronto,215  
 PD 6 of Toronto,66  
 PD 10 of Toronto,32  
 PD 11 of Toronto,66  
 PD 12 of Toronto,107  
 PD 13 of Toronto,622  
 PD 15 of Toronto,304  
 PD 16 of Toronto,182  
 Pickering,968  
 Ajax,300  
 Whitby,81  
 Oshawa,250  
 Carrington,71  
 Richmond Hill,34  
 Markham,158  
 Vaughan,149  
 Mississauga,75  
 Hamilton,16  
 Cambridge,19  
 Barrie,22  
 Peterborough,19

**PM Outbound**

Thu Mar 02 2023 09:09:01 GMT-0500 (Eastern Standard Time) - Run Time: 2356ms

Cross Tabulation Query Form - Trip - 2016 v1.1

Row: Planning district of destination - pd\_dest  
 Column: 2006 GTA zone of origin - gta06\_orig

RowID:  
 ColG: (1046,1047,1048,1049)  
 TabG:

Filters:  
 Start time of trip - start\_time In 1600-1900  
 and  
 Trip purpose of origin - purp\_orig In H.

Trip 2016  
 Table:















.1  
 PD 1 of Toronto,61  
 PD 4 of Toronto,24  
 PD 5 of Toronto,28  
 PD 6 of Toronto,13  
 PD 11 of Toronto,22  
 PD 13 of Toronto,222  
 PD 14 of Toronto,82  
 PD 15 of Toronto,66  
 PD 16 of Toronto,73  
 Pickering,799  
 Ajax,105  
 Whitby,51  
 Oshawa,40  
 Markham,27  
 Mississauga,28

# **Appendix E**

## **Synchro Outputs**

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Existing 2023 AM  
AM Peak Hour

						
Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			 
Traffic Volume (vph)	99	262	511	66	360	480
Future Volume (vph)	99	262	511	66	360	480
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Storage Length (m)	0.0	0.0		30.0	70.0	
Storage Lanes	1	1		1	1	
Taper Length (m)	2.5				30.0	
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt		0.850		0.850		
Flt Protected	0.950				0.950	0.992
Satd. Flow (prot)	1722	1570	3510	1601	1612	3367
Flt Permitted	0.950				0.950	0.992
Satd. Flow (perm)	1722	1570	3510	1601	1612	3367
Right Turn on Red		Yes		Yes		
Satd. Flow (RTOR)		114		62		
Link Speed (k/h)	60		60			60
Link Distance (m)	376.4		200.0			221.2
Travel Time (s)	22.6		12.0			13.3
Peak Hour Factor	0.84	0.84	0.84	0.84	0.84	0.84
Heavy Vehicles (%)	6%	4%	4%	2%	3%	3%
Adj. Flow (vph)	118	312	608	79	429	571
Shared Lane Traffic (%)					24%	
Lane Group Flow (vph)	118	312	608	79	326	674
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Right	Left	Right	Left	Left
Median Width(m)	3.7		3.7			3.7
Link Offset(m)	0.0		0.0			0.0
Crosswalk Width(m)	1.6		1.6			1.6
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24	14		14	24	
Number of Detectors	1	1	2	1	1	2
Detector Template	Left	Right	Thru	Right	Left	Thru
Leading Detector (m)	6.1	6.1	30.5	6.1	6.1	30.5
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)	6.1	6.1	1.8	6.1	6.1	1.8
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel						
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)			28.7			28.7
Detector 2 Size(m)			1.8			1.8
Detector 2 Type			Cl+Ex			Cl+Ex
Detector 2 Channel						
Detector 2 Extend (s)			0.0			0.0
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Existing 2023 AM  
AM Peak Hour




Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Permitted Phases	8	8		5		
Detector Phase	8	2	5	5	2	2
Switch Phase						
Minimum Initial (s)	5.0	20.0	20.0	20.0	20.0	20.0
Minimum Split (s)	32.0	27.0	39.0	39.0	27.0	27.0
Total Split (s)	35.2	28.6	46.2	46.2	28.6	28.6
Total Split (%)	32.0%	26.0%	42.0%	42.0%	26.0%	26.0%
Maximum Green (s)	28.8	21.6	39.2	39.2	21.6	21.6
Yellow Time (s)	4.2	4.4	4.4	4.4	4.4	4.4
All-Red Time (s)	2.2	2.6	2.6	2.6	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lead/Lag						
Lead-Lag Optimize?						
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Recall Mode	None	C-Max	None	None	C-Max	C-Max
Walk Time (s)	7.0	5.0	7.0	7.0	5.0	5.0
Flash Dont Walk (s)	18.0	5.0	25.0	25.0	5.0	5.0
Pedestrian Calls (#/hr)	0	0	0	0	0	0
Act Effct Green (s)	12.9	70.1	25.9	25.9	50.8	50.8
Actuated g/C Ratio	0.12	0.64	0.24	0.24	0.46	0.46
v/c Ratio	0.59	0.30	0.74	0.19	0.44	0.43
Control Delay	57.1	6.9	36.7	7.1	24.5	22.6
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.1	6.9	36.7	7.1	24.5	22.6
LOS	E	A	D	A	C	C
Approach Delay	20.7		33.3			23.2
Approach LOS	C		C			C

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 24.2 (22%), Referenced to phase 2:SBTL and 6:, Start of Green  
 Natural Cycle: 100  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.74  
 Intersection Signal Delay: 26.0  
 Intersection Capacity Utilization 55.8%  
 Analysis Period (min) 15  
 Intersection LOS: C  
 ICU Level of Service B

Splits and Phases: 1: Whites Road South & Bayly Street



Queues  
1: Whites Road South & Bayly Street

Existing 2023 AM  
AM Peak Hour


















Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Group Flow (vph)	118	312	608	79	326	674
v/c Ratio	0.59	0.30	0.74	0.19	0.44	0.43
Control Delay	57.1	6.9	36.7	7.1	24.5	22.6
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.1	6.9	36.7	7.1	24.5	22.6
Queue Length 50th (m)	24.4	16.0	65.0	0.0	50.1	51.6
Queue Length 95th (m)	37.7	31.2	71.2	5.0	84.6	75.1
Internal Link Dist (m)	352.4		176.0			197.2
Turn Bay Length (m)				30.0	70.0	
Base Capacity (vph)	450	1041	1250	610	744	1555
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.26	0.30	0.49	0.13	0.44	0.43
Intersection Summary						

























HCM Signalized Intersection Capacity Analysis  
 1: Whites Road South & Bayly Street

Existing 2023 AM  
 AM Peak Hour

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			  
Traffic Volume (vph)	99	262	511	66	360	480
Future Volume (vph)	99	262	511	66	360	480
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt	1.00	0.85	1.00	0.85	1.00	1.00
Flt Protected	0.95	1.00	1.00	1.00	0.95	0.99
Satd. Flow (prot)	1722	1570	3510	1601	1612	3369
Flt Permitted	0.95	1.00	1.00	1.00	0.95	0.99
Satd. Flow (perm)	1722	1570	3510	1601	1612	3369
Peak-hour factor, PHF	0.84	0.84	0.84	0.84	0.84	0.84
Adj. Flow (vph)	118	312	608	79	429	571
RTOR Reduction (vph)	0	48	0	47	0	0
Lane Group Flow (vph)	118	264	608	32	326	674
Heavy Vehicles (%)	6%	4%	4%	2%	3%	3%
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2
Permitted Phases	8	8		5		
Actuated Green, G (s)	12.9	63.7	25.9	25.9	50.8	50.8
Effective Green, g (s)	12.9	63.7	25.9	25.9	50.8	50.8
Actuated g/C Ratio	0.12	0.58	0.24	0.24	0.46	0.46
Clearance Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	201	909	826	376	744	1555
v/s Ratio Prot		0.13	c0.17		c0.20	0.20
v/s Ratio Perm	c0.07	0.03		0.02		
v/c Ratio	0.59	0.29	0.74	0.08	0.44	0.43
Uniform Delay, d1	46.0	11.7	38.9	32.8	20.0	19.9
Progression Factor	1.00	1.00	0.81	0.57	1.00	1.00
Incremental Delay, d2	4.3	0.2	3.3	0.1	1.9	0.9
Delay (s)	50.4	11.9	34.9	18.7	21.8	20.8
Level of Service	D	B	C	B	C	C
Approach Delay (s)	22.4		33.0			21.1
Approach LOS	C		C			C
<b>Intersection Summary</b>						
HCM 2000 Control Delay			25.3		HCM 2000 Level of Service	C
HCM 2000 Volume to Capacity ratio			0.55			
Actuated Cycle Length (s)			110.0		Sum of lost time (s)	20.4
Intersection Capacity Utilization			55.8%		ICU Level of Service	B
Analysis Period (min)			15			
c	Critical Lane Group					


Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Existing 2023 AM  
AM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	158	40	8	7	52	286	16	124	24	178	66	329
Future Volume (vph)	158	40	8	7	52	286	16	124	24	178	66	329
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (m)	20.0		0.0	15.0		15.0	20.0		0.0	20.0		0.0
Storage Lanes	1		0	1		1	1		0	1		1
Taper Length (m)	40.0			10.0			40.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.975				0.850		0.975				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1658	1833	0	1825	1921	1601	1722	1858	0	1755	1762	1601
Flt Permitted	0.715			0.719			0.704			0.642		
Satd. Flow (perm)	1248	1833	0	1381	1921	1601	1276	1858	0	1186	1762	1601
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		10				353		13				406
Link Speed (k/h)		50			50			60				60
Link Distance (m)		78.3			208.1			259.8				200.0
Travel Time (s)		5.6			15.0			15.6				12.0
Peak Hour Factor	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81
Heavy Vehicles (%)	7%	0%	13%	0%	0%	2%	6%	1%	0%	4%	9%	2%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Adj. Flow (vph)	195	49	10	9	64	353	20	153	30	220	81	406
Shared Lane Traffic (%)												
Lane Group Flow (vph)	195	59	0	9	64	353	20	183	0	220	81	406
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			3.7				3.7
Link Offset(m)		0.0			0.0			0.0				0.0
Crosswalk Width(m)		1.6			1.6			1.6				1.6
Two way Left Turn Lane												
Headway Factor	1.02	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	6.1	30.5		6.1	30.5	6.1	6.1	30.5		6.1	30.5	6.1
Trailing Detector (m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	6.1	1.8		6.1	1.8	6.1	6.1	1.8		6.1	1.8	6.1
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		28.7			28.7			28.7				28.7
Detector 2 Size(m)		1.8			1.8			1.8				1.8
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex				Cl+Ex
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0				0.0
Turn Type	Perm	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Existing 2023 AM  
AM Peak Hour




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Protected Phases		4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Detector Phase	4	4		8	8	8	2	2		6	6	6
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0	5.0	5.0	5.0		5.0	5.0	5.0
Minimum Split (s)	36.0	36.0		36.0	36.0	36.0	32.0	32.0		32.0	32.0	32.0
Total Split (s)	48.4	48.4		48.4	48.4	48.4	61.6	61.6		61.6	61.6	61.6
Total Split (%)	44.0%	44.0%		44.0%	44.0%	44.0%	56.0%	56.0%		56.0%	56.0%	56.0%
Maximum Green (s)	42.2	42.2		42.2	42.2	42.2	55.3	55.3		55.3	55.3	55.3
Yellow Time (s)	3.3	3.3		3.3	3.3	3.3	4.2	4.2		4.2	4.2	4.2
All-Red Time (s)	2.9	2.9		2.9	2.9	2.9	2.1	2.1		2.1	2.1	2.1
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lead/Lag												
Lead-Lag Optimize?												
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	None		None	None	None	C-Max	C-Max		C-Max	C-Max	C-Max
Walk Time (s)	7.0	7.0		7.0	7.0	7.0	7.0	7.0		7.0	7.0	7.0
Flash Dont Walk (s)	22.0	22.0		22.0	22.0	22.0	18.0	18.0		18.0	18.0	18.0
Pedestrian Calls (#/hr)	0	0		0	0	0	0	0		0	0	0
Act Effct Green (s)	22.8	22.8		22.8	22.8	22.8	74.7	74.7		74.7	74.7	74.7
Actuated g/C Ratio	0.21	0.21		0.21	0.21	0.21	0.68	0.68		0.68	0.68	0.68
v/c Ratio	0.75	0.15		0.03	0.16	0.58	0.02	0.14		0.27	0.07	0.33
Control Delay	58.1	28.5		30.6	33.9	7.4	7.9	7.2		11.1	10.4	5.0
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	58.1	28.5		30.6	33.9	7.4	7.9	7.2		11.1	10.4	5.0
LOS	E	C		C	C	A	A	A		B	B	A
Approach Delay		51.2			11.9			7.3			7.5	
Approach LOS		D			B			A			A	

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 83.6 (76%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green  
 Natural Cycle: 70  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.75  
 Intersection Signal Delay: 15.6  
 Intersection LOS: B  
 Intersection Capacity Utilization 50.0%  
 ICU Level of Service A  
 Analysis Period (min) 15

Splits and Phases: 2: Whites Road South & Oklahoma Drive



Queues  
2: Whites Road South & Oklahoma Drive

Existing 2023 AM  
AM Peak Hour

























Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	SBL	SBT	SBR
Lane Group Flow (vph)	195	59	9	64	353	20	183	220	81	406
v/c Ratio	0.75	0.15	0.03	0.16	0.58	0.02	0.14	0.27	0.07	0.33
Control Delay	58.1	28.5	30.6	33.9	7.4	7.9	7.2	11.1	10.4	5.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	58.1	28.5	30.6	33.9	7.4	7.9	7.2	11.1	10.4	5.0
Queue Length 50th (m)	39.6	8.6	1.6	11.3	0.0	1.3	11.6	11.3	4.2	0.9
Queue Length 95th (m)	50.9	15.4	4.7	18.3	12.1	4.3	22.2	35.5	16.1	38.0
Internal Link Dist (m)		54.3		184.1			235.8		176.0	
Turn Bay Length (m)	20.0		15.0		15.0	20.0		20.0		
Base Capacity (vph)	478	709	529	736	831	866	1265	805	1195	1217
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.41	0.08	0.02	0.09	0.42	0.02	0.14	0.27	0.07	0.33

Intersection Summary

HCM Signalized Intersection Capacity Analysis  
2: Whites Road South & Oklahoma Drive

Existing 2023 AM  
AM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	158	40	8	7	52	286	16	124	24	178	66	329
Future Volume (vph)	158	40	8	7	52	286	16	124	24	178	66	329
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lane Util. Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.00	1.00	1.00
Frt	1.00	0.97		1.00	1.00	0.85	1.00	0.98		1.00	1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00	1.00	0.95	1.00		0.95	1.00	1.00
Satd. Flow (prot)	1658	1832		1825	1921	1601	1722	1858		1755	1762	1601
Flt Permitted	0.72	1.00		0.72	1.00	1.00	0.70	1.00		0.64	1.00	1.00
Satd. Flow (perm)	1248	1832		1380	1921	1601	1277	1858		1186	1762	1601
Peak-hour factor, PHF	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81
Adj. Flow (vph)	195	49	10	9	64	353	20	153	30	220	81	406
RTOR Reduction (vph)	0	8	0	0	0	280	0	4	0	0	0	130
Lane Group Flow (vph)	195	51	0	9	64	73	20	179	0	220	81	276
Heavy Vehicles (%)	7%	0%	13%	0%	0%	2%	6%	1%	0%	4%	9%	2%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Turn Type	Perm	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm
Protected Phases		4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Actuated Green, G (s)	22.8	22.8		22.8	22.8	22.8	74.7	74.7		74.7	74.7	74.7
Effective Green, g (s)	22.8	22.8		22.8	22.8	22.8	74.7	74.7		74.7	74.7	74.7
Actuated g/C Ratio	0.21	0.21		0.21	0.21	0.21	0.68	0.68		0.68	0.68	0.68
Clearance Time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Lane Grp Cap (vph)	258	379		286	398	331	867	1261		805	1196	1087
v/s Ratio Prot		0.03			0.03			0.10			0.05	
v/s Ratio Perm	c0.16			0.01		0.05	0.02			c0.19		0.17
v/c Ratio	0.76	0.13		0.03	0.16	0.22	0.02	0.14		0.27	0.07	0.25
Uniform Delay, d1	41.0	35.6		34.8	35.8	36.2	5.8	6.3		7.0	5.9	6.8
Progression Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.22	1.38	4.44
Incremental Delay, d2	11.9	0.2		0.0	0.2	0.3	0.0	0.2		0.8	0.1	0.5
Delay (s)	52.9	35.7		34.8	35.9	36.6	5.8	6.5		9.3	8.3	30.9
Level of Service	D	D		C	D	D	A	A		A	A	C
Approach Delay (s)		48.9			36.4			6.4			21.6	
Approach LOS		D			D			A			C	
<b>Intersection Summary</b>												
HCM 2000 Control Delay			28.0				HCM 2000 Level of Service				C	
HCM 2000 Volume to Capacity ratio			0.39									
Actuated Cycle Length (s)			110.0				Sum of lost time (s)				12.5	
Intersection Capacity Utilization			50.0%				ICU Level of Service				A	
Analysis Period (min)			15									

c Critical Lane Group

Lanes, Volumes, Timings  
3: Granite Court/Oaklahoma Drive

Existing 2023 AM  
AM Peak Hour



Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (vph)	0	206	397	0	0	0
Future Volume (vph)	0	206	397	0	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00
<b>Fr</b>						
Flt Protected						
Satd. Flow (prot)	0	1883	1883	0	1883	0
Flt Permitted						
Satd. Flow (perm)	0	1883	1883	0	1883	0
Link Speed (k/h)		50	50		48	
Link Distance (m)		466.2	78.3		125.8	
Travel Time (s)		33.6	5.6		9.4	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	0	224	432	0	0	0
Shared Lane Traffic (%)						
Lane Group Flow (vph)	0	224	432	0	0	0
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Left	Left	Right	Left	Right
Median Width(m)		3.7	3.7		3.7	
Link Offset(m)		0.0	0.0		0.0	
Crosswalk Width(m)		1.6	1.6		1.6	
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24			14	24	14
Sign Control		Free	Free		Stop	
<b>Intersection Summary</b>						
Area Type:	Other					
Control Type:	Unsignalized					
Intersection Capacity Utilization	24.2%			ICU Level of Service A		
Analysis Period (min)	15					

# HCM Unsignalized Intersection Capacity Analysis

## 3: Granite Court/Oaklahoma Drive

Existing 2023 AM  
AM Peak Hour



Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		↔	↔		↔	
Traffic Volume (veh/h)	0	206	397	0	0	0
Future Volume (Veh/h)	0	206	397	0	0	0
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	224	432	0	0	0
<b>Pedestrians</b>						
Lane Width (m)						
Walking Speed (m/s)						
Percent Blockage						
Right turn flare (veh)						
Median type		None	None			
Median storage (veh)						
Upstream signal (m)	78					
pX, platoon unblocked	0.98				0.98	0.98
vC, conflicting volume	432				656	432
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	415				642	415
tC, single (s)	4.1				6.4	6.2
tC, 2 stage (s)						
tF (s)	2.2				3.5	3.3
p0 queue free %	100				100	100
cM capacity (veh/h)	1126				431	627
<b>Direction, Lane #</b>	<b>EB 1</b>	<b>WB 1</b>	<b>SB 1</b>			
Volume Total	224	432	0			
Volume Left	0	0	0			
Volume Right	0	0	0			
cSH	1126	1700	1700			
Volume to Capacity	0.00	0.25	0.00			
Queue Length 95th (m)	0.0	0.0	0.0			
Control Delay (s)	0.0	0.0	0.0			
Lane LOS			A			
Approach Delay (s)	0.0	0.0	0.0			
Approach LOS			A			
<b>Intersection Summary</b>						
Average Delay			0.0			
Intersection Capacity Utilization			24.2%	ICU Level of Service	A	
Analysis Period (min)			15			

---

**Network Totals**
















---

Number of Intersections	3
Total Delay (hr)	18
Stops (#)	1630
Average Speed (km/hr)	25
Total Travel Time (hr)	33
Distance Traveled (km)	809
Fuel Consumed (l)	173
Fuel Economy (km/l)	4.7
Unserviced Vehicles (#)	0
Vehicles in dilemma zone (#)	66
Performance Index	23.0



Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Existing 2023 PM  
PM Peak Hour

						
Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			  
Traffic Volume (vph)	131	317	503	178	689	470
Future Volume (vph)	131	317	503	178	689	470
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Storage Length (m)	0.0	0.0		30.0	70.0	
Storage Lanes	1	1		1	1	
Taper Length (m)	2.5				30.0	
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt		0.850		0.850		
Flt Protected	0.950				0.950	0.981
Satd. Flow (prot)	1789	1617	3544	1585	1628	3363
Flt Permitted	0.950				0.950	0.981
Satd. Flow (perm)	1789	1617	3544	1585	1628	3363
Right Turn on Red		Yes		Yes		
Satd. Flow (RTOR)		137		164		
Link Speed (k/h)	60		60			60
Link Distance (m)	376.4		200.0			221.2
Travel Time (s)	22.6		12.0			13.3
Peak Hour Factor	0.95	0.95	0.95	0.95	0.95	0.95
Heavy Vehicles (%)	2%	1%	3%	3%	2%	2%
Adj. Flow (vph)	138	334	529	187	725	495
Shared Lane Traffic (%)					45%	
Lane Group Flow (vph)	138	334	529	187	399	821
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Right	Left	Right	Left	Left
Median Width(m)	3.7		3.7			3.7
Link Offset(m)	0.0		0.0			0.0
Crosswalk Width(m)	1.6		1.6			1.6
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24	14		14	24	
Number of Detectors	1	1	2	1	1	2
Detector Template	Left	Right	Thru	Right	Left	Thru
Leading Detector (m)	6.1	6.1	30.5	6.1	6.1	30.5
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)	6.1	6.1	1.8	6.1	6.1	1.8
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel						
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)			28.7			28.7
Detector 2 Size(m)			1.8			1.8
Detector 2 Type			Cl+Ex			Cl+Ex
Detector 2 Channel						
Detector 2 Extend (s)			0.0			0.0
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street


Existing 2023 PM  
PM Peak Hour

Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Permitted Phases	8	8		5		
Detector Phase	8	2	5	5	2	2
Switch Phase						
Minimum Initial (s)	8.0	20.0	20.0	20.0	20.0	20.0
Minimum Split (s)	32.0	27.0	39.0	39.0	27.0	27.0
Total Split (s)	35.2	30.8	44.0	44.0	30.8	30.8
Total Split (%)	32.0%	28.0%	40.0%	40.0%	28.0%	28.0%
Maximum Green (s)	28.8	23.8	37.0	37.0	23.8	23.8
Yellow Time (s)	4.2	4.4	4.4	4.4	4.4	4.4
All-Red Time (s)	2.2	2.6	2.6	2.6	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lead/Lag						
Lead-Lag Optimize?						
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Recall Mode	None	C-Max	None	None	C-Max	C-Max
Walk Time (s)	7.0	5.0	7.0	7.0	5.0	5.0
Flash Dont Walk (s)	18.0	5.0	25.0	25.0	5.0	5.0
Pedestrian Calls (#/hr)	0	0	0	0	0	0
Act Effct Green (s)	13.8	72.2	23.8	23.8	52.0	52.0
Actuated g/C Ratio	0.13	0.66	0.22	0.22	0.47	0.47
v/c Ratio	0.61	0.30	0.69	0.40	0.52	0.52
Control Delay	56.7	5.8	57.3	25.4	25.3	23.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	56.7	5.8	57.3	25.4	25.3	23.2
LOS	E	A	E	C	C	C
Approach Delay	20.7		48.9			23.9
Approach LOS	C		D			C

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 33 (30%), Referenced to phase 2:SBTL and 6:, Start of Green  
 Natural Cycle: 100  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.69  
 Intersection Signal Delay: 30.7  
 Intersection LOS: C  
 Intersection Capacity Utilization 62.9%  
 ICU Level of Service B  
 Analysis Period (min) 15

Splits and Phases: 1: Whites Road South & Bayly Street



Queues  
1: Whites Road South & Bayly Street

Existing 2023 PM  
PM Peak Hour

















Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Group Flow (vph)	138	334	529	187	399	821
v/c Ratio	0.61	0.30	0.69	0.40	0.52	0.52
Control Delay	56.7	5.8	57.3	25.4	25.3	23.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	56.7	5.8	57.3	25.4	25.3	23.2
Queue Length 50th (m)	28.5	15.0	61.2	15.9	63.5	65.2
Queue Length 95th (m)	45.9	32.6	m74.6	m28.1	113.9	101.3
Internal Link Dist (m)	352.4		176.0			197.2
Turn Bay Length (m)				30.0	70.0	
Base Capacity (vph)	468	1108	1192	641	769	1589
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.29	0.30	0.44	0.29	0.52	0.52

Intersection Summary

m Volume for 95th percentile queue is metered by upstream signal.























HCM Signalized Intersection Capacity Analysis  
 1: Whites Road South & Bayly Street

Existing 2023 PM  
 PM Peak Hour

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			 
Traffic Volume (vph)	131	317	503	178	689	470
Future Volume (vph)	131	317	503	178	689	470
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt	1.00	0.85	1.00	0.85	1.00	1.00
Flt Protected	0.95	1.00	1.00	1.00	0.95	0.98
Satd. Flow (prot)	1789	1617	3544	1585	1628	3361
Flt Permitted	0.95	1.00	1.00	1.00	0.95	0.98
Satd. Flow (perm)	1789	1617	3544	1585	1628	3361
Peak-hour factor, PHF	0.95	0.95	0.95	0.95	0.95	0.95
Adj. Flow (vph)	138	334	529	187	725	495
RTOR Reduction (vph)	0	55	0	129	0	0
Lane Group Flow (vph)	138	279	529	58	399	821
Heavy Vehicles (%)	2%	1%	3%	3%	2%	2%
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2
Permitted Phases	8	8		5		
Actuated Green, G (s)	13.8	65.8	23.8	23.8	52.0	52.0
Effective Green, g (s)	13.8	65.8	23.8	23.8	52.0	52.0
Actuated g/C Ratio	0.13	0.60	0.22	0.22	0.47	0.47
Clearance Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	224	967	766	342	769	1588
v/s Ratio Prot		0.14	c0.15		c0.25	0.24
v/s Ratio Perm	c0.08	0.04		0.04		
v/c Ratio	0.62	0.29	0.69	0.17	0.52	0.52
Uniform Delay, d1	45.6	10.7	39.7	35.1	20.3	20.2
Progression Factor	1.00	1.00	1.35	3.16	1.00	1.00
Incremental Delay, d2	5.0	0.2	2.2	0.2	2.5	1.2
Delay (s)	50.6	10.9	55.8	110.9	22.8	21.4
Level of Service	D	B	E	F	C	C
Approach Delay (s)	22.5		70.2			21.9
Approach LOS	C		E			C
<b>Intersection Summary</b>						
HCM 2000 Control Delay			36.4		HCM 2000 Level of Service	D
HCM 2000 Volume to Capacity ratio			0.58			
Actuated Cycle Length (s)			110.0		Sum of lost time (s)	20.4
Intersection Capacity Utilization			62.9%		ICU Level of Service	B
Analysis Period (min)			15			
c Critical Lane Group						

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Existing 2023 PM  
PM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	387	68	11	10	55	186	15	102	13	251	172	177
Future Volume (vph)	387	68	11	10	55	186	15	102	13	251	172	177
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (m)	20.0		0.0	15.0		15.0	20.0		0.0	20.0		0.0
Storage Lanes	1		0	1		1	1		0	1		1
Taper Length (m)	40.0			10.0			40.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.979				0.850		0.983				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1706	1881	0	1659	1921	1601	1825	1856	0	1807	1902	1570
Flt Permitted	0.549			0.702			0.641			0.677		
Satd. Flow (perm)	986	1881	0	1226	1921	1601	1231	1856	0	1288	1902	1570
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		11				200		7				190
Link Speed (k/h)		50			50			60				60
Link Distance (m)		78.3			208.1			259.8				200.0
Travel Time (s)		5.6			15.0			15.6				12.0
Peak Hour Factor	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93
Heavy Vehicles (%)	4%	0%	0%	10%	0%	2%	0%	2%	0%	1%	1%	4%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Adj. Flow (vph)	416	73	12	11	59	200	16	110	14	270	185	190
Shared Lane Traffic (%)												
Lane Group Flow (vph)	416	85	0	11	59	200	16	124	0	270	185	190
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			3.7				3.7
Link Offset(m)		0.0			0.0			0.0				0.0
Crosswalk Width(m)		1.6			1.6			1.6				1.6
Two way Left Turn Lane												
Headway Factor	1.02	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	6.1	30.5		6.1	30.5	6.1	6.1	30.5		6.1	30.5	6.1
Trailing Detector (m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	6.1	1.8		6.1	1.8	6.1	6.1	1.8		6.1	1.8	6.1
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		28.7			28.7			28.7				28.7
Detector 2 Size(m)		1.8			1.8			1.8				1.8
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex				Cl+Ex
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0				0.0
Turn Type	pm+pt	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive


Existing 2023 PM  
PM Peak Hour

	↖	→	↘	↙	←	↖	↙	↑	↘	↘	↓	↙
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Protected Phases	7	4			8			2			6	
Permitted Phases	4			8	8	8	2			6		6
Detector Phase	7	4		8	8	8	2	2		6	6	6
Switch Phase												
Minimum Initial (s)	5.0	8.0		8.0	8.0	8.0	20.0	20.0		20.0	20.0	20.0
Minimum Split (s)	9.5	36.0		36.0	36.0	36.0	32.0	32.0		32.0	32.0	32.0
Total Split (s)	25.3	60.5		35.2	35.2	35.2	49.5	49.5		49.5	49.5	49.5
Total Split (%)	23.0%	55.0%		32.0%	32.0%	32.0%	45.0%	45.0%		45.0%	45.0%	45.0%
Maximum Green (s)	22.3	54.3		29.0	29.0	29.0	43.2	43.2		43.2	43.2	43.2
Yellow Time (s)	3.0	3.3		3.3	3.3	3.3	4.2	4.2		4.2	4.2	4.2
All-Red Time (s)	0.0	2.9		2.9	2.9	2.9	2.1	2.1		2.1	2.1	2.1
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lead/Lag	Lead			Lag	Lag	Lag						
Lead-Lag Optimize?	Yes			Yes	Yes	Yes						
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	None		None	None	None	C-Max	C-Max		C-Max	C-Max	C-Max
Walk Time (s)		7.0		7.0	7.0	7.0	7.0	7.0		7.0	7.0	7.0
Flash Dont Walk (s)		22.0		22.0	22.0	22.0	18.0	18.0		18.0	18.0	18.0
Pedestrian Calls (#/hr)		0		0	0	0	0	0		0	0	0
Act Effct Green (s)	38.2	35.0		9.7	9.7	9.7	62.5	62.5		62.5	62.5	62.5
Actuated g/C Ratio	0.35	0.32		0.09	0.09	0.09	0.57	0.57		0.57	0.57	0.57
v/c Ratio	0.85	0.14		0.10	0.35	0.62	0.02	0.12		0.37	0.17	0.20
Control Delay	49.0	23.3		46.9	52.3	15.4	11.4	11.2		9.2	5.9	2.5
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	49.0	23.3		46.9	52.3	15.4	11.4	11.2		9.2	5.9	2.5
LOS	D	C		D	D	B	B	B		A	A	A
Approach Delay		44.6			24.7			11.2			6.3	
Approach LOS		D			C			B			A	

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 40.7 (37%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green  
 Natural Cycle: 80  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.85  
 Intersection Signal Delay: 22.3  
 Intersection LOS: C  
 Intersection Capacity Utilization 63.4%  
 ICU Level of Service B  
 Analysis Period (min) 15

Splits and Phases: 2: Whites Road South & Oklahoma Drive



Queues  
2: Whites Road South & Oklahoma Drive

Existing 2023 PM  
PM Peak Hour



Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	SBL	SBT	SBR
Lane Group Flow (vph)	416	85	11	59	200	16	124	270	185	190
v/c Ratio	0.85	0.14	0.10	0.35	0.62	0.02	0.12	0.37	0.17	0.20
Control Delay	49.0	23.3	46.9	52.3	15.4	11.4	11.2	9.2	5.9	2.5
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	49.0	23.3	46.9	52.3	15.4	11.4	11.2	9.2	5.9	2.5
Queue Length 50th (m)	77.5	11.4	2.2	12.2	0.0	1.4	10.7	30.4	10.1	1.9
Queue Length 95th (m)	#113.1	21.5	7.5	24.0	20.4	4.9	21.3	19.9	14.5	5.7
Internal Link Dist (m)		54.3		184.1			235.8		176.0	
Turn Bay Length (m)	20.0		15.0		15.0	20.0		20.0		
Base Capacity (vph)	488	934	323	506	569	699	1057	732	1081	974
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.85	0.09	0.03	0.12	0.35	0.02	0.12	0.37	0.17	0.20

Intersection Summary

# 95th percentile volume exceeds capacity, queue may be longer.  
Queue shown is maximum after two cycles.

# HCM Signalized Intersection Capacity Analysis

## 2: Whites Road South & Oklahoma Drive

Existing 2023 PM  
PM Peak Hour

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	387	68	11	10	55	186	15	102	13	251	172	177
Future Volume (vph)	387	68	11	10	55	186	15	102	13	251	172	177
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lane Util. Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.00	1.00	1.00
Frt	1.00	0.98		1.00	1.00	0.85	1.00	0.98		1.00	1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00	1.00	0.95	1.00		0.95	1.00	1.00
Satd. Flow (prot)	1706	1880		1659	1921	1601	1825	1856		1807	1902	1570
Flt Permitted	0.55	1.00		0.70	1.00	1.00	0.64	1.00		0.68	1.00	1.00
Satd. Flow (perm)	985	1880		1226	1921	1601	1231	1856		1289	1902	1570
Peak-hour factor, PHF	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93
Adj. Flow (vph)	416	73	12	11	59	200	16	110	14	270	185	190
RTOR Reduction (vph)	0	8	0	0	0	182	0	3	0	0	0	82
Lane Group Flow (vph)	416	78	0	11	59	18	16	121	0	270	185	108
Heavy Vehicles (%)	4%	0%	0%	10%	0%	2%	0%	2%	0%	1%	1%	4%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Turn Type	pm+pt	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm
Protected Phases	7	4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Actuated Green, G (s)	35.0	35.0		9.7	9.7	9.7	62.5	62.5		62.5	62.5	62.5
Effective Green, g (s)	35.0	35.0		9.7	9.7	9.7	62.5	62.5		62.5	62.5	62.5
Actuated g/C Ratio	0.32	0.32		0.09	0.09	0.09	0.57	0.57		0.57	0.57	0.57
Clearance Time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Lane Grp Cap (vph)	459	598		108	169	141	699	1054		732	1080	892
v/s Ratio Prot	c0.18	0.04			0.03			0.07			0.10	
v/s Ratio Perm	c0.10			0.01		0.01	0.01			c0.21		0.07
v/c Ratio	0.91	0.13		0.10	0.35	0.13	0.02	0.11		0.37	0.17	0.12
Uniform Delay, d1	34.1	26.7		46.1	47.2	46.2	10.4	11.0		13.0	11.4	11.0
Progression Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		0.57	0.47	1.13
Incremental Delay, d2	21.2	0.1		0.4	1.3	0.4	0.1	0.2		1.3	0.3	0.3
Delay (s)	55.3	26.8		46.6	48.4	46.6	10.5	11.2		8.7	5.6	12.7
Level of Service	E	C		D	D	D	B	B		A	A	B
Approach Delay (s)		50.5			47.0			11.1			9.0	
Approach LOS		D			D			B			A	
<b>Intersection Summary</b>												
HCM 2000 Control Delay			29.1				HCM 2000 Level of Service				C	
HCM 2000 Volume to Capacity ratio			0.58									
Actuated Cycle Length (s)			110.0				Sum of lost time (s)				15.5	
Intersection Capacity Utilization			63.4%				ICU Level of Service				B	
Analysis Period (min)			15									

c Critical Lane Group



Lanes, Volumes, Timings  
3: Granite Court/Oaklahoma Drive

Existing 2023 PM  
PM Peak Hour



Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (vph)	0	466	247	0	0	0
Future Volume (vph)	0	466	247	0	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00
<b>Fr</b>						
Flt Protected						
Satd. Flow (prot)	0	1883	1883	0	1883	0
Flt Permitted						
Satd. Flow (perm)	0	1883	1883	0	1883	0
Link Speed (k/h)		50	50		48	
Link Distance (m)		466.2	78.3		125.8	
Travel Time (s)		33.6	5.6		9.4	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	0	507	268	0	0	0
Shared Lane Traffic (%)						
Lane Group Flow (vph)	0	507	268	0	0	0
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Left	Left	Right	Left	Right
Median Width(m)		3.7	3.7		3.7	
Link Offset(m)		0.0	0.0		0.0	
Crosswalk Width(m)		1.6	1.6		1.6	
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24			14	24	14
Sign Control		Free	Free		Stop	
<b>Intersection Summary</b>						
Area Type:	Other					
Control Type:	Unsignalized					
Intersection Capacity Utilization	27.9%			ICU Level of Service A		
Analysis Period (min)	15					

# HCM Unsignalized Intersection Capacity Analysis

## 3: Granite Court/Oaklahoma Drive

Existing 2023 PM  
PM Peak Hour



Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (veh/h)	0	466	247	0	0	0
Future Volume (Veh/h)	0	466	247	0	0	0
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	507	268	0	0	0
<b>Pedestrians</b>						
Lane Width (m)						
Walking Speed (m/s)						
Percent Blockage						
Right turn flare (veh)						
Median type		None	None			
Median storage (veh)						
Upstream signal (m)	78					
pX, platoon unblocked	0.98			0.98	0.98	
vC, conflicting volume	268			775	268	
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	239			758	239	
tC, single (s)	4.1			6.4	6.2	
tC, 2 stage (s)						
tF (s)	2.2			3.5	3.3	
p0 queue free %	100			100	100	
cM capacity (veh/h)	1297			366	782	
<b>Direction, Lane #</b>	<b>EB 1</b>	<b>WB 1</b>	<b>SB 1</b>			
Volume Total	507	268	0			
Volume Left	0	0	0			
Volume Right	0	0	0			
cSH	1297	1700	1700			
Volume to Capacity	0.00	0.16	0.00			
Queue Length 95th (m)	0.0	0.0	0.0			
Control Delay (s)	0.0	0.0	0.0			
Lane LOS			A			
Approach Delay (s)	0.0	0.0	0.0			
Approach LOS			A			
<b>Intersection Summary</b>						
Average Delay			0.0			
Intersection Capacity Utilization			27.9%	ICU Level of Service	A	
Analysis Period (min)			15			

---













**Network Totals**

---

Number of Intersections	3
Total Delay (hr)	28
Stops (#)	2346
Average Speed (km/hr)	22
Total Travel Time (hr)	47
Distance Traveled (km)	1040
Fuel Consumed (l)	243
Fuel Economy (km/l)	4.3
Unserviced Vehicles (#)	0
Vehicles in dilemma zone (#)	47
Performance Index	35.0

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Future Background 2027 AM  
AM Peak Hour

						
Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Volume (vph)	103	272	534	68	374	508
Future Volume (vph)	103	272	534	68	374	508
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Storage Length (m)	0.0	0.0		30.0	70.0	
Storage Lanes	1	1		1	1	
Taper Length (m)	2.5				30.0	
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt		0.850		0.850		
Flt Protected	0.950				0.950	0.993
Satd. Flow (prot)	1722	1570	3510	1601	1612	3371
Flt Permitted	0.950				0.950	0.993
Satd. Flow (perm)	1722	1570	3510	1601	1612	3371
Right Turn on Red		Yes		Yes		
Satd. Flow (RTOR)		102		61		
Link Speed (k/h)	60		60			60
Link Distance (m)	376.4		200.0			221.2
Travel Time (s)	22.6		12.0			13.3
Peak Hour Factor	0.84	0.84	0.84	0.84	0.84	0.84
Heavy Vehicles (%)	6%	4%	4%	2%	3%	3%
Adj. Flow (vph)	123	324	636	81	445	605
Shared Lane Traffic (%)					24%	
Lane Group Flow (vph)	123	324	636	81	338	712
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Right	Left	Right	Left	Left
Median Width(m)	3.7		3.7			3.7
Link Offset(m)	0.0		0.0			0.0
Crosswalk Width(m)	1.6		1.6			1.6
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24	14		14	24	
Number of Detectors	1	1	2	1	1	2
Detector Template	Left	Right	Thru	Right	Left	Thru
Leading Detector (m)	6.1	6.1	30.5	6.1	6.1	30.5
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)	6.1	6.1	1.8	6.1	6.1	1.8
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel						
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)			28.7			28.7
Detector 2 Size(m)			1.8			1.8
Detector 2 Type			Cl+Ex			Cl+Ex
Detector 2 Channel						
Detector 2 Extend (s)			0.0			0.0
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Future Background 2027 AM  
AM Peak Hour




Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Permitted Phases	8	8		5		
Detector Phase	8	2	5	5	2	2
Switch Phase						
Minimum Initial (s)	5.0	20.0	20.0	20.0	20.0	20.0
Minimum Split (s)	32.0	27.0	39.0	39.0	27.0	27.0
Total Split (s)	35.2	28.6	46.2	46.2	28.6	28.6
Total Split (%)	32.0%	26.0%	42.0%	42.0%	26.0%	26.0%
Maximum Green (s)	28.8	21.6	39.2	39.2	21.6	21.6
Yellow Time (s)	4.2	4.4	4.4	4.4	4.4	4.4
All-Red Time (s)	2.2	2.6	2.6	2.6	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lead/Lag						
Lead-Lag Optimize?						
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Recall Mode	None	C-Max	None	None	C-Max	C-Max
Walk Time (s)	7.0	5.0	7.0	7.0	5.0	5.0
Flash Dont Walk (s)	18.0	5.0	25.0	25.0	5.0	5.0
Pedestrian Calls (#/hr)	0	0	0	0	0	0
Act Effct Green (s)	13.2	69.2	26.8	26.8	49.6	49.6
Actuated g/C Ratio	0.12	0.63	0.24	0.24	0.45	0.45
v/c Ratio	0.60	0.32	0.75	0.19	0.46	0.47
Control Delay	57.2	7.9	36.5	7.5	25.9	24.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.2	7.9	36.5	7.5	25.9	24.0
LOS	E	A	D	A	C	C
Approach Delay	21.4		33.2			24.6
Approach LOS	C		C			C

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 24.2 (22%), Referenced to phase 2:SBTL and 6:, Start of Green  
 Natural Cycle: 100  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.75  
 Intersection Signal Delay: 26.8  
 Intersection LOS: C  
 Intersection Capacity Utilization 56.0%  
 ICU Level of Service B  
 Analysis Period (min) 15

Splits and Phases: 1: Whites Road South & Bayly Street



Queues  
1: Whites Road South & Bayly Street
















Future Background 2027 AM  
AM Peak Hour



Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Group Flow (vph)	123	324	636	81	338	712
v/c Ratio	0.60	0.32	0.75	0.19	0.46	0.47
Control Delay	57.2	7.9	36.5	7.5	25.9	24.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.2	7.9	36.5	7.5	25.9	24.0
Queue Length 50th (m)	25.4	19.2	66.0	0.0	54.2	57.3
Queue Length 95th (m)	38.9	35.3	74.4	5.5	89.6	81.5
Internal Link Dist (m)	352.4		176.0			197.2
Turn Bay Length (m)				30.0	70.0	
Base Capacity (vph)	450	1026	1250	609	727	1521
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.27	0.32	0.51	0.13	0.46	0.47
<b>Intersection Summary</b>						























HCM Signalized Intersection Capacity Analysis  
1: Whites Road South & Bayly Street

Future Background 2027 AM  
AM Peak Hour

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			  
Traffic Volume (vph)	103	272	534	68	374	508
Future Volume (vph)	103	272	534	68	374	508
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt	1.00	0.85	1.00	0.85	1.00	1.00
Flt Protected	0.95	1.00	1.00	1.00	0.95	0.99
Satd. Flow (prot)	1722	1570	3510	1601	1612	3369
Flt Permitted	0.95	1.00	1.00	1.00	0.95	0.99
Satd. Flow (perm)	1722	1570	3510	1601	1612	3369
Peak-hour factor, PHF	0.84	0.84	0.84	0.84	0.84	0.84
Adj. Flow (vph)	123	324	636	81	445	605
RTOR Reduction (vph)	0	44	0	46	0	0
Lane Group Flow (vph)	123	280	636	35	338	712
Heavy Vehicles (%)	6%	4%	4%	2%	3%	3%
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2
Permitted Phases	8	8		5		
Actuated Green, G (s)	13.2	62.8	26.8	26.8	49.6	49.6
Effective Green, g (s)	13.2	62.8	26.8	26.8	49.6	49.6
Actuated g/C Ratio	0.12	0.57	0.24	0.24	0.45	0.45
Clearance Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	206	896	855	390	726	1519
v/s Ratio Prot		0.14	c0.18		0.21	c0.21
v/s Ratio Perm	c0.07	0.04		0.02		
v/c Ratio	0.60	0.31	0.74	0.09	0.47	0.47
Uniform Delay, d1	45.9	12.3	38.4	32.2	21.0	21.0
Progression Factor	1.00	1.00	0.81	0.59	1.00	1.00
Incremental Delay, d2	4.6	0.2	3.3	0.1	2.1	1.0
Delay (s)	50.5	12.5	34.7	19.2	23.1	22.1
Level of Service	D	B	C	B	C	C
Approach Delay (s)	23.0		32.9			22.4
Approach LOS	C		C			C
<b>Intersection Summary</b>						
HCM 2000 Control Delay			25.9		HCM 2000 Level of Service	C
HCM 2000 Volume to Capacity ratio			0.57			
Actuated Cycle Length (s)			110.0		Sum of lost time (s)	20.4
Intersection Capacity Utilization			56.0%		ICU Level of Service	B
Analysis Period (min)			15			
c	Critical Lane Group					

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Background 2027 AM  
AM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	164	41	8	7	54	297	16	132	24	185	77	342
Future Volume (vph)	164	41	8	7	54	297	16	132	24	185	77	342
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (m)	20.0		0.0	15.0		15.0	20.0		0.0	20.0		0.0
Storage Lanes	1		0	1		1	1		0	1		1
Taper Length (m)	40.0			10.0			40.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.975				0.850		0.977				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1658	1834	0	1825	1921	1601	1722	1861	0	1755	1762	1601
Flt Permitted	0.713			0.717			0.695			0.636		
Satd. Flow (perm)	1244	1834	0	1377	1921	1601	1260	1861	0	1175	1762	1601
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		10				367		12				422
Link Speed (k/h)		50			50			60				60
Link Distance (m)		78.3			208.1			259.8				200.0
Travel Time (s)		5.6			15.0			15.6				12.0
Peak Hour Factor	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81
Heavy Vehicles (%)	7%	0%	13%	0%	0%	2%	6%	1%	0%	4%	9%	2%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Adj. Flow (vph)	202	51	10	9	67	367	20	163	30	228	95	422
Shared Lane Traffic (%)												
Lane Group Flow (vph)	202	61	0	9	67	367	20	193	0	228	95	422
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			3.7				3.7
Link Offset(m)		0.0			0.0			0.0				0.0
Crosswalk Width(m)		1.6			1.6			1.6				1.6
Two way Left Turn Lane												
Headway Factor	1.02	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	6.1	30.5		6.1	30.5	6.1	6.1	30.5		6.1	30.5	6.1
Trailing Detector (m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	6.1	1.8		6.1	1.8	6.1	6.1	1.8		6.1	1.8	6.1
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		28.7			28.7			28.7				28.7
Detector 2 Size(m)		1.8			1.8			1.8				1.8
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex				Cl+Ex
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0				0.0
Turn Type	Perm	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm



Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Background 2027 AM  
AM Peak Hour




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Protected Phases		4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Detector Phase	4	4		8	8	8	2	2		6	6	6
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0	5.0	5.0	5.0		5.0	5.0	5.0
Minimum Split (s)	36.0	36.0		36.0	36.0	36.0	32.0	32.0		32.0	32.0	32.0
Total Split (s)	48.4	48.4		48.4	48.4	48.4	61.6	61.6		61.6	61.6	61.6
Total Split (%)	44.0%	44.0%		44.0%	44.0%	44.0%	56.0%	56.0%		56.0%	56.0%	56.0%
Maximum Green (s)	42.2	42.2		42.2	42.2	42.2	55.3	55.3		55.3	55.3	55.3
Yellow Time (s)	3.3	3.3		3.3	3.3	3.3	4.2	4.2		4.2	4.2	4.2
All-Red Time (s)	2.9	2.9		2.9	2.9	2.9	2.1	2.1		2.1	2.1	2.1
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lead/Lag												
Lead-Lag Optimize?												
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	None		None	None	None	C-Max	C-Max		C-Max	C-Max	C-Max
Walk Time (s)	7.0	7.0		7.0	7.0	7.0	7.0	7.0		7.0	7.0	7.0
Flash Dont Walk (s)	22.0	22.0		22.0	22.0	22.0	18.0	18.0		18.0	18.0	18.0
Pedestrian Calls (#/hr)	0	0		0	0	0	0	0		0	0	0
Act Effct Green (s)	23.5	23.5		23.5	23.5	23.5	74.0	74.0		74.0	74.0	74.0
Actuated g/C Ratio	0.21	0.21		0.21	0.21	0.21	0.67	0.67		0.67	0.67	0.67
v/c Ratio	0.76	0.15		0.03	0.16	0.58	0.02	0.15		0.29	0.08	0.35
Control Delay	57.7	28.1		30.0	33.4	7.2	8.2	7.6		12.8	11.8	5.9
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	57.7	28.1		30.0	33.4	7.2	8.2	7.6		12.8	11.8	5.9
LOS	E	C		C	C	A	A	A		B	B	A
Approach Delay		50.9			11.7			7.7			8.8	
Approach LOS		D			B			A			A	

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 83.6 (76%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green  
 Natural Cycle: 70  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.76  
 Intersection Signal Delay: 16.1  
 Intersection LOS: B  
 Intersection Capacity Utilization 51.5%  
 ICU Level of Service A  
 Analysis Period (min) 15

Splits and Phases: 2: Whites Road South & Oklahoma Drive



Queues  
2: Whites Road South & Oklahoma Drive

Future Background 2027 AM  
AM Peak Hour

























Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	SBL	SBT	SBR
Lane Group Flow (vph)	202	61	9	67	367	20	193	228	95	422
v/c Ratio	0.76	0.15	0.03	0.16	0.58	0.02	0.15	0.29	0.08	0.35
Control Delay	57.7	28.1	30.0	33.4	7.2	8.2	7.6	12.8	11.8	5.9
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.7	28.1	30.0	33.4	7.2	8.2	7.6	12.8	11.8	5.9
Queue Length 50th (m)	41.0	8.9	1.5	11.8	0.0	1.3	12.8	11.7	4.8	0.8
Queue Length 95th (m)	52.2	15.7	4.6	18.7	12.0	4.3	24.0	40.3	20.1	47.4
Internal Link Dist (m)		54.3		184.1			235.8		176.0	
Turn Bay Length (m)	20.0		15.0		15.0	20.0		20.0		
Base Capacity (vph)	477	709	528	736	840	847	1255	790	1184	1214
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.42	0.09	0.02	0.09	0.44	0.02	0.15	0.29	0.08	0.35

Intersection Summary

# HCM Signalized Intersection Capacity Analysis

## 2: Whites Road South & Oklahoma Drive

Future Background 2027 AM  
AM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	164	41	8	7	54	297	16	132	24	185	77	342
Future Volume (vph)	164	41	8	7	54	297	16	132	24	185	77	342
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lane Util. Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.00	1.00	1.00
Frt	1.00	0.98		1.00	1.00	0.85	1.00	0.98		1.00	1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00	1.00	0.95	1.00		0.95	1.00	1.00
Satd. Flow (prot)	1658	1835		1825	1921	1601	1722	1861		1755	1762	1601
Flt Permitted	0.71	1.00		0.72	1.00	1.00	0.70	1.00		0.64	1.00	1.00
Satd. Flow (perm)	1245	1835		1378	1921	1601	1260	1861		1175	1762	1601
Peak-hour factor, PHF	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81
Adj. Flow (vph)	202	51	10	9	67	367	20	163	30	228	95	422
RTOR Reduction (vph)	0	8	0	0	0	289	0	4	0	0	0	138
Lane Group Flow (vph)	202	53	0	9	67	78	20	189	0	228	95	284
Heavy Vehicles (%)	7%	0%	13%	0%	0%	2%	6%	1%	0%	4%	9%	2%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Turn Type	Perm	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm
Protected Phases		4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Actuated Green, G (s)	23.5	23.5		23.5	23.5	23.5	74.0	74.0		74.0	74.0	74.0
Effective Green, g (s)	23.5	23.5		23.5	23.5	23.5	74.0	74.0		74.0	74.0	74.0
Actuated g/C Ratio	0.21	0.21		0.21	0.21	0.21	0.67	0.67		0.67	0.67	0.67
Clearance Time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Lane Grp Cap (vph)	265	392		294	410	342	847	1251		790	1185	1077
v/s Ratio Prot		0.03			0.03			0.10			0.05	
v/s Ratio Perm	c0.16			0.01		0.05	0.02			c0.19		0.18
v/c Ratio	0.76	0.14		0.03	0.16	0.23	0.02	0.15		0.29	0.08	0.26
Uniform Delay, d1	40.6	35.0		34.2	35.2	35.8	6.0	6.6		7.3	6.2	7.2
Progression Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.35	1.51	5.22
Incremental Delay, d2	12.2	0.2		0.0	0.2	0.3	0.1	0.3		0.8	0.1	0.6
Delay (s)	52.8	35.2		34.3	35.4	36.1	6.0	6.8		10.7	9.5	38.0
Level of Service	D	D		C	D	D	A	A		B	A	D
Approach Delay (s)		48.7			36.0			6.7			26.0	
Approach LOS		D			D			A			C	
<b>Intersection Summary</b>												
HCM 2000 Control Delay			29.8			HCM 2000 Level of Service			C			
HCM 2000 Volume to Capacity ratio			0.40									
Actuated Cycle Length (s)			110.0			Sum of lost time (s)			12.5			
Intersection Capacity Utilization			51.5%			ICU Level of Service			A			
Analysis Period (min)			15									

c Critical Lane Group

Lanes, Volumes, Timings  
3: Granite Court/Oaklahoma Drive

Future Background 2027 AM  
AM Peak Hour



Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (vph)	0	214	413	0	0	0
Future Volume (vph)	0	214	413	0	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00
<b>Fr</b>						
Flt Protected						
Satd. Flow (prot)	0	1883	1883	0	1883	0
Flt Permitted						
Satd. Flow (perm)	0	1883	1883	0	1883	0
Link Speed (k/h)		50	50		48	
Link Distance (m)		466.2	78.3		125.8	
Travel Time (s)		33.6	5.6		9.4	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	0	233	449	0	0	0
Shared Lane Traffic (%)						
Lane Group Flow (vph)	0	233	449	0	0	0
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Left	Left	Right	Left	Right
Median Width(m)		3.7	3.7		3.7	
Link Offset(m)		0.0	0.0		0.0	
Crosswalk Width(m)		1.6	1.6		1.6	
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24			14	24	14
Sign Control		Free	Free		Stop	
<b>Intersection Summary</b>						
Area Type:	Other					
Control Type:	Unsignalized					
Intersection Capacity Utilization	25.1%			ICU Level of Service A		
Analysis Period (min)	15					

HCM Unsignalized Intersection Capacity Analysis  
3: Granite Court/Oaklahoma Drive

Future Background 2027 AM  
AM Peak Hour



Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (veh/h)	0	214	413	0	0	0
Future Volume (Veh/h)	0	214	413	0	0	0
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	233	449	0	0	0
<b>Pedestrians</b>						
Lane Width (m)						
Walking Speed (m/s)						
Percent Blockage						
Right turn flare (veh)						
Median type		None	None			
Median storage (veh)						
Upstream signal (m)	78					
pX, platoon unblocked	0.98				0.98	0.98
vC, conflicting volume	449				682	449
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	431				668	431
tC, single (s)	4.1				6.4	6.2
tC, 2 stage (s)						
tF (s)	2.2				3.5	3.3
p0 queue free %	100				100	100
cM capacity (veh/h)	1109				416	614
<b>Direction, Lane #</b>	<b>EB 1</b>	<b>WB 1</b>	<b>SB 1</b>			
Volume Total	233	449	0			
Volume Left	0	0	0			
Volume Right	0	0	0			
cSH	1109	1700	1700			
Volume to Capacity	0.00	0.26	0.00			
Queue Length 95th (m)	0.0	0.0	0.0			
Control Delay (s)	0.0	0.0	0.0			
Lane LOS			A			
Approach Delay (s)	0.0	0.0	0.0			
Approach LOS			A			
<b>Intersection Summary</b>						
Average Delay			0.0			
Intersection Capacity Utilization			25.1%	ICU Level of Service	A	
Analysis Period (min)			15			

---















**Network Totals**

---

Number of Intersections	3
Total Delay (hr)	20
Stops (#)	1753
Average Speed (km/hr)	24
Total Travel Time (hr)	35
Distance Traveled (km)	845
Fuel Consumed (l)	184
Fuel Economy (km/l)	4.6
Unserviced Vehicles (#)	0
Vehicles in dilemma zone (#)	68
Performance Index	24.7

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Future Background 2027 PM  
PM Peak Hour

						
Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			 
Traffic Volume (vph)	136	329	532	185	716	494
Future Volume (vph)	136	329	532	185	716	494
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Storage Length (m)	0.0	0.0		30.0	70.0	
Storage Lanes	1	1		1	1	
Taper Length (m)	2.5				30.0	
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt		0.850		0.850		
Flt Protected	0.950				0.950	0.981
Satd. Flow (prot)	1789	1617	3544	1585	1628	3363
Flt Permitted	0.950				0.950	0.981
Satd. Flow (perm)	1789	1617	3544	1585	1628	3363
Right Turn on Red		Yes		Yes		
Satd. Flow (RTOR)		121		161		
Link Speed (k/h)	60		60			60
Link Distance (m)	376.4		200.0			221.2
Travel Time (s)	22.6		12.0			13.3
Peak Hour Factor	0.95	0.95	0.95	0.95	0.95	0.95
Heavy Vehicles (%)	2%	1%	3%	3%	2%	2%
Adj. Flow (vph)	143	346	560	195	754	520
Shared Lane Traffic (%)					45%	
Lane Group Flow (vph)	143	346	560	195	415	859
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Right	Left	Right	Left	Left
Median Width(m)	3.7		3.7			3.7
Link Offset(m)	0.0		0.0			0.0
Crosswalk Width(m)	1.6		1.6			1.6
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24	14		14	24	
Number of Detectors	1	1	2	1	1	2
Detector Template	Left	Right	Thru	Right	Left	Thru
Leading Detector (m)	6.1	6.1	30.5	6.1	6.1	30.5
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)	6.1	6.1	1.8	6.1	6.1	1.8
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel						
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)			28.7			28.7
Detector 2 Size(m)			1.8			1.8
Detector 2 Type			Cl+Ex			Cl+Ex
Detector 2 Channel						
Detector 2 Extend (s)			0.0			0.0
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Future Background 2027 PM  
PM Peak Hour




Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Permitted Phases	8	8		5		
Detector Phase	8	2	5	5	2	2
Switch Phase						
Minimum Initial (s)	8.0	20.0	20.0	20.0	20.0	20.0
Minimum Split (s)	32.0	27.0	39.0	39.0	27.0	27.0
Total Split (s)	35.2	30.8	44.0	44.0	30.8	30.8
Total Split (%)	32.0%	28.0%	40.0%	40.0%	28.0%	28.0%
Maximum Green (s)	28.8	23.8	37.0	37.0	23.8	23.8
Yellow Time (s)	4.2	4.4	4.4	4.4	4.4	4.4
All-Red Time (s)	2.2	2.6	2.6	2.6	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lead/Lag						
Lead-Lag Optimize?						
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Recall Mode	None	C-Max	None	None	C-Max	C-Max
Walk Time (s)	7.0	5.0	7.0	7.0	5.0	5.0
Flash Dont Walk (s)	18.0	5.0	25.0	25.0	5.0	5.0
Pedestrian Calls (#/hr)	0	0	0	0	0	0
Act Effct Green (s)	14.1	71.1	24.9	24.9	50.6	50.6
Actuated g/C Ratio	0.13	0.65	0.23	0.23	0.46	0.46
v/c Ratio	0.62	0.32	0.70	0.40	0.55	0.56
Control Delay	56.8	6.8	58.8	27.0	27.3	24.9
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	56.8	6.8	58.8	27.0	27.3	24.9
LOS	E	A	E	C	C	C
Approach Delay	21.4		50.6			25.7
Approach LOS	C		D			C

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 33 (30%), Referenced to phase 2:SBTL and 6:, Start of Green  
 Natural Cycle: 100  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.70  
 Intersection Signal Delay: 32.3  
 Intersection LOS: C  
 Intersection Capacity Utilization 64.2%  
 ICU Level of Service C  
 Analysis Period (min) 15

Splits and Phases: 1: Whites Road South & Bayly Street





Queues

1: Whites Road South & Bayly Street


















Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Group Flow (vph)	143	346	560	195	415	859
v/c Ratio	0.62	0.32	0.70	0.40	0.55	0.56
Control Delay	56.8	6.8	58.8	27.0	27.3	24.9
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	56.8	6.8	58.8	27.0	27.3	24.9
Queue Length 50th (m)	29.5	18.0	64.7	17.0	68.5	70.9
Queue Length 95th (m)	47.1	38.5	m80.9	m30.3	124.0	110.9
Internal Link Dist (m)	352.4		176.0			197.2
Turn Bay Length (m)				30.0	70.0	
Base Capacity (vph)	468	1088	1192	639	748	1547
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.31	0.32	0.47	0.31	0.55	0.56

Intersection Summary

m Volume for 95th percentile queue is metered by upstream signal.























HCM Signalized Intersection Capacity Analysis  
 1: Whites Road South & Bayly Street

Future Background 2027 PM  
 PM Peak Hour

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			  
Traffic Volume (vph)	136	329	532	185	716	494
Future Volume (vph)	136	329	532	185	716	494
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt	1.00	0.85	1.00	0.85	1.00	1.00
Flt Protected	0.95	1.00	1.00	1.00	0.95	0.98
Satd. Flow (prot)	1789	1617	3544	1585	1628	3362
Flt Permitted	0.95	1.00	1.00	1.00	0.95	0.98
Satd. Flow (perm)	1789	1617	3544	1585	1628	3362
Peak-hour factor, PHF	0.95	0.95	0.95	0.95	0.95	0.95
Adj. Flow (vph)	143	346	560	195	754	520
RTOR Reduction (vph)	0	50	0	125	0	0
Lane Group Flow (vph)	143	296	560	70	415	859
Heavy Vehicles (%)	2%	1%	3%	3%	2%	2%
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2
Permitted Phases	8	8		5		
Actuated Green, G (s)	14.1	64.7	24.9	24.9	50.6	50.6
Effective Green, g (s)	14.1	64.7	24.9	24.9	50.6	50.6
Actuated g/C Ratio	0.13	0.59	0.23	0.23	0.46	0.46
Clearance Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	229	951	802	358	748	1546
v/s Ratio Prot		0.14	c0.16		0.25	c0.26
v/s Ratio Perm	c0.08	0.04		0.04		
v/c Ratio	0.62	0.31	0.70	0.20	0.55	0.56
Uniform Delay, d1	45.4	11.4	39.1	34.5	21.5	21.5
Progression Factor	1.00	1.00	1.41	3.09	1.00	1.00
Incremental Delay, d2	5.2	0.2	2.2	0.2	3.0	1.4
Delay (s)	50.7	11.6	57.5	106.6	24.5	23.0
Level of Service	D	B	E	F	C	C
Approach Delay (s)	23.0		70.2			23.5
Approach LOS	C		E			C
<b>Intersection Summary</b>						
HCM 2000 Control Delay			37.4		HCM 2000 Level of Service	D
HCM 2000 Volume to Capacity ratio			0.61			
Actuated Cycle Length (s)			110.0		Sum of lost time (s)	20.4
Intersection Capacity Utilization			64.2%		ICU Level of Service	C
Analysis Period (min)			15			
c Critical Lane Group						

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Background 2027 PM  
PM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	402	70	11	10	57	193	15	106	13	261	183	184
Future Volume (vph)	402	70	11	10	57	193	15	106	13	261	183	184
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (m)	20.0		0.0	15.0		15.0	20.0		0.0	20.0		0.0
Storage Lanes	1		0	1		1	1		0	1		1
Taper Length (m)	40.0			10.0			40.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.979				0.850		0.984				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1706	1881	0	1659	1921	1601	1825	1857	0	1807	1902	1570
Flt Permitted	0.549			0.701			0.634			0.675		
Satd. Flow (perm)	986	1881	0	1224	1921	1601	1218	1857	0	1284	1902	1570
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		11				208		6				198
Link Speed (k/h)		50			50			60			60	
Link Distance (m)		78.3			208.1			259.8			200.0	
Travel Time (s)		5.6			15.0			15.6			12.0	
Peak Hour Factor	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93
Heavy Vehicles (%)	4%	0%	0%	10%	0%	2%	0%	2%	0%	1%	1%	4%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Adj. Flow (vph)	432	75	12	11	61	208	16	114	14	281	197	198
Shared Lane Traffic (%)												
Lane Group Flow (vph)	432	87	0	11	61	208	16	128	0	281	197	198
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			3.7			3.7	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			1.6			1.6			1.6	
Two way Left Turn Lane												
Headway Factor	1.02	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	6.1	30.5		6.1	30.5	6.1	6.1	30.5		6.1	30.5	6.1
Trailing Detector (m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	6.1	1.8		6.1	1.8	6.1	6.1	1.8		6.1	1.8	6.1
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	pm+pt	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Background 2027 PM  
PM Peak Hour




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Protected Phases	7	4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Detector Phase	7	4		8	8	8	2	2		6	6	6
Switch Phase												
Minimum Initial (s)	5.0	8.0		8.0	8.0	8.0	20.0	20.0		20.0	20.0	20.0
Minimum Split (s)	9.5	36.0		36.0	36.0	36.0	32.0	32.0		32.0	32.0	32.0
Total Split (s)	28.0	64.0		36.0	36.0	36.0	46.0	46.0		46.0	46.0	46.0
Total Split (%)	25.5%	58.2%		32.7%	32.7%	32.7%	41.8%	41.8%		41.8%	41.8%	41.8%
Maximum Green (s)	25.0	57.8		29.8	29.8	29.8	39.7	39.7		39.7	39.7	39.7
Yellow Time (s)	3.0	3.3		3.3	3.3	3.3	4.2	4.2		4.2	4.2	4.2
All-Red Time (s)	0.0	2.9		2.9	2.9	2.9	2.1	2.1		2.1	2.1	2.1
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lead/Lag	Lead			Lag	Lag	Lag						
Lead-Lag Optimize?	Yes			Yes	Yes	Yes						
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	None		None	None	None	C-Max	C-Max		C-Max	C-Max	C-Max
Walk Time (s)		7.0		7.0	7.0	7.0	7.0	7.0		7.0	7.0	7.0
Flash Dont Walk (s)		22.0		22.0	22.0	22.0	18.0	18.0		18.0	18.0	18.0
Pedestrian Calls (#/hr)		0		0	0	0	0	0		0	0	0
Act Effct Green (s)	40.9	37.7		9.8	9.8	9.8	59.8	59.8		59.8	59.8	59.8
Actuated g/C Ratio	0.37	0.34		0.09	0.09	0.09	0.54	0.54		0.54	0.54	0.54
v/c Ratio	0.82	0.13		0.10	0.36	0.63	0.02	0.13		0.40	0.19	0.21
Control Delay	42.7	21.7		46.7	52.4	15.3	12.7	12.6		7.9	5.1	2.2
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	42.7	21.7		46.7	52.4	15.3	12.7	12.6		7.9	5.1	2.2
LOS	D	C		D	D	B	B	B		A	A	A
Approach Delay		39.2			24.6			12.6			5.4	
Approach LOS		D			C			B			A	

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 40.7 (37%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green  
 Natural Cycle: 80  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.82  
 Intersection Signal Delay: 20.2  
 Intersection LOS: C  
 Intersection Capacity Utilization 64.6%  
 ICU Level of Service C  
 Analysis Period (min) 15

Splits and Phases: 2: Whites Road South & Oklahoma Drive



Queues  
2: Whites Road South & Oklahoma Drive

Future Background 2027 PM  
PM Peak Hour

























Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	SBL	SBT	SBR
Lane Group Flow (vph)	432	87	11	61	208	16	128	281	197	198
v/c Ratio	0.82	0.13	0.10	0.36	0.63	0.02	0.13	0.40	0.19	0.21
Control Delay	42.7	21.7	46.7	52.4	15.3	12.7	12.6	7.9	5.1	2.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	42.7	21.7	46.7	52.4	15.3	12.7	12.6	7.9	5.1	2.2
Queue Length 50th (m)	78.1	11.2	2.2	12.7	0.0	1.5	12.0	21.6	10.1	2.1
Queue Length 95th (m)	105.4	21.0	7.5	24.6	20.9	5.2	23.4	20.4	15.2	5.7
Internal Link Dist (m)		54.3		184.1			235.8		176.0	
Turn Bay Length (m)	20.0		15.0		15.0	20.0		20.0		
Base Capacity (vph)	530	993	331	520	585	662	1012	698	1034	944
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.82	0.09	0.03	0.12	0.36	0.02	0.13	0.40	0.19	0.21

Intersection Summary

# HCM Signalized Intersection Capacity Analysis

## 2: Whites Road South & Oklahoma Drive

Future Background 2027 PM  
PM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	402	70	11	10	57	193	15	106	13	261	183	184
Future Volume (vph)	402	70	11	10	57	193	15	106	13	261	183	184
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lane Util. Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.00	1.00	1.00
Frt	1.00	0.98		1.00	1.00	0.85	1.00	0.98		1.00	1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00	1.00	0.95	1.00		0.95	1.00	1.00
Satd. Flow (prot)	1706	1881		1659	1921	1601	1825	1857		1807	1902	1570
Flt Permitted	0.55	1.00		0.70	1.00	1.00	0.63	1.00		0.67	1.00	1.00
Satd. Flow (perm)	986	1881		1223	1921	1601	1218	1857		1284	1902	1570
Peak-hour factor, PHF	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93
Adj. Flow (vph)	432	75	12	11	61	208	16	114	14	281	197	198
RTOR Reduction (vph)	0	7	0	0	0	189	0	3	0	0	0	90
Lane Group Flow (vph)	432	80	0	11	61	19	16	125	0	281	197	108
Heavy Vehicles (%)	4%	0%	0%	10%	0%	2%	0%	2%	0%	1%	1%	4%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Turn Type	pm+pt	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm
Protected Phases	7	4			8			2				6
Permitted Phases	4			8		8	2			6		6
Actuated Green, G (s)	37.7	37.7		9.8	9.8	9.8	59.8	59.8		59.8	59.8	59.8
Effective Green, g (s)	37.7	37.7		9.8	9.8	9.8	59.8	59.8		59.8	59.8	59.8
Actuated g/C Ratio	0.34	0.34		0.09	0.09	0.09	0.54	0.54		0.54	0.54	0.54
Clearance Time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Lane Grp Cap (vph)	500	644		108	171	142	662	1009		698	1033	853
v/s Ratio Prot	c0.20	0.04			0.03			0.07				0.10
v/s Ratio Perm	c0.10			0.01		0.01	0.01			c0.22		0.07
v/c Ratio	0.86	0.12		0.10	0.36	0.13	0.02	0.12		0.40	0.19	0.13
Uniform Delay, d1	31.9	24.8		46.1	47.1	46.2	11.6	12.3		14.7	12.8	12.3
Progression Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		0.41	0.36	0.86
Incremental Delay, d2	14.4	0.1		0.4	1.3	0.4	0.1	0.3		1.5	0.4	0.3
Delay (s)	46.3	24.9		46.5	48.4	46.6	11.7	12.5		7.5	4.9	10.9
Level of Service	D	C		D	D	D	B	B		A	A	B
Approach Delay (s)		42.7			47.0			12.4			7.8	
Approach LOS		D			D			B			A	
<b>Intersection Summary</b>												
HCM 2000 Control Delay			26.1				HCM 2000 Level of Service			C		
HCM 2000 Volume to Capacity ratio			0.60									
Actuated Cycle Length (s)			110.0				Sum of lost time (s)			15.5		
Intersection Capacity Utilization			64.6%				ICU Level of Service			C		
Analysis Period (min)			15									

c Critical Lane Group

Lanes, Volumes, Timings  
3: Granite Court/Oaklahoma Drive

Future Background 2027 PM  
PM Peak Hour




Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (vph)	0	484	257	0	0	0
Future Volume (vph)	0	484	257	0	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00
<b>Fr</b>						
Flt Protected						
Satd. Flow (prot)	0	1883	1883	0	1883	0
Flt Permitted						
Satd. Flow (perm)	0	1883	1883	0	1883	0
Link Speed (k/h)		50	50		48	
Link Distance (m)		466.2	78.3		125.8	
Travel Time (s)		33.6	5.6		9.4	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	0	526	279	0	0	0
Shared Lane Traffic (%)						
Lane Group Flow (vph)	0	526	279	0	0	0
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Left	Left	Right	Left	Right
Median Width(m)		3.7	3.7		3.7	
Link Offset(m)		0.0	0.0		0.0	
Crosswalk Width(m)		1.6	1.6		1.6	
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24			14	24	14
Sign Control		Free	Free		Stop	
<b>Intersection Summary</b>						
Area Type:	Other					
Control Type:	Unsignalized					
Intersection Capacity Utilization	28.8%			ICU Level of Service A		
Analysis Period (min)	15					

# HCM Unsignalized Intersection Capacity Analysis

## 3: Granite Court/Oaklahoma Drive

Future Background 2027 PM  
PM Peak Hour



Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		↔	↔		↔	
Traffic Volume (veh/h)	0	484	257	0	0	0
Future Volume (Veh/h)	0	484	257	0	0	0
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	526	279	0	0	0
<b>Pedestrians</b>						
Lane Width (m)						
Walking Speed (m/s)						
Percent Blockage						
Right turn flare (veh)						
Median type		None	None			
Median storage (veh)						
Upstream signal (m)	78					
pX, platoon unblocked	0.98			0.98	0.98	
vC, conflicting volume	279			805	279	
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	248			788	248	
tC, single (s)	4.1			6.4	6.2	
tC, 2 stage (s)						
tF (s)	2.2			3.5	3.3	
p0 queue free %	100			100	100	
cM capacity (veh/h)	1285			351	771	
<b>Direction, Lane #</b>	<b>EB 1</b>	<b>WB 1</b>	<b>SB 1</b>			
Volume Total	526	279	0			
Volume Left	0	0	0			
Volume Right	0	0	0			
cSH	1285	1700	1700			
Volume to Capacity	0.00	0.16	0.00			
Queue Length 95th (m)	0.0	0.0	0.0			
Control Delay (s)	0.0	0.0	0.0			
Lane LOS			A			
Approach Delay (s)	0.0	0.0	0.0			
Approach LOS			A			
<b>Intersection Summary</b>						
Average Delay			0.0			
Intersection Capacity Utilization			28.8%	ICU Level of Service	A	
Analysis Period (min)			15			



---
















**Network Totals**

---

Number of Intersections	3
Total Delay (hr)	30
Stops (#)	2452
Average Speed (km/hr)	22
Total Travel Time (hr)	49
Distance Traveled (km)	1084
Fuel Consumed (l)	254
Fuel Economy (km/l)	4.3
Unserved Vehicles (#)	0
Vehicles in dilemma zone (#)	48
Performance Index	36.8

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Future Background 2032 AM  
AM Peak Hour

						
Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			  
Traffic Volume (vph)	105	279	551	70	384	530
Future Volume (vph)	105	279	551	70	384	530
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Storage Length (m)	0.0	0.0		30.0	70.0	
Storage Lanes	1	1		1	1	
Taper Length (m)	2.5				30.0	
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt		0.850		0.850		
Flt Protected	0.950				0.950	0.993
Satd. Flow (prot)	1722	1570	3510	1601	1612	3371
Flt Permitted	0.950				0.950	0.993
Satd. Flow (perm)	1722	1570	3510	1601	1612	3371
Right Turn on Red		Yes		Yes		
Satd. Flow (RTOR)		95		61		
Link Speed (k/h)	60		60			60
Link Distance (m)	376.4		200.0			221.2
Travel Time (s)	22.6		12.0			13.3
Peak Hour Factor	0.84	0.84	0.84	0.84	0.84	0.84
Heavy Vehicles (%)	6%	4%	4%	2%	3%	3%
Adj. Flow (vph)	125	332	656	83	457	631
Shared Lane Traffic (%)					23%	
Lane Group Flow (vph)	125	332	656	83	352	736
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Right	Left	Right	Left	Left
Median Width(m)	3.7		3.7			3.7
Link Offset(m)	0.0		0.0			0.0
Crosswalk Width(m)	1.6		1.6			1.6
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24	14		14	24	
Number of Detectors	1	1	2	1	1	2
Detector Template	Left	Right	Thru	Right	Left	Thru
Leading Detector (m)	6.1	6.1	30.5	6.1	6.1	30.5
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)	6.1	6.1	1.8	6.1	6.1	1.8
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel						
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)			28.7			28.7
Detector 2 Size(m)			1.8			1.8
Detector 2 Type			Cl+Ex			Cl+Ex
Detector 2 Channel						
Detector 2 Extend (s)			0.0			0.0
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Future Background 2032 AM  
AM Peak Hour




Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Permitted Phases	8	8		5		
Detector Phase	8	2	5	5	2	2
Switch Phase						
Minimum Initial (s)	5.0	20.0	20.0	20.0	20.0	20.0
Minimum Split (s)	32.0	27.0	39.0	39.0	27.0	27.0
Total Split (s)	35.2	28.6	46.2	46.2	28.6	28.6
Total Split (%)	32.0%	26.0%	42.0%	42.0%	26.0%	26.0%
Maximum Green (s)	28.8	21.6	39.2	39.2	21.6	21.6
Yellow Time (s)	4.2	4.4	4.4	4.4	4.4	4.4
All-Red Time (s)	2.2	2.6	2.6	2.6	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lead/Lag						
Lead-Lag Optimize?						
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Recall Mode	None	C-Max	None	None	C-Max	C-Max
Walk Time (s)	7.0	5.0	7.0	7.0	5.0	5.0
Flash Dont Walk (s)	18.0	5.0	25.0	25.0	5.0	5.0
Pedestrian Calls (#/hr)	0	0	0	0	0	0
Act Effct Green (s)	13.3	68.7	27.3	27.3	49.0	49.0
Actuated g/C Ratio	0.12	0.62	0.25	0.25	0.45	0.45
v/c Ratio	0.60	0.33	0.75	0.19	0.49	0.49
Control Delay	57.2	8.5	36.4	7.6	27.0	24.8
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.2	8.5	36.4	7.6	27.0	24.8
LOS	E	A	D	A	C	C
Approach Delay	21.8		33.2			25.5
Approach LOS	C		C			C

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 24.2 (22%), Referenced to phase 2:SBTL and 6:, Start of Green  
 Natural Cycle: 100  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.75  
 Intersection Signal Delay: 27.3  
 Intersection Capacity Utilization 56.7%  
 Analysis Period (min) 15  
 Intersection LOS: C  
 ICU Level of Service B

Splits and Phases: 1: Whites Road South & Bayly Street



Queues  
1: Whites Road South & Bayly Street
















Future Background 2032 AM  
AM Peak Hour



Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Group Flow (vph)	125	332	656	83	352	736
v/c Ratio	0.60	0.33	0.75	0.19	0.49	0.49
Control Delay	57.2	8.5	36.4	7.6	27.0	24.8
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.2	8.5	36.4	7.6	27.0	24.8
Queue Length 50th (m)	25.8	21.1	67.7	0.3	57.9	60.4
Queue Length 95th (m)	39.2	38.2	76.3	5.8	95.1	85.6
Internal Link Dist (m)	352.4		176.0			197.2
Turn Bay Length (m)				30.0	70.0	
Base Capacity (vph)	450	1016	1250	609	718	1502
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.28	0.33	0.52	0.14	0.49	0.49
<b>Intersection Summary</b>						























HCM Signalized Intersection Capacity Analysis  
1: Whites Road South & Bayly Street

Future Background 2032 AM  
AM Peak Hour

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			  
Traffic Volume (vph)	105	279	551	70	384	530
Future Volume (vph)	105	279	551	70	384	530
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt	1.00	0.85	1.00	0.85	1.00	1.00
Flt Protected	0.95	1.00	1.00	1.00	0.95	0.99
Satd. Flow (prot)	1722	1570	3510	1601	1612	3371
Flt Permitted	0.95	1.00	1.00	1.00	0.95	0.99
Satd. Flow (perm)	1722	1570	3510	1601	1612	3371
Peak-hour factor, PHF	0.84	0.84	0.84	0.84	0.84	0.84
Adj. Flow (vph)	125	332	656	83	457	631
RTOR Reduction (vph)	0	41	0	46	0	0
Lane Group Flow (vph)	125	291	656	37	352	736
Heavy Vehicles (%)	6%	4%	4%	2%	3%	3%
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2
Permitted Phases	8	8		5		
Actuated Green, G (s)	13.3	62.3	27.3	27.3	49.0	49.0
Effective Green, g (s)	13.3	62.3	27.3	27.3	49.0	49.0
Actuated g/C Ratio	0.12	0.57	0.25	0.25	0.45	0.45
Clearance Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	208	889	871	397	718	1501
v/s Ratio Prot		0.15	c0.19		c0.22	0.22
v/s Ratio Perm	c0.07	0.04		0.02		
v/c Ratio	0.60	0.33	0.75	0.09	0.49	0.49
Uniform Delay, d1	45.8	12.7	38.2	31.8	21.6	21.6
Progression Factor	1.00	1.00	0.81	0.60	1.00	1.00
Incremental Delay, d2	4.8	0.2	3.5	0.1	2.4	1.1
Delay (s)	50.7	12.9	34.6	19.3	24.0	22.8
Level of Service	D	B	C	B	C	C
Approach Delay (s)	23.2		32.9			23.2
Approach LOS	C		C			C
<b>Intersection Summary</b>						
HCM 2000 Control Delay			26.3		HCM 2000 Level of Service	C
HCM 2000 Volume to Capacity ratio			0.59			
Actuated Cycle Length (s)			110.0		Sum of lost time (s)	20.4
Intersection Capacity Utilization			56.7%		ICU Level of Service	B
Analysis Period (min)			15			
c Critical Lane Group						

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Background 2032 AM  
AM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	168	42	8	7	55	305	17	135	25	189	88	351
Future Volume (vph)	168	42	8	7	55	305	17	135	25	189	88	351
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (m)	20.0		0.0	15.0		15.0	20.0		0.0	20.0		0.0
Storage Lanes	1		0	1		1	1		0	1		1
Taper Length (m)	40.0			10.0			40.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.976				0.850		0.977				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1658	1836	0	1825	1921	1601	1722	1861	0	1755	1762	1601
Flt Permitted	0.713			0.717			0.687			0.633		
Satd. Flow (perm)	1244	1836	0	1377	1921	1601	1245	1861	0	1169	1762	1601
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		10				377		12				433
Link Speed (k/h)		50			50			60				60
Link Distance (m)		78.3			208.1			259.8				200.0
Travel Time (s)		5.6			15.0			15.6				12.0
Peak Hour Factor	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81
Heavy Vehicles (%)	7%	0%	13%	0%	0%	2%	6%	1%	0%	4%	9%	2%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Adj. Flow (vph)	207	52	10	9	68	377	21	167	31	233	109	433
Shared Lane Traffic (%)												
Lane Group Flow (vph)	207	62	0	9	68	377	21	198	0	233	109	433
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			3.7				3.7
Link Offset(m)		0.0			0.0			0.0				0.0
Crosswalk Width(m)		1.6			1.6			1.6				1.6
Two way Left Turn Lane												
Headway Factor	1.02	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	6.1	30.5		6.1	30.5	6.1	6.1	30.5		6.1	30.5	6.1
Trailing Detector (m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	6.1	1.8		6.1	1.8	6.1	6.1	1.8		6.1	1.8	6.1
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		28.7			28.7			28.7				28.7
Detector 2 Size(m)		1.8			1.8			1.8				1.8
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex				Cl+Ex
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0				0.0
Turn Type	Perm	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Background 2032 AM  
AM Peak Hour




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Protected Phases		4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Detector Phase	4	4		8	8	8	2	2		6	6	6
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0	5.0	5.0	5.0		5.0	5.0	5.0
Minimum Split (s)	36.0	36.0		36.0	36.0	36.0	32.0	32.0		32.0	32.0	32.0
Total Split (s)	48.4	48.4		48.4	48.4	48.4	61.6	61.6		61.6	61.6	61.6
Total Split (%)	44.0%	44.0%		44.0%	44.0%	44.0%	56.0%	56.0%		56.0%	56.0%	56.0%
Maximum Green (s)	42.2	42.2		42.2	42.2	42.2	55.3	55.3		55.3	55.3	55.3
Yellow Time (s)	3.3	3.3		3.3	3.3	3.3	4.2	4.2		4.2	4.2	4.2
All-Red Time (s)	2.9	2.9		2.9	2.9	2.9	2.1	2.1		2.1	2.1	2.1
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lead/Lag												
Lead-Lag Optimize?												
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	None		None	None	None	C-Max	C-Max		C-Max	C-Max	C-Max
Walk Time (s)	7.0	7.0		7.0	7.0	7.0	7.0	7.0		7.0	7.0	7.0
Flash Dont Walk (s)	22.0	22.0		22.0	22.0	22.0	18.0	18.0		18.0	18.0	18.0
Pedestrian Calls (#/hr)	0	0		0	0	0	0	0		0	0	0
Act Effct Green (s)	24.0	24.0		24.0	24.0	24.0	73.5	73.5		73.5	73.5	73.5
Actuated g/C Ratio	0.22	0.22		0.22	0.22	0.22	0.67	0.67		0.67	0.67	0.67
v/c Ratio	0.76	0.15		0.03	0.16	0.59	0.03	0.16		0.30	0.09	0.36
Control Delay	57.6	27.8		29.6	33.1	7.1	8.4	7.9		14.0	12.7	6.5
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	57.6	27.8		29.6	33.1	7.1	8.4	7.9		14.0	12.7	6.5
LOS	E	C		C	C	A	A	A		B	B	A
Approach Delay		50.8			11.5			7.9			9.6	
Approach LOS		D			B			A			A	

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 83.6 (76%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green  
 Natural Cycle: 70  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.76  
 Intersection Signal Delay: 16.3  
 Intersection LOS: B  
 Intersection Capacity Utilization 52.4%  
 ICU Level of Service A  
 Analysis Period (min) 15

Splits and Phases: 2: Whites Road South & Oklahoma Drive



Queues  
2: Whites Road South & Oklahoma Drive

Future Background 2032 AM  
AM Peak Hour

























Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	SBL	SBT	SBR
Lane Group Flow (vph)	207	62	9	68	377	21	198	233	109	433
v/c Ratio	0.76	0.15	0.03	0.16	0.59	0.03	0.16	0.30	0.09	0.36
Control Delay	57.6	27.8	29.6	33.1	7.1	8.4	7.9	14.0	12.7	6.5
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.6	27.8	29.6	33.1	7.1	8.4	7.9	14.0	12.7	6.5
Queue Length 50th (m)	41.9	9.1	1.5	11.9	0.0	1.4	13.3	12.1	5.6	0.7
Queue Length 95th (m)	53.1	15.8	4.6	18.7	12.0	4.6	25.0	42.8	23.6	52.9
Internal Link Dist (m)		54.3		184.1			235.8		176.0	
Turn Bay Length (m)	20.0		15.0		15.0	20.0		20.0		
Base Capacity (vph)	477	710	528	736	846	832	1247	781	1177	1213
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.43	0.09	0.02	0.09	0.45	0.03	0.16	0.30	0.09	0.36

Intersection Summary



HCM Signalized Intersection Capacity Analysis  
2: Whites Road South & Oklahoma Drive

Future Background 2032 AM  
AM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	168	42	8	7	55	305	17	135	25	189	88	351
Future Volume (vph)	168	42	8	7	55	305	17	135	25	189	88	351
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lane Util. Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.00	1.00	1.00
Frt	1.00	0.98		1.00	1.00	0.85	1.00	0.98		1.00	1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00	1.00	0.95	1.00		0.95	1.00	1.00
Satd. Flow (prot)	1658	1836		1825	1921	1601	1722	1860		1755	1762	1601
Flt Permitted	0.71	1.00		0.72	1.00	1.00	0.69	1.00		0.63	1.00	1.00
Satd. Flow (perm)	1244	1836		1377	1921	1601	1245	1860		1170	1762	1601
Peak-hour factor, PHF	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81
Adj. Flow (vph)	207	52	10	9	68	377	21	167	31	233	109	433
RTOR Reduction (vph)	0	8	0	0	0	295	0	4	0	0	0	144
Lane Group Flow (vph)	207	54	0	9	68	82	21	194	0	233	109	289
Heavy Vehicles (%)	7%	0%	13%	0%	0%	2%	6%	1%	0%	4%	9%	2%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Turn Type	Perm	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm
Protected Phases		4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Actuated Green, G (s)	24.0	24.0		24.0	24.0	24.0	73.5	73.5		73.5	73.5	73.5
Effective Green, g (s)	24.0	24.0		24.0	24.0	24.0	73.5	73.5		73.5	73.5	73.5
Actuated g/C Ratio	0.22	0.22		0.22	0.22	0.22	0.67	0.67		0.67	0.67	0.67
Clearance Time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Lane Grp Cap (vph)	271	400		300	419	349	831	1242		781	1177	1069
v/s Ratio Prot		0.03			0.04			0.10			0.06	
v/s Ratio Perm	c0.17			0.01		0.05	0.02			c0.20		0.18
v/c Ratio	0.76	0.14		0.03	0.16	0.24	0.03	0.16		0.30	0.09	0.27
Uniform Delay, d1	40.3	34.6		33.8	34.9	35.4	6.2	6.8		7.6	6.5	7.4
Progression Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.42	1.58	5.72
Incremental Delay, d2	12.0	0.2		0.0	0.2	0.3	0.1	0.3		0.9	0.1	0.6
Delay (s)	52.4	34.8		33.9	35.0	35.8	6.2	7.0		11.7	10.3	42.9
Level of Service	D	C		C	D	D	A	A		B	B	D
Approach Delay (s)		48.3			35.6			7.0			28.9	
Approach LOS		D			D			A			C	
<b>Intersection Summary</b>												
HCM 2000 Control Delay			30.9	HCM 2000 Level of Service				C				
HCM 2000 Volume to Capacity ratio			0.41									
Actuated Cycle Length (s)			110.0	Sum of lost time (s)				12.5				
Intersection Capacity Utilization			52.4%	ICU Level of Service				A				
Analysis Period (min)			15									

c Critical Lane Group

Lanes, Volumes, Timings  
3: Granite Court/Oaklahoma Drive

Future Background 2032 AM  
AM Peak Hour




Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		↔	↔		↔	
Traffic Volume (vph)	0	219	423	0	0	0
Future Volume (vph)	0	219	423	0	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00
<b>Fr</b>						
Flt Protected						
Satd. Flow (prot)	0	1883	1883	0	1883	0
Flt Permitted						
Satd. Flow (perm)	0	1883	1883	0	1883	0
Link Speed (k/h)		50	50		48	
Link Distance (m)		466.2	78.3		125.8	
Travel Time (s)		33.6	5.6		9.4	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	0	238	460	0	0	0
Shared Lane Traffic (%)						
Lane Group Flow (vph)	0	238	460	0	0	0
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Left	Left	Right	Left	Right
Median Width(m)		3.7	3.7		3.7	
Link Offset(m)		0.0	0.0		0.0	
Crosswalk Width(m)		1.6	1.6		1.6	
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24			14	24	14
Sign Control		Free	Free		Stop	
<b>Intersection Summary</b>						
Area Type:	Other					
Control Type:	Unsignalized					
Intersection Capacity Utilization	25.6%			ICU Level of Service A		
Analysis Period (min)	15					

# HCM Unsignalized Intersection Capacity Analysis

## 3: Granite Court/Oaklahoma Drive

Future Background 2032 AM  
AM Peak Hour



Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		↔	↔		↔	
Traffic Volume (veh/h)	0	219	423	0	0	0
Future Volume (Veh/h)	0	219	423	0	0	0
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	238	460	0	0	0
Pedestrians						
Lane Width (m)						
Walking Speed (m/s)						
Percent Blockage						
Right turn flare (veh)						
Median type		None	None			
Median storage (veh)						
Upstream signal (m)			78			
pX, platoon unblocked	0.98				0.98	0.98
vC, conflicting volume	460				698	460
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	441				684	441
tC, single (s)	4.1				6.4	6.2
tC, 2 stage (s)						
tF (s)	2.2				3.5	3.3
p0 queue free %	100				100	100
cM capacity (veh/h)	1099				407	605
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total	238	460	0			
Volume Left	0	0	0			
Volume Right	0	0	0			
cSH	1099	1700	1700			
Volume to Capacity	0.00	0.27	0.00			
Queue Length 95th (m)	0.0	0.0	0.0			
Control Delay (s)	0.0	0.0	0.0			
Lane LOS			A			
Approach Delay (s)	0.0	0.0	0.0			
Approach LOS			A			
Intersection Summary						
Average Delay			0.0			
Intersection Capacity Utilization			25.6%		ICU Level of Service	A
Analysis Period (min)			15			

---













**Network Totals**

---

Number of Intersections	3
Total Delay (hr)	21
Stops (#)	1838
Average Speed (km/hr)	24
Total Travel Time (hr)	36
Distance Traveled (km)	871
Fuel Consumed (l)	192
Fuel Economy (km/l)	4.5
Unserviced Vehicles (#)	0
Vehicles in dilemma zone (#)	70
Performance Index	25.9

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Future Background 2032 PM  
PM Peak Hour

						
Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Volume (vph)	139	338	554	189	735	511
Future Volume (vph)	139	338	554	189	735	511
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Storage Length (m)	0.0	0.0		30.0	70.0	
Storage Lanes	1	1		1	1	
Taper Length (m)	2.5				30.0	
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt		0.850		0.850		
Flt Protected	0.950				0.950	0.981
Satd. Flow (prot)	1789	1617	3544	1585	1628	3363
Flt Permitted	0.950				0.950	0.981
Satd. Flow (perm)	1789	1617	3544	1585	1628	3363
Right Turn on Red		Yes		Yes		
Satd. Flow (RTOR)		110		158		
Link Speed (k/h)	60		60			60
Link Distance (m)	376.4		200.0			221.2
Travel Time (s)	22.6		12.0			13.3
Peak Hour Factor	0.95	0.95	0.95	0.95	0.95	0.95
Heavy Vehicles (%)	2%	1%	3%	3%	2%	2%
Adj. Flow (vph)	146	356	583	199	774	538
Shared Lane Traffic (%)					45%	
Lane Group Flow (vph)	146	356	583	199	426	886
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Right	Left	Right	Left	Left
Median Width(m)	3.7		3.7			3.7
Link Offset(m)	0.0		0.0			0.0
Crosswalk Width(m)	1.6		1.6			1.6
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24	14		14	24	
Number of Detectors	1	1	2	1	1	2
Detector Template	Left	Right	Thru	Right	Left	Thru
Leading Detector (m)	6.1	6.1	30.5	6.1	6.1	30.5
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)	6.1	6.1	1.8	6.1	6.1	1.8
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel						
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)			28.7			28.7
Detector 2 Size(m)			1.8			1.8
Detector 2 Type			Cl+Ex			Cl+Ex
Detector 2 Channel						
Detector 2 Extend (s)			0.0			0.0
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Future Background 2032 PM  
PM Peak Hour




Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Permitted Phases	8	8		5		
Detector Phase	8	2	5	5	2	2
Switch Phase						
Minimum Initial (s)	8.0	20.0	20.0	20.0	20.0	20.0
Minimum Split (s)	32.0	27.0	39.0	39.0	27.0	27.0
Total Split (s)	35.2	30.8	44.0	44.0	30.8	30.8
Total Split (%)	32.0%	28.0%	40.0%	40.0%	28.0%	28.0%
Maximum Green (s)	28.8	23.8	37.0	37.0	23.8	23.8
Yellow Time (s)	4.2	4.4	4.4	4.4	4.4	4.4
All-Red Time (s)	2.2	2.6	2.6	2.6	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lead/Lag						
Lead-Lag Optimize?						
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Recall Mode	None	C-Max	None	None	C-Max	C-Max
Walk Time (s)	7.0	5.0	7.0	7.0	5.0	5.0
Flash Dont Walk (s)	18.0	5.0	25.0	25.0	5.0	5.0
Pedestrian Calls (#/hr)	0	0	0	0	0	0
Act Effect Green (s)	14.3	70.5	25.5	25.5	49.8	49.8
Actuated g/C Ratio	0.13	0.64	0.23	0.23	0.45	0.45
v/c Ratio	0.63	0.33	0.71	0.41	0.58	0.58
Control Delay	56.8	7.5	58.9	27.5	28.6	26.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	56.8	7.5	58.9	27.5	28.6	26.0
LOS	E	A	E	C	C	C
Approach Delay	21.9		50.9			26.9
Approach LOS	C		D			C

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 33 (30%), Referenced to phase 2:SBTL and 6:, Start of Green  
 Natural Cycle: 100  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.71  
 Intersection Signal Delay: 33.1  
 Intersection LOS: C  
 Intersection Capacity Utilization 65.0%  
 ICU Level of Service C  
 Analysis Period (min) 15

Splits and Phases: 1: Whites Road South & Bayly Street



Queues

1: Whites Road South & Bayly Street


















Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Group Flow (vph)	146	356	583	199	426	886
v/c Ratio	0.63	0.33	0.71	0.41	0.58	0.58
Control Delay	56.8	7.5	58.9	27.5	28.6	26.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	56.8	7.5	58.9	27.5	28.6	26.0
Queue Length 50th (m)	30.1	20.3	67.3	17.6	72.1	75.2
Queue Length 95th (m)	47.9	42.5	m83.5	m31.1	130.1	116.7
Internal Link Dist (m)	352.4		176.0			197.2
Turn Bay Length (m)				30.0	70.0	
Base Capacity (vph)	468	1076	1192	637	737	1523
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.31	0.33	0.49	0.31	0.58	0.58

Intersection Summary

m Volume for 95th percentile queue is metered by upstream signal.

HCM Signalized Intersection Capacity Analysis  
 1: Whites Road South & Bayly Street























Future Background 2032 PM  
 PM Peak Hour

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			  
Traffic Volume (vph)	139	338	554	189	735	511
Future Volume (vph)	139	338	554	189	735	511
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt	1.00	0.85	1.00	0.85	1.00	1.00
Flt Protected	0.95	1.00	1.00	1.00	0.95	0.98
Satd. Flow (prot)	1789	1617	3544	1585	1628	3362
Flt Permitted	0.95	1.00	1.00	1.00	0.95	0.98
Satd. Flow (perm)	1789	1617	3544	1585	1628	3362
Peak-hour factor, PHF	0.95	0.95	0.95	0.95	0.95	0.95
Adj. Flow (vph)	146	356	583	199	774	538
RTOR Reduction (vph)	0	46	0	121	0	0
Lane Group Flow (vph)	146	310	583	78	426	886
Heavy Vehicles (%)	2%	1%	3%	3%	2%	2%
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2
Permitted Phases	8	8		5		
Actuated Green, G (s)	14.3	64.1	25.5	25.5	49.8	49.8
Effective Green, g (s)	14.3	64.1	25.5	25.5	49.8	49.8
Actuated g/C Ratio	0.13	0.58	0.23	0.23	0.45	0.45
Clearance Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	232	942	821	367	737	1522
v/s Ratio Prot		0.15	c0.16		0.26	c0.26
v/s Ratio Perm	c0.08	0.04		0.05		
v/c Ratio	0.63	0.33	0.71	0.21	0.58	0.58
Uniform Delay, d1	45.3	11.8	38.9	34.1	22.3	22.4
Progression Factor	1.00	1.00	1.42	2.98	1.00	1.00
Incremental Delay, d2	5.3	0.2	2.4	0.2	3.3	1.6
Delay (s)	50.6	12.1	57.7	102.1	25.6	24.0
Level of Service	D	B	E	F	C	C
Approach Delay (s)	23.3		69.0			24.5
Approach LOS	C		E			C
<b>Intersection Summary</b>						
HCM 2000 Control Delay			37.7		HCM 2000 Level of Service	D
HCM 2000 Volume to Capacity ratio			0.63			
Actuated Cycle Length (s)			110.0		Sum of lost time (s)	20.4
Intersection Capacity Utilization			65.0%		ICU Level of Service	C
Analysis Period (min)			15			
c Critical Lane Group						




Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Background 2032 PM  
PM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	412	72	11	10	58	198	16	108	13	267	193	188
Future Volume (vph)	412	72	11	10	58	198	16	108	13	267	193	188
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (m)	20.0		0.0	15.0		15.0	20.0		0.0	20.0		0.0
Storage Lanes	1		0	1		1	1		0	1		1
Taper Length (m)	40.0			10.0			40.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.980				0.850		0.984				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1706	1883	0	1659	1921	1601	1825	1857	0	1807	1902	1570
Flt Permitted	0.549			0.699			0.624			0.674		
Satd. Flow (perm)	986	1883	0	1221	1921	1601	1199	1857	0	1282	1902	1570
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		11				213		6				202
Link Speed (k/h)		50			50			60				60
Link Distance (m)		78.3			208.1			259.8				200.0
Travel Time (s)		5.6			15.0			15.6				12.0
Peak Hour Factor	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93
Heavy Vehicles (%)	4%	0%	0%	10%	0%	2%	0%	2%	0%	1%	1%	4%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Adj. Flow (vph)	443	77	12	11	62	213	17	116	14	287	208	202
Shared Lane Traffic (%)												
Lane Group Flow (vph)	443	89	0	11	62	213	17	130	0	287	208	202
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			3.7				3.7
Link Offset(m)		0.0			0.0			0.0				0.0
Crosswalk Width(m)		1.6			1.6			1.6				1.6
Two way Left Turn Lane												
Headway Factor	1.02	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	6.1	30.5		6.1	30.5	6.1	6.1	30.5		6.1	30.5	6.1
Trailing Detector (m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	6.1	1.8		6.1	1.8	6.1	6.1	1.8		6.1	1.8	6.1
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		28.7			28.7			28.7				28.7
Detector 2 Size(m)		1.8			1.8			1.8				1.8
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex				Cl+Ex
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0				0.0
Turn Type	pm+pt	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Background 2032 PM  
PM Peak Hour




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Protected Phases	7	4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Detector Phase	7	4		8	8	8	2	2		6	6	6
Switch Phase												
Minimum Initial (s)	5.0	8.0		8.0	8.0	8.0	20.0	20.0		20.0	20.0	20.0
Minimum Split (s)	9.5	36.0		36.0	36.0	36.0	32.0	32.0		32.0	32.0	32.0
Total Split (s)	28.4	64.4		36.0	36.0	36.0	45.6	45.6		45.6	45.6	45.6
Total Split (%)	25.8%	58.5%		32.7%	32.7%	32.7%	41.5%	41.5%		41.5%	41.5%	41.5%
Maximum Green (s)	25.4	58.2		29.8	29.8	29.8	39.3	39.3		39.3	39.3	39.3
Yellow Time (s)	3.0	3.3		3.3	3.3	3.3	4.2	4.2		4.2	4.2	4.2
All-Red Time (s)	0.0	2.9		2.9	2.9	2.9	2.1	2.1		2.1	2.1	2.1
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lead/Lag	Lead			Lag	Lag	Lag						
Lead-Lag Optimize?	Yes			Yes	Yes	Yes						
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	None		None	None	None	C-Max	C-Max		C-Max	C-Max	C-Max
Walk Time (s)		7.0		7.0	7.0	7.0	7.0	7.0		7.0	7.0	7.0
Flash Dont Walk (s)		22.0		22.0	22.0	22.0	18.0	18.0		18.0	18.0	18.0
Pedestrian Calls (#/hr)		0		0	0	0	0	0		0	0	0
Act Effct Green (s)	41.4	38.2		9.8	9.8	9.8	59.3	59.3		59.3	59.3	59.3
Actuated g/C Ratio	0.38	0.35		0.09	0.09	0.09	0.54	0.54		0.54	0.54	0.54
v/c Ratio	0.82	0.13		0.10	0.36	0.63	0.03	0.13		0.42	0.20	0.22
Control Delay	43.1	21.5		46.6	52.5	15.3	13.0	12.9		7.6	4.9	2.1
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	43.1	21.5		46.6	52.5	15.3	13.0	12.9		7.6	4.9	2.1
LOS	D	C		D	D	B	B	B		A	A	A
Approach Delay		39.5			24.6			12.9			5.2	
Approach LOS		D			C			B			A	

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 40.7 (37%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green  
 Natural Cycle: 80  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.82  
 Intersection Signal Delay: 20.2  
 Intersection LOS: C  
 Intersection Capacity Utilization 78.5%  
 ICU Level of Service D  
 Analysis Period (min) 15

Splits and Phases: 2: Whites Road South & Oklahoma Drive



Queues  
2: Whites Road South & Oklahoma Drive

Future Background 2032 PM  
PM Peak Hour



Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	SBL	SBT	SBR
Lane Group Flow (vph)	443	89	11	62	213	17	130	287	208	202
v/c Ratio	0.82	0.13	0.10	0.36	0.63	0.03	0.13	0.42	0.20	0.22
Control Delay	43.1	21.5	46.6	52.5	15.3	13.0	12.9	7.6	4.9	2.1
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	43.1	21.5	46.6	52.5	15.3	13.0	12.9	7.6	4.9	2.1
Queue Length 50th (m)	80.2	11.5	2.2	12.9	0.0	1.6	12.3	17.5	10.6	2.2
Queue Length 95th (m)	#109.0	21.1	7.5	24.8	20.9	5.4	23.9	20.3	15.5	5.7
Internal Link Dist (m)		54.3		184.1			235.8		176.0	
Turn Bay Length (m)	20.0		15.0		15.0	20.0		20.0		
Base Capacity (vph)	537	1001	330	520	589	646	1004	691	1025	939
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.82	0.09	0.03	0.12	0.36	0.03	0.13	0.42	0.20	0.22























Intersection Summary

# 95th percentile volume exceeds capacity, queue may be longer.  
Queue shown is maximum after two cycles.

# HCM Signalized Intersection Capacity Analysis

## 2: Whites Road South & Oklahoma Drive

Future Background 2032 PM  
PM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	412	72	11	10	58	198	16	108	13	267	193	188
Future Volume (vph)	412	72	11	10	58	198	16	108	13	267	193	188
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lane Util. Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.00	1.00	1.00
Frt	1.00	0.98		1.00	1.00	0.85	1.00	0.98		1.00	1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00	1.00	0.95	1.00		0.95	1.00	1.00
Satd. Flow (prot)	1706	1882		1659	1921	1601	1825	1857		1807	1902	1570
Flt Permitted	0.55	1.00		0.70	1.00	1.00	0.62	1.00		0.67	1.00	1.00
Satd. Flow (perm)	985	1882		1221	1921	1601	1199	1857		1282	1902	1570
Peak-hour factor, PHF	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93
Adj. Flow (vph)	443	77	12	11	62	213	17	116	14	287	208	202
RTOR Reduction (vph)	0	7	0	0	0	194	0	3	0	0	0	93
Lane Group Flow (vph)	443	82	0	11	62	19	17	127	0	287	208	109
Heavy Vehicles (%)	4%	0%	0%	10%	0%	2%	0%	2%	0%	1%	1%	4%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Turn Type	pm+pt	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm
Protected Phases	7	4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Actuated Green, G (s)	38.2	38.2		9.8	9.8	9.8	59.3	59.3		59.3	59.3	59.3
Effective Green, g (s)	38.2	38.2		9.8	9.8	9.8	59.3	59.3		59.3	59.3	59.3
Actuated g/C Ratio	0.35	0.35		0.09	0.09	0.09	0.54	0.54		0.54	0.54	0.54
Clearance Time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Lane Grp Cap (vph)	508	653		108	171	142	646	1001		691	1025	846
v/s Ratio Prot	c0.20	0.04			0.03			0.07			0.11	
v/s Ratio Perm	c0.10			0.01		0.01	0.01			c0.22		0.07
v/c Ratio	0.87	0.13		0.10	0.36	0.13	0.03	0.13		0.42	0.20	0.13
Uniform Delay, d1	31.7	24.5		46.1	47.2	46.2	11.9	12.5		15.1	13.1	12.6
Progression Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		0.37	0.33	0.79
Incremental Delay, d2	15.1	0.1		0.4	1.3	0.4	0.1	0.3		1.6	0.4	0.3
Delay (s)	46.9	24.6		46.5	48.5	46.6	11.9	12.8		7.2	4.7	10.2
Level of Service	D	C		D	D	D	B	B		A	A	B
Approach Delay (s)		43.1			47.0			12.7			7.3	
Approach LOS		D			D			B			A	
<b>Intersection Summary</b>												
HCM 2000 Control Delay			26.1	HCM 2000 Level of Service				C				
HCM 2000 Volume to Capacity ratio			0.61									
Actuated Cycle Length (s)			110.0	Sum of lost time (s)				15.5				
Intersection Capacity Utilization			78.5%	ICU Level of Service				D				
Analysis Period (min)			15									

c Critical Lane Group

Lanes, Volumes, Timings  
3: Granite Court/Oaklahoma Drive

Future Background 2032 PM  
PM Peak Hour




Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (vph)	0	497	263	0	0	0
Future Volume (vph)	0	497	263	0	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00
<b>Fr</b>						
Flt Protected						
Satd. Flow (prot)	0	1883	1883	0	1883	0
Flt Permitted						
Satd. Flow (perm)	0	1883	1883	0	1883	0
Link Speed (k/h)		50	50		48	
Link Distance (m)		466.2	78.3		125.8	
Travel Time (s)		33.6	5.6		9.4	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	0	540	286	0	0	0
Shared Lane Traffic (%)						
Lane Group Flow (vph)	0	540	286	0	0	0
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Left	Left	Right	Left	Right
Median Width(m)		3.7	3.7		3.7	
Link Offset(m)		0.0	0.0		0.0	
Crosswalk Width(m)		1.6	1.6		1.6	
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24			14	24	14
Sign Control		Free	Free		Stop	
<b>Intersection Summary</b>						
Area Type:	Other					
Control Type:	Unsignalized					
Intersection Capacity Utilization	29.5%			ICU Level of Service A		
Analysis Period (min)	15					

# HCM Unsignalized Intersection Capacity Analysis

## 3: Granite Court/Oaklahoma Drive

Future Background 2032 PM  
PM Peak Hour



Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (veh/h)	0	497	263	0	0	0
Future Volume (Veh/h)	0	497	263	0	0	0
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	540	286	0	0	0
<b>Pedestrians</b>						
Lane Width (m)						
Walking Speed (m/s)						
Percent Blockage						
Right turn flare (veh)						
Median type		None	None			
Median storage (veh)						
Upstream signal (m)	78					
pX, platoon unblocked	0.97			0.97	0.97	
vC, conflicting volume	286			826	286	
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	255			809	255	
tC, single (s)	4.1			6.4	6.2	
tC, 2 stage (s)						
tF (s)	2.2			3.5	3.3	
p0 queue free %	100			100	100	
cM capacity (veh/h)	1277			341	764	
<b>Direction, Lane #</b>	<b>EB 1</b>	<b>WB 1</b>	<b>SB 1</b>			
Volume Total	540	286	0			
Volume Left	0	0	0			
Volume Right	0	0	0			
cSH	1277	1700	1700			
Volume to Capacity	0.00	0.17	0.00			
Queue Length 95th (m)	0.0	0.0	0.0			
Control Delay (s)	0.0	0.0	0.0			
Lane LOS			A			
Approach Delay (s)	0.0	0.0	0.0			
Approach LOS			A			
<b>Intersection Summary</b>						
Average Delay			0.0			
Intersection Capacity Utilization			29.5%	ICU Level of Service	A	
Analysis Period (min)			15			

---















**Network Totals**

---

Number of Intersections	3
Total Delay (hr)	31
Stops (#)	2537
Average Speed (km/hr)	22
Total Travel Time (hr)	51
Distance Traveled (km)	1116
Fuel Consumed (l)	264
Fuel Economy (km/l)	4.2
Unserviced Vehicles (#)	0
Vehicles in dilemma zone (#)	50
Performance Index	38.4

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Future Background 2037 AM  
AM Peak Hour

						
Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			 
Traffic Volume (vph)	108	286	565	72	393	543
Future Volume (vph)	108	286	565	72	393	543
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Storage Length (m)	0.0	0.0		30.0	70.0	
Storage Lanes	1	1		1	1	
Taper Length (m)	2.5				30.0	
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt		0.850		0.850		
Flt Protected	0.950				0.950	0.993
Satd. Flow (prot)	1722	1570	3510	1601	1612	3371
Flt Permitted	0.950				0.950	0.993
Satd. Flow (perm)	1722	1570	3510	1601	1612	3371
Right Turn on Red		Yes		Yes		
Satd. Flow (RTOR)		89		61		
Link Speed (k/h)	60		60			60
Link Distance (m)	376.4		200.0			221.2
Travel Time (s)	22.6		12.0			13.3
Peak Hour Factor	0.84	0.84	0.84	0.84	0.84	0.84
Heavy Vehicles (%)	6%	4%	4%	2%	3%	3%
Adj. Flow (vph)	129	340	673	86	468	646
Shared Lane Traffic (%)					23%	
Lane Group Flow (vph)	129	340	673	86	360	754
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Right	Left	Right	Left	Left
Median Width(m)	3.7		3.7			3.7
Link Offset(m)	0.0		0.0			0.0
Crosswalk Width(m)	1.6		1.6			1.6
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24	14		14	24	
Number of Detectors	1	1	2	1	1	2
Detector Template	Left	Right	Thru	Right	Left	Thru
Leading Detector (m)	6.1	6.1	30.5	6.1	6.1	30.5
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)	6.1	6.1	1.8	6.1	6.1	1.8
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel						
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)			28.7			28.7
Detector 2 Size(m)			1.8			1.8
Detector 2 Type			Cl+Ex			Cl+Ex
Detector 2 Channel						
Detector 2 Extend (s)			0.0			0.0
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2



Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street


Future Background 2037 AM  
AM Peak Hour

Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Permitted Phases	8	8		5		
Detector Phase	8	2	5	5	2	2
Switch Phase						
Minimum Initial (s)	5.0	20.0	20.0	20.0	20.0	20.0
Minimum Split (s)	32.0	27.0	39.0	39.0	27.0	27.0
Total Split (s)	35.2	28.6	46.2	46.2	28.6	28.6
Total Split (%)	32.0%	26.0%	42.0%	42.0%	26.0%	26.0%
Maximum Green (s)	28.8	21.6	39.2	39.2	21.6	21.6
Yellow Time (s)	4.2	4.4	4.4	4.4	4.4	4.4
All-Red Time (s)	2.2	2.6	2.6	2.6	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lead/Lag						
Lead-Lag Optimize?						
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Recall Mode	None	C-Max	None	None	C-Max	C-Max
Walk Time (s)	7.0	5.0	7.0	7.0	5.0	5.0
Flash Dont Walk (s)	18.0	5.0	25.0	25.0	5.0	5.0
Pedestrian Calls (#/hr)	0	0	0	0	0	0
Act Effct Green (s)	13.6	68.0	28.0	28.0	48.0	48.0
Actuated g/C Ratio	0.12	0.62	0.25	0.25	0.44	0.44
v/c Ratio	0.61	0.34	0.75	0.19	0.51	0.51
Control Delay	57.3	9.2	35.5	7.5	28.4	26.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.3	9.2	35.5	7.5	28.4	26.0
LOS	E	A	D	A	C	C
Approach Delay	22.4		32.4			26.8
Approach LOS	C		C			C

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 24.2 (22%), Referenced to phase 2:SBTL and 6:, Start of Green  
 Natural Cycle: 100  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.75  
 Intersection Signal Delay: 27.7  
 Intersection LOS: C  
 Intersection Capacity Utilization 57.3%  
 ICU Level of Service B  
 Analysis Period (min) 15

Splits and Phases: 1: Whites Road South & Bayly Street



Queues  
1: Whites Road South & Bayly Street
















Future Background 2037 AM  
AM Peak Hour



Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Group Flow (vph)	129	340	673	86	360	754
v/c Ratio	0.61	0.34	0.75	0.19	0.51	0.51
Control Delay	57.3	9.2	35.5	7.5	28.4	26.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.3	9.2	35.5	7.5	28.4	26.0
Queue Length 50th (m)	26.6	23.1	69.6	0.5	60.5	63.4
Queue Length 95th (m)	40.2	41.7	76.6	5.8	100.2	90.3
Internal Link Dist (m)	352.4		176.0			197.2
Turn Bay Length (m)				30.0	70.0	
Base Capacity (vph)	450	1004	1250	609	703	1471
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.29	0.34	0.54	0.14	0.51	0.51
<b>Intersection Summary</b>						























HCM Signalized Intersection Capacity Analysis  
 1: Whites Road South & Bayly Street

Future Background 2037 AM  
 AM Peak Hour

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			  
Traffic Volume (vph)	108	286	565	72	393	543
Future Volume (vph)	108	286	565	72	393	543
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt	1.00	0.85	1.00	0.85	1.00	1.00
Flt Protected	0.95	1.00	1.00	1.00	0.95	0.99
Satd. Flow (prot)	1722	1570	3510	1601	1612	3370
Flt Permitted	0.95	1.00	1.00	1.00	0.95	0.99
Satd. Flow (perm)	1722	1570	3510	1601	1612	3370
Peak-hour factor, PHF	0.84	0.84	0.84	0.84	0.84	0.84
Adj. Flow (vph)	129	340	673	86	468	646
RTOR Reduction (vph)	0	39	0	45	0	0
Lane Group Flow (vph)	129	301	673	41	360	754
Heavy Vehicles (%)	6%	4%	4%	2%	3%	3%
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2
Permitted Phases	8	8		5		
Actuated Green, G (s)	13.6	61.6	28.0	28.0	48.0	48.0
Effective Green, g (s)	13.6	61.6	28.0	28.0	48.0	48.0
Actuated g/C Ratio	0.12	0.56	0.25	0.25	0.44	0.44
Clearance Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	212	879	893	407	703	1470
v/s Ratio Prot		0.15	c0.19		0.22	c0.22
v/s Ratio Perm	c0.07	0.04		0.03		
v/c Ratio	0.61	0.34	0.75	0.10	0.51	0.51
Uniform Delay, d1	45.7	13.2	37.8	31.4	22.5	22.5
Progression Factor	1.00	1.00	0.81	0.59	1.00	1.00
Incremental Delay, d2	4.9	0.2	3.4	0.1	2.7	1.3
Delay (s)	50.6	13.4	34.0	18.6	25.2	23.8
Level of Service	D	B	C	B	C	C
Approach Delay (s)	23.6		32.2			24.2
Approach LOS	C		C			C
<b>Intersection Summary</b>						
HCM 2000 Control Delay			26.7		HCM 2000 Level of Service	C
HCM 2000 Volume to Capacity ratio			0.60			
Actuated Cycle Length (s)			110.0		Sum of lost time (s)	20.4
Intersection Capacity Utilization			57.3%		ICU Level of Service	B
Analysis Period (min)			15			
c	Critical Lane Group					

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Background 2037 AM  
AM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	172	43	8	7	56	312	17	138	26	194	90	359
Future Volume (vph)	172	43	8	7	56	312	17	138	26	194	90	359
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (m)	20.0		0.0	15.0		15.0	20.0		0.0	20.0		0.0
Storage Lanes	1		0	1		1	1		0	1		1
Taper Length (m)	40.0			10.0			40.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.976				0.850		0.976				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1658	1837	0	1825	1921	1601	1722	1859	0	1755	1762	1601
Flt Permitted	0.712			0.716			0.685			0.631		
Satd. Flow (perm)	1243	1837	0	1376	1921	1601	1241	1859	0	1166	1762	1601
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		10				385		12				443
Link Speed (k/h)		50			50			60				60
Link Distance (m)		78.3			208.1			259.8				200.0
Travel Time (s)		5.6			15.0			15.6				12.0
Peak Hour Factor	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81
Heavy Vehicles (%)	7%	0%	13%	0%	0%	2%	6%	1%	0%	4%	9%	2%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Adj. Flow (vph)	212	53	10	9	69	385	21	170	32	240	111	443
Shared Lane Traffic (%)												
Lane Group Flow (vph)	212	63	0	9	69	385	21	202	0	240	111	443
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			3.7				3.7
Link Offset(m)		0.0			0.0			0.0				0.0
Crosswalk Width(m)		1.6			1.6			1.6				1.6
Two way Left Turn Lane												
Headway Factor	1.02	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	6.1	30.5		6.1	30.5	6.1	6.1	30.5		6.1	30.5	6.1
Trailing Detector (m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	6.1	1.8		6.1	1.8	6.1	6.1	1.8		6.1	1.8	6.1
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		28.7			28.7			28.7				28.7
Detector 2 Size(m)		1.8			1.8			1.8				1.8
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex				Cl+Ex
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0				0.0
Turn Type	Perm	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Background 2037 AM  
AM Peak Hour




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Protected Phases		4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Detector Phase	4	4		8	8	8	2	2		6	6	6
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0	5.0	5.0	5.0		5.0	5.0	5.0
Minimum Split (s)	36.0	36.0		36.0	36.0	36.0	32.0	32.0		32.0	32.0	32.0
Total Split (s)	48.4	48.4		48.4	48.4	48.4	61.6	61.6		61.6	61.6	61.6
Total Split (%)	44.0%	44.0%		44.0%	44.0%	44.0%	56.0%	56.0%		56.0%	56.0%	56.0%
Maximum Green (s)	42.2	42.2		42.2	42.2	42.2	55.3	55.3		55.3	55.3	55.3
Yellow Time (s)	3.3	3.3		3.3	3.3	3.3	4.2	4.2		4.2	4.2	4.2
All-Red Time (s)	2.9	2.9		2.9	2.9	2.9	2.1	2.1		2.1	2.1	2.1
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lead/Lag												
Lead-Lag Optimize?												
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	None		None	None	None	C-Max	C-Max		C-Max	C-Max	C-Max
Walk Time (s)	7.0	7.0		7.0	7.0	7.0	7.0	7.0		7.0	7.0	7.0
Flash Dont Walk (s)	22.0	22.0		22.0	22.0	22.0	18.0	18.0		18.0	18.0	18.0
Pedestrian Calls (#/hr)	0	0		0	0	0	0	0		0	0	0
Act Effct Green (s)	24.4	24.4		24.4	24.4	24.4	73.1	73.1		73.1	73.1	73.1
Actuated g/C Ratio	0.22	0.22		0.22	0.22	0.22	0.66	0.66		0.66	0.66	0.66
v/c Ratio	0.77	0.15		0.03	0.16	0.59	0.03	0.16		0.31	0.09	0.37
Control Delay	57.4	27.5		29.1	32.7	7.0	8.6	8.1		15.4	13.8	7.3
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	57.4	27.5		29.1	32.7	7.0	8.6	8.1		15.4	13.8	7.3
LOS	E	C		C	C	A	A	A		B	B	A
Approach Delay		50.5			11.3			8.1			10.6	
Approach LOS		D			B			A			B	

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 83.6 (76%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green  
 Natural Cycle: 70  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.77  
 Intersection Signal Delay: 16.7  
 Intersection Capacity Utilization 53.3%  
 Analysis Period (min) 15  
 Intersection LOS: B  
 ICU Level of Service A

Splits and Phases: 2: Whites Road South & Oklahoma Drive



Queues  
2: Whites Road South & Oklahoma Drive

Future Background 2037 AM  
AM Peak Hour

























Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	SBL	SBT	SBR
Lane Group Flow (vph)	212	63	9	69	385	21	202	240	111	443
v/c Ratio	0.77	0.15	0.03	0.16	0.59	0.03	0.16	0.31	0.09	0.37
Control Delay	57.4	27.5	29.1	32.7	7.0	8.6	8.1	15.4	13.8	7.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.4	27.5	29.1	32.7	7.0	8.6	8.1	15.4	13.8	7.3
Queue Length 50th (m)	42.9	9.2	1.5	12.0	0.0	1.4	13.9	12.4	5.8	0.7
Queue Length 95th (m)	54.2	15.9	4.5	18.8	12.0	4.6	25.9	47.5	25.7	56.7
Internal Link Dist (m)		54.3		184.1			235.8		176.0	
Turn Bay Length (m)	20.0		15.0		15.0	20.0		20.0		
Base Capacity (vph)	476	710	527	736	851	824	1238	774	1170	1212
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.45	0.09	0.02	0.09	0.45	0.03	0.16	0.31	0.09	0.37

Intersection Summary

# HCM Signalized Intersection Capacity Analysis

## 2: Whites Road South & Oklahoma Drive

Future Background 2037 AM  
AM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	172	43	8	7	56	312	17	138	26	194	90	359
Future Volume (vph)	172	43	8	7	56	312	17	138	26	194	90	359
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lane Util. Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.00	1.00	1.00
Frt	1.00	0.98		1.00	1.00	0.85	1.00	0.98		1.00	1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00	1.00	0.95	1.00		0.95	1.00	1.00
Satd. Flow (prot)	1658	1837		1825	1921	1601	1722	1860		1755	1762	1601
Flt Permitted	0.71	1.00		0.72	1.00	1.00	0.69	1.00		0.63	1.00	1.00
Satd. Flow (perm)	1243	1837		1375	1921	1601	1242	1860		1166	1762	1601
Peak-hour factor, PHF	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81
Adj. Flow (vph)	212	53	10	9	69	385	21	170	32	240	111	443
RTOR Reduction (vph)	0	8	0	0	0	300	0	4	0	0	0	149
Lane Group Flow (vph)	212	55	0	9	69	85	21	198	0	240	111	294
Heavy Vehicles (%)	7%	0%	13%	0%	0%	2%	6%	1%	0%	4%	9%	2%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Turn Type	Perm	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm
Protected Phases		4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Actuated Green, G (s)	24.4	24.4		24.4	24.4	24.4	73.1	73.1		73.1	73.1	73.1
Effective Green, g (s)	24.4	24.4		24.4	24.4	24.4	73.1	73.1		73.1	73.1	73.1
Actuated g/C Ratio	0.22	0.22		0.22	0.22	0.22	0.66	0.66		0.66	0.66	0.66
Clearance Time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Lane Grp Cap (vph)	275	407		305	426	355	825	1236		774	1170	1063
v/s Ratio Prot		0.03			0.04			0.11			0.06	
v/s Ratio Perm	c0.17			0.01		0.05	0.02			c0.21		0.18
v/c Ratio	0.77	0.14		0.03	0.16	0.24	0.03	0.16		0.31	0.09	0.28
Uniform Delay, d1	40.2	34.3		33.5	34.5	35.2	6.3	6.9		7.8	6.6	7.6
Progression Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.52	1.68	6.42
Incremental Delay, d2	12.5	0.2		0.0	0.2	0.4	0.1	0.3		0.9	0.1	0.6
Delay (s)	52.7	34.5		33.6	34.7	35.5	6.4	7.2		12.8	11.2	49.2
Level of Service	D	C		C	C	D	A	A		B	B	D
Approach Delay (s)		48.5			35.4			7.1			32.9	
Approach LOS		D			D			A			C	
<b>Intersection Summary</b>												
HCM 2000 Control Delay			32.7				HCM 2000 Level of Service				C	
HCM 2000 Volume to Capacity ratio			0.42									
Actuated Cycle Length (s)			110.0				Sum of lost time (s)			12.5		
Intersection Capacity Utilization			53.3%				ICU Level of Service			A		
Analysis Period (min)			15									

c Critical Lane Group

Lanes, Volumes, Timings  
3: Granite Court/Oaklahoma Drive

Future Background 2037 AM  
AM Peak Hour




Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (vph)	0	225	434	0	0	0
Future Volume (vph)	0	225	434	0	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00
<b>Fr</b>						
Flt Protected						
Satd. Flow (prot)	0	1883	1883	0	1883	0
Flt Permitted						
Satd. Flow (perm)	0	1883	1883	0	1883	0
Link Speed (k/h)		50	50		48	
Link Distance (m)		466.2	78.3		125.8	
Travel Time (s)		33.6	5.6		9.4	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	0	245	472	0	0	0
Shared Lane Traffic (%)						
Lane Group Flow (vph)	0	245	472	0	0	0
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Left	Left	Right	Left	Right
Median Width(m)		3.7	3.7		3.7	
Link Offset(m)		0.0	0.0		0.0	
Crosswalk Width(m)		1.6	1.6		1.6	
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24			14	24	14
Sign Control		Free	Free		Stop	
<b>Intersection Summary</b>						
Area Type:	Other					
Control Type:	Unsignalized					
Intersection Capacity Utilization	26.2%			ICU Level of Service A		
Analysis Period (min)	15					



# HCM Unsignalized Intersection Capacity Analysis

## 3: Granite Court/Oaklahoma Drive

Future Background 2037 AM  
AM Peak Hour



Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (veh/h)	0	225	434	0	0	0
Future Volume (Veh/h)	0	225	434	0	0	0
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	245	472	0	0	0
<b>Pedestrians</b>						
Lane Width (m)						
Walking Speed (m/s)						
Percent Blockage						
Right turn flare (veh)						
Median type		None	None			
Median storage (veh)						
Upstream signal (m)	78					
pX, platoon unblocked	0.98				0.98	0.98
vC, conflicting volume	472				717	472
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	453				702	453
tC, single (s)	4.1				6.4	6.2
tC, 2 stage (s)						
tF (s)	2.2				3.5	3.3
p0 queue free %	100				100	100
cM capacity (veh/h)	1088				397	596
<b>Direction, Lane #</b>	<b>EB 1</b>	<b>WB 1</b>	<b>SB 1</b>			
Volume Total	245	472	0			
Volume Left	0	0	0			
Volume Right	0	0	0			
cSH	1088	1700	1700			
Volume to Capacity	0.00	0.28	0.00			
Queue Length 95th (m)	0.0	0.0	0.0			
Control Delay (s)	0.0	0.0	0.0			
Lane LOS			A			
Approach Delay (s)	0.0	0.0	0.0			
Approach LOS			A			
<b>Intersection Summary</b>						
Average Delay			0.0			
Intersection Capacity Utilization			26.2%	ICU Level of Service	A	
Analysis Period (min)			15			

---













**Network Totals**

---

Number of Intersections	3
Total Delay (hr)	22
Stops (#)	1921
Average Speed (km/hr)	24
Total Travel Time (hr)	37
Distance Traveled (km)	893
Fuel Consumed (l)	199
Fuel Economy (km/l)	4.5
Unserved Vehicles (#)	0
Vehicles in dilemma zone (#)	73
Performance Index	27.1

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Future Background 2037 PM  
PM Peak Hour

						
Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Volume (vph)	143	346	568	194	753	524
Future Volume (vph)	143	346	568	194	753	524
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Storage Length (m)	0.0	0.0		30.0	70.0	
Storage Lanes	1	1		1	1	
Taper Length (m)	2.5				30.0	
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt		0.850		0.850		
Flt Protected	0.950				0.950	0.981
Satd. Flow (prot)	1789	1617	3544	1585	1628	3363
Flt Permitted	0.950				0.950	0.981
Satd. Flow (perm)	1789	1617	3544	1585	1628	3363
Right Turn on Red		Yes		Yes		
Satd. Flow (RTOR)		103		158		
Link Speed (k/h)	60		60			60
Link Distance (m)	376.4		200.0			221.2
Travel Time (s)	22.6		12.0			13.3
Peak Hour Factor	0.95	0.95	0.95	0.95	0.95	0.95
Heavy Vehicles (%)	2%	1%	3%	3%	2%	2%
Adj. Flow (vph)	151	364	598	204	793	552
Shared Lane Traffic (%)					45%	
Lane Group Flow (vph)	151	364	598	204	436	909
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Right	Left	Right	Left	Left
Median Width(m)	3.7		3.7			3.7
Link Offset(m)	0.0		0.0			0.0
Crosswalk Width(m)	1.6		1.6			1.6
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24	14		14	24	
Number of Detectors	1	1	2	1	1	2
Detector Template	Left	Right	Thru	Right	Left	Thru
Leading Detector (m)	6.1	6.1	30.5	6.1	6.1	30.5
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)	6.1	6.1	1.8	6.1	6.1	1.8
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel						
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)			28.7			28.7
Detector 2 Size(m)			1.8			1.8
Detector 2 Type			Cl+Ex			Cl+Ex
Detector 2 Channel						
Detector 2 Extend (s)			0.0			0.0
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Future Background 2037 PM  
PM Peak Hour




Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Permitted Phases	8	8		5		
Detector Phase	8	2	5	5	2	2
Switch Phase						
Minimum Initial (s)	8.0	20.0	20.0	20.0	20.0	20.0
Minimum Split (s)	32.0	27.0	39.0	39.0	27.0	27.0
Total Split (s)	35.2	30.8	44.0	44.0	30.8	30.8
Total Split (%)	32.0%	28.0%	40.0%	40.0%	28.0%	28.0%
Maximum Green (s)	28.8	23.8	37.0	37.0	23.8	23.8
Yellow Time (s)	4.2	4.4	4.4	4.4	4.4	4.4
All-Red Time (s)	2.2	2.6	2.6	2.6	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lead/Lag						
Lead-Lag Optimize?						
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Recall Mode	None	C-Max	None	None	C-Max	C-Max
Walk Time (s)	7.0	5.0	7.0	7.0	5.0	5.0
Flash Dont Walk (s)	18.0	5.0	25.0	25.0	5.0	5.0
Pedestrian Calls (#/hr)	0	0	0	0	0	0
Act Effct Green (s)	14.6	70.2	25.8	25.8	49.1	49.1
Actuated g/C Ratio	0.13	0.64	0.23	0.23	0.45	0.45
v/c Ratio	0.64	0.34	0.72	0.41	0.60	0.61
Control Delay	56.8	8.0	58.5	27.8	29.8	27.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	56.8	8.0	58.5	27.8	29.8	27.0
LOS	E	A	E	C	C	C
Approach Delay	22.3		50.7			27.9
Approach LOS	C		D			C

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 33 (30%), Referenced to phase 2:SBTL and 6:, Start of Green  
 Natural Cycle: 100  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.72  
 Intersection Signal Delay: 33.7  
 Intersection LOS: C  
 Intersection Capacity Utilization 65.8%  
 ICU Level of Service C  
 Analysis Period (min) 15

Splits and Phases: 1: Whites Road South & Bayly Street



Queues

1: Whites Road South & Bayly Street



Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Group Flow (vph)	151	364	598	204	436	909
v/c Ratio	0.64	0.34	0.72	0.41	0.60	0.61
Control Delay	56.8	8.0	58.5	27.8	29.8	27.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	56.8	8.0	58.5	27.8	29.8	27.0
Queue Length 50th (m)	31.1	22.3	69.0	18.6	75.6	79.0
Queue Length 95th (m)	49.1	45.5	m83.4	m31.0	#145.3	122.5
Internal Link Dist (m)	352.4		176.0			197.2
Turn Bay Length (m)				30.0	70.0	
Base Capacity (vph)	468	1068	1192	637	727	1502
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.32	0.34	0.50	0.32	0.60	0.61

Intersection Summary
















# 95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

m Volume for 95th percentile queue is metered by upstream signal.























HCM Signalized Intersection Capacity Analysis  
 1: Whites Road South & Bayly Street

Future Background 2037 PM  
 PM Peak Hour

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			  
Traffic Volume (vph)	143	346	568	194	753	524
Future Volume (vph)	143	346	568	194	753	524
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt	1.00	0.85	1.00	0.85	1.00	1.00
Flt Protected	0.95	1.00	1.00	1.00	0.95	0.98
Satd. Flow (prot)	1789	1617	3544	1585	1628	3362
Flt Permitted	0.95	1.00	1.00	1.00	0.95	0.98
Satd. Flow (perm)	1789	1617	3544	1585	1628	3362
Peak-hour factor, PHF	0.95	0.95	0.95	0.95	0.95	0.95
Adj. Flow (vph)	151	364	598	204	793	552
RTOR Reduction (vph)	0	43	0	121	0	0
Lane Group Flow (vph)	151	321	598	83	436	909
Heavy Vehicles (%)	2%	1%	3%	3%	2%	2%
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2
Permitted Phases	8	8		5		
Actuated Green, G (s)	14.6	63.8	25.8	25.8	49.2	49.2
Effective Green, g (s)	14.6	63.8	25.8	25.8	49.2	49.2
Actuated g/C Ratio	0.13	0.58	0.23	0.23	0.45	0.45
Clearance Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	237	937	831	371	728	1503
v/s Ratio Prot		0.15	c0.17		0.27	c0.27
v/s Ratio Perm	c0.08	0.05		0.05		
v/c Ratio	0.64	0.34	0.72	0.22	0.60	0.60
Uniform Delay, d1	45.2	12.1	38.8	34.0	23.0	23.0
Progression Factor	1.00	1.00	1.42	2.88	1.00	1.00
Incremental Delay, d2	5.5	0.2	2.4	0.2	3.6	1.8
Delay (s)	50.7	12.3	57.4	98.1	26.6	24.8
Level of Service	D	B	E	F	C	C
Approach Delay (s)	23.6		67.7			25.4
Approach LOS	C		E			C
<b>Intersection Summary</b>						
HCM 2000 Control Delay			37.8		HCM 2000 Level of Service	D
HCM 2000 Volume to Capacity ratio			0.64			
Actuated Cycle Length (s)			110.0		Sum of lost time (s)	20.4
Intersection Capacity Utilization			65.8%		ICU Level of Service	C
Analysis Period (min)			15			
c Critical Lane Group						

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Background 2037 PM  
PM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	423	74	12	10	60	203	16	111	14	274	198	193
Future Volume (vph)	423	74	12	10	60	203	16	111	14	274	198	193
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (m)	20.0		0.0	15.0		15.0	20.0		0.0	20.0		0.0
Storage Lanes	1		0	1		1	1		0	1		1
Taper Length (m)	40.0			10.0			40.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.979				0.850		0.983				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1706	1881	0	1659	1921	1601	1825	1855	0	1807	1902	1570
Flt Permitted	0.551			0.697			0.620			0.671		
Satd. Flow (perm)	989	1881	0	1217	1921	1601	1191	1855	0	1276	1902	1570
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		11				218		6				208
Link Speed (k/h)		50			50			60				60
Link Distance (m)		78.3			208.1			259.8				200.0
Travel Time (s)		5.6			15.0			15.6				12.0
Peak Hour Factor	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93
Heavy Vehicles (%)	4%	0%	0%	10%	0%	2%	0%	2%	0%	1%	1%	4%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Adj. Flow (vph)	455	80	13	11	65	218	17	119	15	295	213	208
Shared Lane Traffic (%)												
Lane Group Flow (vph)	455	93	0	11	65	218	17	134	0	295	213	208
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			3.7				3.7
Link Offset(m)		0.0			0.0			0.0				0.0
Crosswalk Width(m)		1.6			1.6			1.6				1.6
Two way Left Turn Lane												
Headway Factor	1.02	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	6.1	30.5		6.1	30.5	6.1	6.1	30.5		6.1	30.5	6.1
Trailing Detector (m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	6.1	1.8		6.1	1.8	6.1	6.1	1.8		6.1	1.8	6.1
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		28.7			28.7			28.7				28.7
Detector 2 Size(m)		1.8			1.8			1.8				1.8
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex				Cl+Ex
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0				0.0
Turn Type	pm+pt	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Background 2037 PM  
PM Peak Hour




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Protected Phases	7	4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Detector Phase	7	4		8	8	8	2	2		6	6	6
Switch Phase												
Minimum Initial (s)	5.0	8.0		8.0	8.0	8.0	20.0	20.0		20.0	20.0	20.0
Minimum Split (s)	9.5	36.0		36.0	36.0	36.0	32.0	32.0		32.0	32.0	32.0
Total Split (s)	27.6	63.6		36.0	36.0	36.0	46.4	46.4		46.4	46.4	46.4
Total Split (%)	25.1%	57.8%		32.7%	32.7%	32.7%	42.2%	42.2%		42.2%	42.2%	42.2%
Maximum Green (s)	24.6	57.4		29.8	29.8	29.8	40.1	40.1		40.1	40.1	40.1
Yellow Time (s)	3.0	3.3		3.3	3.3	3.3	4.2	4.2		4.2	4.2	4.2
All-Red Time (s)	0.0	2.9		2.9	2.9	2.9	2.1	2.1		2.1	2.1	2.1
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lead/Lag	Lead			Lag	Lag	Lag						
Lead-Lag Optimize?	Yes			Yes	Yes	Yes						
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	None		None	None	None	C-Max	C-Max		C-Max	C-Max	C-Max
Walk Time (s)		7.0		7.0	7.0	7.0	7.0	7.0		7.0	7.0	7.0
Flash Dont Walk (s)		22.0		22.0	22.0	22.0	18.0	18.0		18.0	18.0	18.0
Pedestrian Calls (#/hr)		0		0	0	0	0	0		0	0	0
Act Effct Green (s)	40.9	37.7		10.1	10.1	10.1	59.8	59.8		59.8	59.8	59.8
Actuated g/C Ratio	0.37	0.34		0.09	0.09	0.09	0.54	0.54		0.54	0.54	0.54
v/c Ratio	0.86	0.14		0.10	0.37	0.63	0.03	0.13		0.43	0.21	0.22
Control Delay	47.3	21.9		46.0	52.2	14.9	12.9	12.8		7.5	4.9	2.0
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	47.3	21.9		46.0	52.2	14.9	12.9	12.8		7.5	4.9	2.0
LOS	D	C		D	D	B	B	B		A	A	A
Approach Delay		43.0			24.3			12.8			5.1	
Approach LOS		D			C			B			A	

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 40.7 (37%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green  
 Natural Cycle: 80  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.86  
 Intersection Signal Delay: 21.2      Intersection LOS: C  
 Intersection Capacity Utilization 79.1%      ICU Level of Service D  
 Analysis Period (min) 15

Splits and Phases: 2: Whites Road South & Oklahoma Drive





Queues  
2: Whites Road South & Oklahoma Drive

Future Background 2037 PM  
PM Peak Hour



Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	SBL	SBT	SBR
Lane Group Flow (vph)	455	93	11	65	218	17	134	295	213	208
v/c Ratio	0.86	0.14	0.10	0.37	0.63	0.03	0.13	0.43	0.21	0.22
Control Delay	47.3	21.9	46.0	52.2	14.9	12.9	12.8	7.5	4.9	2.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	47.3	21.9	46.0	52.2	14.9	12.9	12.8	7.5	4.9	2.0
Queue Length 50th (m)	84.0	12.2	2.2	13.5	0.0	1.6	12.6	15.6	10.9	2.4
Queue Length 95th (m)	#117.6	22.0	7.4	25.6	20.8	5.4	24.9	21.0	15.9	5.9
Internal Link Dist (m)		54.3		184.1			235.8		176.0	
Turn Bay Length (m)	20.0		15.0		15.0	20.0		20.0		
Base Capacity (vph)	528	986	329	520	592	647	1011	694	1034	948
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.86	0.09	0.03	0.13	0.37	0.03	0.13	0.43	0.21	0.22























Intersection Summary

# 95th percentile volume exceeds capacity, queue may be longer.  
Queue shown is maximum after two cycles.

# HCM Signalized Intersection Capacity Analysis

## 2: Whites Road South & Oklahoma Drive

Future Background 2037 PM  
PM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	423	74	12	10	60	203	16	111	14	274	198	193
Future Volume (vph)	423	74	12	10	60	203	16	111	14	274	198	193
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lane Util. Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.00	1.00	1.00
Frt	1.00	0.98		1.00	1.00	0.85	1.00	0.98		1.00	1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00	1.00	0.95	1.00		0.95	1.00	1.00
Satd. Flow (prot)	1706	1881		1659	1921	1601	1825	1856		1807	1902	1570
Flt Permitted	0.55	1.00		0.70	1.00	1.00	0.62	1.00		0.67	1.00	1.00
Satd. Flow (perm)	989	1881		1217	1921	1601	1191	1856		1277	1902	1570
Peak-hour factor, PHF	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93
Adj. Flow (vph)	455	80	13	11	65	218	17	119	15	295	213	208
RTOR Reduction (vph)	0	7	0	0	0	198	0	3	0	0	0	95
Lane Group Flow (vph)	455	86	0	11	65	20	17	131	0	295	213	113
Heavy Vehicles (%)	4%	0%	0%	10%	0%	2%	0%	2%	0%	1%	1%	4%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Turn Type	pm+pt	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm
Protected Phases	7	4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Actuated Green, G (s)	37.7	37.7		10.1	10.1	10.1	59.8	59.8		59.8	59.8	59.8
Effective Green, g (s)	37.7	37.7		10.1	10.1	10.1	59.8	59.8		59.8	59.8	59.8
Actuated g/C Ratio	0.34	0.34		0.09	0.09	0.09	0.54	0.54		0.54	0.54	0.54
Clearance Time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Lane Grp Cap (vph)	499	644		111	176	147	647	1008		694	1033	853
v/s Ratio Prot	c0.20	0.05			0.03			0.07			0.11	
v/s Ratio Perm	c0.11			0.01		0.01	0.01			c0.23		0.07
v/c Ratio	0.91	0.13		0.10	0.37	0.14	0.03	0.13		0.43	0.21	0.13
Uniform Delay, d1	32.7	24.9		45.8	47.0	45.9	11.6	12.3		14.9	12.9	12.3
Progression Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		0.37	0.33	0.78
Incremental Delay, d2	20.9	0.1		0.4	1.3	0.4	0.1	0.3		1.6	0.4	0.3
Delay (s)	53.6	25.0		46.2	48.3	46.4	11.7	12.6		7.1	4.6	9.9
Level of Service	D	C		D	D	D	B	B		A	A	A
Approach Delay (s)		48.7			46.8			12.5			7.2	
Approach LOS		D			D			B			A	
<b>Intersection Summary</b>												
HCM 2000 Control Delay			27.8	HCM 2000 Level of Service				C				
HCM 2000 Volume to Capacity ratio			0.63									
Actuated Cycle Length (s)			110.0	Sum of lost time (s)				15.5				
Intersection Capacity Utilization			79.1%	ICU Level of Service				D				
Analysis Period (min)			15									

c Critical Lane Group

Lanes, Volumes, Timings  
3: Granite Court/Oaklahoma Drive

Future Background 2037 PM  
PM Peak Hour




Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		↶	↷		↶	↷
Traffic Volume (vph)	0	509	270	0	0	0
Future Volume (vph)	0	509	270	0	0	0
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00
<b>Fr</b>						
Flt Protected						
Satd. Flow (prot)	0	1883	1883	0	1883	0
Flt Permitted						
Satd. Flow (perm)	0	1883	1883	0	1883	0
Link Speed (k/h)		50	50		48	
Link Distance (m)		466.2	78.3		125.8	
Travel Time (s)		33.6	5.6		9.4	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	0	553	293	0	0	0
Shared Lane Traffic (%)						
Lane Group Flow (vph)	0	553	293	0	0	0
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Left	Left	Right	Left	Right
Median Width(m)		3.7	3.7		3.7	
Link Offset(m)		0.0	0.0		0.0	
Crosswalk Width(m)		1.6	1.6		1.6	
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24			14	24	14
Sign Control		Free	Free		Stop	
<b>Intersection Summary</b>						
Area Type:	Other					
Control Type:	Unsignalized					
Intersection Capacity Utilization	30.1%			ICU Level of Service A		
Analysis Period (min)	15					

# HCM Unsignalized Intersection Capacity Analysis

## 3: Granite Court/Oaklahoma Drive

Future Background 2037 PM  
PM Peak Hour



Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		↔	↔		↔	
Traffic Volume (veh/h)	0	509	270	0	0	0
Future Volume (Veh/h)	0	509	270	0	0	0
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	553	293	0	0	0
Pedestrians						
Lane Width (m)						
Walking Speed (m/s)						
Percent Blockage						
Right turn flare (veh)						
Median type		None	None			
Median storage (veh)						
Upstream signal (m)			78			
pX, platoon unblocked	0.97				0.97	0.97
vC, conflicting volume	293				846	293
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	260				828	260
tC, single (s)	4.1				6.4	6.2
tC, 2 stage (s)						
tF (s)	2.2				3.5	3.3
p0 queue free %	100				100	100
cM capacity (veh/h)	1270				332	758
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total	553	293	0			
Volume Left	0	0	0			
Volume Right	0	0	0			
cSH	1270	1700	1700			
Volume to Capacity	0.00	0.17	0.00			
Queue Length 95th (m)	0.0	0.0	0.0			
Control Delay (s)	0.0	0.0	0.0			
Lane LOS			A			
Approach Delay (s)	0.0	0.0	0.0			
Approach LOS			A			
Intersection Summary						
Average Delay			0.0			
Intersection Capacity Utilization			30.1%	ICU Level of Service		A
Analysis Period (min)			15			

---
















**Network Totals**

---

Number of Intersections	3
Total Delay (hr)	33
Stops (#)	2612
Average Speed (km/hr)	21
Total Travel Time (hr)	53
Distance Traveled (km)	1144
Fuel Consumed (l)	273
Fuel Economy (km/l)	4.2
Unserviced Vehicles (#)	0
Vehicles in dilemma zone (#)	52
Performance Index	40.3

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Future Total 2027 AM  
AM Peak Hour

						
Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			  
Traffic Volume (vph)	106	272	573	74	374	521
Future Volume (vph)	106	272	573	74	374	521
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Storage Length (m)	0.0	0.0		30.0	70.0	
Storage Lanes	1	1		1	1	
Taper Length (m)	2.5				30.0	
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt		0.850		0.850		
Flt Protected	0.950				0.950	0.993
Satd. Flow (prot)	1722	1570	3510	1601	1612	3371
Flt Permitted	0.950				0.950	0.993
Satd. Flow (perm)	1722	1570	3510	1601	1612	3371
Right Turn on Red		Yes		Yes		
Satd. Flow (RTOR)		86		62		
Link Speed (k/h)	60		60			60
Link Distance (m)	376.4		200.0			221.2
Travel Time (s)	22.6		12.0			13.3
Peak Hour Factor	0.84	0.84	0.84	0.84	0.84	0.84
Heavy Vehicles (%)	6%	4%	4%	2%	3%	3%
Adj. Flow (vph)	126	324	682	88	445	620
Shared Lane Traffic (%)					22%	
Lane Group Flow (vph)	126	324	682	88	347	718
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Right	Left	Right	Left	Left
Median Width(m)	3.7		3.7			3.7
Link Offset(m)	0.0		0.0			0.0
Crosswalk Width(m)	1.6		1.6			1.6
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24	14		14	24	
Number of Detectors	1	1	2	1	1	2
Detector Template	Left	Right	Thru	Right	Left	Thru
Leading Detector (m)	6.1	6.1	30.5	6.1	6.1	30.5
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)	6.1	6.1	1.8	6.1	6.1	1.8
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel						
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)			28.7			28.7
Detector 2 Size(m)			1.8			1.8
Detector 2 Type			Cl+Ex			Cl+Ex
Detector 2 Channel						
Detector 2 Extend (s)			0.0			0.0
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street


Future Total 2027 AM  
AM Peak Hour

Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Permitted Phases	8	8		5		
Detector Phase	8	2	5	5	2	2
Switch Phase						
Minimum Initial (s)	5.0	20.0	20.0	20.0	20.0	20.0
Minimum Split (s)	32.0	27.0	39.0	39.0	27.0	27.0
Total Split (s)	35.2	28.6	46.2	46.2	28.6	28.6
Total Split (%)	32.0%	26.0%	42.0%	42.0%	26.0%	26.0%
Maximum Green (s)	28.8	21.6	39.2	39.2	21.6	21.6
Yellow Time (s)	4.2	4.4	4.4	4.4	4.4	4.4
All-Red Time (s)	2.2	2.6	2.6	2.6	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lead/Lag						
Lead-Lag Optimize?						
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Recall Mode	None	C-Max	None	None	C-Max	C-Max
Walk Time (s)	7.0	5.0	7.0	7.0	5.0	5.0
Flash Dont Walk (s)	18.0	5.0	25.0	25.0	5.0	5.0
Pedestrian Calls (#/hr)	0	0	0	0	0	0
Act Effct Green (s)	13.4	67.7	28.3	28.3	47.9	47.9
Actuated g/C Ratio	0.12	0.62	0.26	0.26	0.44	0.44
v/c Ratio	0.60	0.32	0.76	0.19	0.49	0.49
Control Delay	57.2	9.1	35.9	7.8	28.0	25.6
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.2	9.1	35.9	7.8	28.0	25.6
LOS	E	A	D	A	C	C
Approach Delay	22.6		32.7			26.4
Approach LOS	C		C			C

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 24.2 (22%), Referenced to phase 2:SBTL and 6:, Start of Green  
 Natural Cycle: 100  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.76  
 Intersection Signal Delay: 27.7  
 Intersection LOS: C  
 Intersection Capacity Utilization 56.4%  
 ICU Level of Service B  
 Analysis Period (min) 15

Splits and Phases: 1: Whites Road South & Bayly Street



Queues  
1: Whites Road South & Bayly Street

Future Total 2027 AM  
AM Peak Hour

















Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Group Flow (vph)	126	324	682	88	347	718
v/c Ratio	0.60	0.32	0.76	0.19	0.49	0.49
Control Delay	57.2	9.1	35.9	7.8	28.0	25.6
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.2	9.1	35.9	7.8	28.0	25.6
Queue Length 50th (m)	26.0	21.8	72.2	0.0	57.8	59.6
Queue Length 95th (m)	39.6	39.5	71.8	5.4	95.6	85.4
Internal Link Dist (m)	352.4		176.0			197.2
Turn Bay Length (m)				30.0	70.0	
Base Capacity (vph)	450	999	1250	610	702	1469
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.28	0.32	0.55	0.14	0.49	0.49
<b>Intersection Summary</b>						

























HCM Signalized Intersection Capacity Analysis  
 1: Whites Road South & Bayly Street

Future Total 2027 AM  
 AM Peak Hour

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			 
Traffic Volume (vph)	106	272	573	74	374	521
Future Volume (vph)	106	272	573	74	374	521
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt	1.00	0.85	1.00	0.85	1.00	1.00
Flt Protected	0.95	1.00	1.00	1.00	0.95	0.99
Satd. Flow (prot)	1722	1570	3510	1601	1612	3372
Flt Permitted	0.95	1.00	1.00	1.00	0.95	0.99
Satd. Flow (perm)	1722	1570	3510	1601	1612	3372
Peak-hour factor, PHF	0.84	0.84	0.84	0.84	0.84	0.84
Adj. Flow (vph)	126	324	682	88	445	620
RTOR Reduction (vph)	0	38	0	46	0	0
Lane Group Flow (vph)	126	286	682	42	347	718
Heavy Vehicles (%)	6%	4%	4%	2%	3%	3%
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2
Permitted Phases	8	8		5		
Actuated Green, G (s)	13.4	61.3	28.3	28.3	47.9	47.9
Effective Green, g (s)	13.4	61.3	28.3	28.3	47.9	47.9
Actuated g/C Ratio	0.12	0.56	0.26	0.26	0.44	0.44
Clearance Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	209	874	903	411	701	1468
v/s Ratio Prot		0.14	c0.19		c0.22	0.21
v/s Ratio Perm	c0.07	0.04		0.03		
v/c Ratio	0.60	0.33	0.76	0.10	0.50	0.49
Uniform Delay, d1	45.8	13.2	37.7	31.2	22.3	22.3
Progression Factor	1.00	1.00	0.82	0.62	1.00	1.00
Incremental Delay, d2	4.8	0.2	3.4	0.1	2.5	1.2
Delay (s)	50.6	13.4	34.2	19.6	24.8	23.4
Level of Service	D	B	C	B	C	C
Approach Delay (s)	23.8		32.6			23.9
Approach LOS	C		C			C
<b>Intersection Summary</b>						
HCM 2000 Control Delay			26.8		HCM 2000 Level of Service	C
HCM 2000 Volume to Capacity ratio			0.59			
Actuated Cycle Length (s)			110.0		Sum of lost time (s)	20.4
Intersection Capacity Utilization			56.4%		ICU Level of Service	B
Analysis Period (min)			15			
c Critical Lane Group						


Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Total 2027 AM  
AM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	209	44	11	7	55	297	17	132	24	185	77	358
Future Volume (vph)	209	44	11	7	55	297	17	132	24	185	77	358
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (m)	20.0		0.0	15.0		15.0	20.0		0.0	20.0		0.0
Storage Lanes	1		0	1		1	1		0	1		1
Taper Length (m)	40.0			10.0			40.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.969				0.850		0.977				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1658	1813	0	1825	1921	1601	1722	1861	0	1755	1762	1601
Flt Permitted	0.713			0.713			0.695			0.636		
Satd. Flow (perm)	1244	1813	0	1370	1921	1601	1260	1861	0	1175	1762	1601
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		14				367		12				442
Link Speed (k/h)		50			50			60				60
Link Distance (m)		78.3			208.1			259.8				200.0
Travel Time (s)		5.6			15.0			15.6				12.0
Peak Hour Factor	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81
Heavy Vehicles (%)	7%	0%	13%	0%	0%	2%	6%	1%	0%	4%	9%	2%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Adj. Flow (vph)	258	54	14	9	68	367	21	163	30	228	95	442
Shared Lane Traffic (%)												
Lane Group Flow (vph)	258	68	0	9	68	367	21	193	0	228	95	442
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			3.7				3.7
Link Offset(m)		0.0			0.0			0.0				0.0
Crosswalk Width(m)		1.6			1.6			1.6				1.6
Two way Left Turn Lane												
Headway Factor	1.02	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	6.1	30.5		6.1	30.5	6.1	6.1	30.5		6.1	30.5	6.1
Trailing Detector (m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	6.1	1.8		6.1	1.8	6.1	6.1	1.8		6.1	1.8	6.1
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		28.7			28.7			28.7				28.7
Detector 2 Size(m)		1.8			1.8			1.8				1.8
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex				Cl+Ex
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0				0.0
Turn Type	Perm	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Total 2027 AM  
AM Peak Hour




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Protected Phases		4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Detector Phase	4	4		8	8	8	2	2		6	6	6
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0	5.0	5.0	5.0		5.0	5.0	5.0
Minimum Split (s)	36.0	36.0		36.0	36.0	36.0	32.0	32.0		32.0	32.0	32.0
Total Split (s)	48.4	48.4		48.4	48.4	48.4	61.6	61.6		61.6	61.6	61.6
Total Split (%)	44.0%	44.0%		44.0%	44.0%	44.0%	56.0%	56.0%		56.0%	56.0%	56.0%
Maximum Green (s)	42.2	42.2		42.2	42.2	42.2	55.3	55.3		55.3	55.3	55.3
Yellow Time (s)	3.3	3.3		3.3	3.3	3.3	4.2	4.2		4.2	4.2	4.2
All-Red Time (s)	2.9	2.9		2.9	2.9	2.9	2.1	2.1		2.1	2.1	2.1
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lead/Lag												
Lead-Lag Optimize?												
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	None		None	None	None	C-Max	C-Max		C-Max	C-Max	C-Max
Walk Time (s)	7.0	7.0		7.0	7.0	7.0	7.0	7.0		7.0	7.0	7.0
Flash Dont Walk (s)	22.0	22.0		22.0	22.0	22.0	18.0	18.0		18.0	18.0	18.0
Pedestrian Calls (#/hr)	0	0		0	0	0	0	0		0	0	0
Act Effct Green (s)	28.6	28.6		28.6	28.6	28.6	68.9	68.9		68.9	68.9	68.9
Actuated g/C Ratio	0.26	0.26		0.26	0.26	0.26	0.63	0.63		0.63	0.63	0.63
v/c Ratio	0.80	0.14		0.03	0.14	0.53	0.03	0.16		0.31	0.09	0.38
Control Delay	55.2	23.1		25.7	29.0	5.8	10.6	9.9		16.9	15.7	8.0
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	55.2	23.1		25.7	29.0	5.8	10.6	9.9		16.9	15.7	8.0
LOS	E	C		C	C	A	B	A		B	B	A
Approach Delay		48.5			9.8			10.0			11.6	
Approach LOS		D			A			A			B	

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 83.6 (76%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green  
 Natural Cycle: 70  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.80  
 Intersection Signal Delay: 17.8  
 Intersection Capacity Utilization 54.0%  
 Analysis Period (min) 15  
 Intersection LOS: B  
 ICU Level of Service A

Splits and Phases: 2: Whites Road South & Oklahoma Drive



Queues  
2: Whites Road South & Oklahoma Drive























Future Total 2027 AM  
AM Peak Hour



Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	SBL	SBT	SBR
Lane Group Flow (vph)	258	68	9	68	367	21	193	228	95	442
v/c Ratio	0.80	0.14	0.03	0.14	0.53	0.03	0.16	0.31	0.09	0.38
Control Delay	55.2	23.1	25.7	29.0	5.8	10.6	9.9	16.9	15.7	8.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	55.2	23.1	25.7	29.0	5.8	10.6	9.9	16.9	15.7	8.0
Queue Length 50th (m)	51.8	8.9	1.4	11.2	0.0	1.6	14.9	11.8	4.9	2.4
Queue Length 95th (m)	61.7	15.1	4.2	17.2	10.9	5.2	27.9	44.8	22.6	57.2
Internal Link Dist (m)		54.3		184.1			235.8		176.0	
Turn Bay Length (m)	20.0		15.0		15.0	20.0		20.0		
Base Capacity (vph)	477	704	525	736	840	789	1170	735	1103	1167
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.54	0.10	0.02	0.09	0.44	0.03	0.16	0.31	0.09	0.38
Intersection Summary										

HCM Signalized Intersection Capacity Analysis  
2: Whites Road South & Oklahoma Drive

Future Total 2027 AM  
AM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	209	44	11	7	55	297	17	132	24	185	77	358
Future Volume (vph)	209	44	11	7	55	297	17	132	24	185	77	358
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lane Util. Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.00	1.00	1.00
Frt	1.00	0.97		1.00	1.00	0.85	1.00	0.98		1.00	1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00	1.00	0.95	1.00		0.95	1.00	1.00
Satd. Flow (prot)	1658	1813		1825	1921	1601	1722	1861		1755	1762	1601
Flt Permitted	0.71	1.00		0.71	1.00	1.00	0.70	1.00		0.64	1.00	1.00
Satd. Flow (perm)	1244	1813		1369	1921	1601	1260	1861		1175	1762	1601
Peak-hour factor, PHF	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81
Adj. Flow (vph)	258	54	14	9	68	367	21	163	30	228	95	442
RTOR Reduction (vph)	0	10	0	0	0	272	0	4	0	0	0	165
Lane Group Flow (vph)	258	58	0	9	68	95	21	189	0	228	95	277
Heavy Vehicles (%)	7%	0%	13%	0%	0%	2%	6%	1%	0%	4%	9%	2%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Turn Type	Perm	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm
Protected Phases		4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Actuated Green, G (s)	28.6	28.6		28.6	28.6	28.6	68.9	68.9		68.9	68.9	68.9
Effective Green, g (s)	28.6	28.6		28.6	28.6	28.6	68.9	68.9		68.9	68.9	68.9
Actuated g/C Ratio	0.26	0.26		0.26	0.26	0.26	0.63	0.63		0.63	0.63	0.63
Clearance Time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Lane Grp Cap (vph)	323	471		355	499	416	789	1165		735	1103	1002
v/s Ratio Prot		0.03			0.04			0.10			0.05	
v/s Ratio Perm	c0.21			0.01		0.06	0.02			c0.19		0.17
v/c Ratio	0.80	0.12		0.03	0.14	0.23	0.03	0.16		0.31	0.09	0.28
Uniform Delay, d1	38.0	31.1		30.3	31.2	32.0	7.8	8.5		9.5	8.1	9.3
Progression Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.38	1.55	5.68
Incremental Delay, d2	12.9	0.1		0.0	0.1	0.3	0.1	0.3		1.0	0.1	0.6
Delay (s)	50.9	31.2		30.3	31.3	32.3	7.9	8.8		14.1	12.7	53.4
Level of Service	D	C		C	C	C	A	A		B	B	D
Approach Delay (s)		46.8			32.1			8.7			36.6	
Approach LOS		D			C			A			D	
<b>Intersection Summary</b>												
HCM 2000 Control Delay			34.0				HCM 2000 Level of Service				C	
HCM 2000 Volume to Capacity ratio			0.45									
Actuated Cycle Length (s)			110.0				Sum of lost time (s)			12.5		
Intersection Capacity Utilization			54.0%				ICU Level of Service			A		
Analysis Period (min)			15									

c Critical Lane Group

Lanes, Volumes, Timings  
3: Granite Court/Oaklahoma Drive

Future Total 2027 AM  
AM Peak Hour



Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (vph)	2	214	413	18	50	5
Future Volume (vph)	2	214	413	18	50	5
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00
Frt			0.994		0.989	
Flt Protected					0.956	
Satd. Flow (prot)	0	1883	1872	0	1781	0
Flt Permitted					0.956	
Satd. Flow (perm)	0	1883	1872	0	1781	0
Link Speed (k/h)		50	50		48	
Link Distance (m)		466.2	78.3		125.8	
Travel Time (s)		33.6	5.6		9.4	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	2	233	449	20	54	5
Shared Lane Traffic (%)						
Lane Group Flow (vph)	0	235	469	0	59	0
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Left	Left	Right	Left	Right
Median Width(m)		3.7	3.7		3.7	
Link Offset(m)		0.0	0.0		0.0	
Crosswalk Width(m)		1.6	1.6		1.6	
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24			14	24	14
Sign Control		Free	Free		Stop	

Intersection Summary

Area Type:	Other
Control Type:	Unsignalized
Intersection Capacity Utilization	32.8%
Analysis Period (min)	15
	ICU Level of Service A

HCM Unsignalized Intersection Capacity Analysis  
3: Granite Court/Oaklahoma Drive

Future Total 2027 AM  
AM Peak Hour



Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		↔	↔		↔	
Traffic Volume (veh/h)	2	214	413	18	50	5
Future Volume (Veh/h)	2	214	413	18	50	5
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	2	233	449	20	54	5
Pedestrians						
Lane Width (m)						
Walking Speed (m/s)						
Percent Blockage						
Right turn flare (veh)						
Median type		None	None			
Median storage (veh)						
Upstream signal (m)			78			
pX, platoon unblocked	0.98				0.98	0.98
vC, conflicting volume	469				696	459
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	453				683	442
tC, single (s)	4.1				6.4	6.2
tC, 2 stage (s)						
tF (s)	2.2				3.5	3.3
p0 queue free %	100				87	99
cM capacity (veh/h)	1091				408	606
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total	235	469	59			
Volume Left	2	0	54			
Volume Right	0	20	5			
cSH	1091	1700	419			
Volume to Capacity	0.00	0.28	0.14			
Queue Length 95th (m)	0.0	0.0	3.7			
Control Delay (s)	0.1	0.0	15.0			
Lane LOS	A		B			
Approach Delay (s)	0.1	0.0	15.0			
Approach LOS			B			
Intersection Summary						
Average Delay			1.2			
Intersection Capacity Utilization			32.8%		ICU Level of Service	A
Analysis Period (min)			15			

---

**Network Totals**
















---

Number of Intersections	3
Total Delay (hr)	22
Stops (#)	1971
Average Speed (km/hr)	23
Total Travel Time (hr)	37
Distance Traveled (km)	875
Fuel Consumed (l)	199
Fuel Economy (km/l)	4.4
Unserved Vehicles (#)	0
Vehicles in dilemma zone (#)	65
Performance Index	27.5



Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Future Total 2027 PM  
PM Peak Hour

						
Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			  
Traffic Volume (vph)	144	329	551	192	716	530
Future Volume (vph)	144	329	551	192	716	530
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Storage Length (m)	0.0	0.0		30.0	70.0	
Storage Lanes	1	1		1	1	
Taper Length (m)	2.5				30.0	
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt		0.850		0.850		
Flt Protected	0.950				0.950	0.982
Satd. Flow (prot)	1789	1617	3544	1585	1628	3366
Flt Permitted	0.950				0.950	0.982
Satd. Flow (perm)	1789	1617	3544	1585	1628	3366
Right Turn on Red		Yes		Yes		
Satd. Flow (RTOR)		111		162		
Link Speed (k/h)	60		60			60
Link Distance (m)	376.4		200.0			221.2
Travel Time (s)	22.6		12.0			13.3
Peak Hour Factor	0.95	0.95	0.95	0.95	0.95	0.95
Heavy Vehicles (%)	2%	1%	3%	3%	2%	2%
Adj. Flow (vph)	152	346	580	202	754	558
Shared Lane Traffic (%)					43%	
Lane Group Flow (vph)	152	346	580	202	430	882
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Right	Left	Right	Left	Left
Median Width(m)	3.7		3.7			3.7
Link Offset(m)	0.0		0.0			0.0
Crosswalk Width(m)	1.6		1.6			1.6
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24	14		14	24	
Number of Detectors	1	1	2	1	1	2
Detector Template	Left	Right	Thru	Right	Left	Thru
Leading Detector (m)	6.1	6.1	30.5	6.1	6.1	30.5
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)	6.1	6.1	1.8	6.1	6.1	1.8
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel						
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)			28.7			28.7
Detector 2 Size(m)			1.8			1.8
Detector 2 Type			Cl+Ex			Cl+Ex
Detector 2 Channel						
Detector 2 Extend (s)			0.0			0.0
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Future Total 2027 PM  
PM Peak Hour




Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Permitted Phases	8	8		5		
Detector Phase	8	2	5	5	2	2
Switch Phase						
Minimum Initial (s)	8.0	20.0	20.0	20.0	20.0	20.0
Minimum Split (s)	32.0	27.0	39.0	39.0	27.0	27.0
Total Split (s)	35.2	30.8	44.0	44.0	30.8	30.8
Total Split (%)	32.0%	28.0%	40.0%	40.0%	28.0%	28.0%
Maximum Green (s)	28.8	23.8	37.0	37.0	23.8	23.8
Yellow Time (s)	4.2	4.4	4.4	4.4	4.4	4.4
All-Red Time (s)	2.2	2.6	2.6	2.6	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lead/Lag						
Lead-Lag Optimize?						
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Recall Mode	None	C-Max	None	None	C-Max	C-Max
Walk Time (s)	7.0	5.0	7.0	7.0	5.0	5.0
Flash Dont Walk (s)	18.0	5.0	25.0	25.0	5.0	5.0
Pedestrian Calls (#/hr)	0	0	0	0	0	0
Act Effct Green (s)	14.7	70.6	25.4	25.4	49.5	49.5
Actuated g/C Ratio	0.13	0.64	0.23	0.23	0.45	0.45
v/c Ratio	0.64	0.32	0.71	0.41	0.59	0.58
Control Delay	56.7	7.3	59.0	27.8	29.1	26.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	56.7	7.3	59.0	27.8	29.1	26.3
LOS	E	A	E	C	C	C
Approach Delay	22.4		51.0			27.2
Approach LOS	C		D			C

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 33 (30%), Referenced to phase 2:SBTL and 6:, Start of Green  
 Natural Cycle: 100  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.71  
 Intersection Signal Delay: 33.5  
 Intersection Capacity Utilization 65.3%  
 Analysis Period (min) 15  
 Intersection LOS: C  
 ICU Level of Service C

Splits and Phases: 1: Whites Road South & Bayly Street



Queues

Future Total 2027 PM

1: Whites Road South & Bayly Street

PM Peak Hour



Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Group Flow (vph)	152	346	580	202	430	882
v/c Ratio	0.64	0.32	0.71	0.41	0.59	0.58
Control Delay	56.7	7.3	59.0	27.8	29.1	26.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	56.7	7.3	59.0	27.8	29.1	26.3
Queue Length 50th (m)	31.3	19.2	67.2	18.6	73.6	75.1
Queue Length 95th (m)	49.3	40.6	m80.8	m30.8	#135.7	116.9
Internal Link Dist (m)	352.4		176.0			197.2
Turn Bay Length (m)				30.0	70.0	
Base Capacity (vph)	468	1077	1192	640	733	1515
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.32	0.32	0.49	0.32	0.59	0.58

Intersection Summary
















# 95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

m Volume for 95th percentile queue is metered by upstream signal.























HCM Signalized Intersection Capacity Analysis  
 1: Whites Road South & Bayly Street

Future Total 2027 PM  
 PM Peak Hour

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			  
Traffic Volume (vph)	144	329	551	192	716	530
Future Volume (vph)	144	329	551	192	716	530
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt	1.00	0.85	1.00	0.85	1.00	1.00
Flt Protected	0.95	1.00	1.00	1.00	0.95	0.98
Satd. Flow (prot)	1789	1617	3544	1585	1628	3366
Flt Permitted	0.95	1.00	1.00	1.00	0.95	0.98
Satd. Flow (perm)	1789	1617	3544	1585	1628	3366
Peak-hour factor, PHF	0.95	0.95	0.95	0.95	0.95	0.95
Adj. Flow (vph)	152	346	580	202	754	558
RTOR Reduction (vph)	0	46	0	125	0	0
Lane Group Flow (vph)	152	300	580	77	430	882
Heavy Vehicles (%)	2%	1%	3%	3%	2%	2%
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2
Permitted Phases	8	8		5		
Actuated Green, G (s)	14.7	64.2	25.4	25.4	49.5	49.5
Effective Green, g (s)	14.7	64.2	25.4	25.4	49.5	49.5
Actuated g/C Ratio	0.13	0.58	0.23	0.23	0.45	0.45
Clearance Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	239	943	818	365	732	1514
v/s Ratio Prot		0.14	c0.16		c0.26	0.26
v/s Ratio Perm	c0.08	0.04		0.05		
v/c Ratio	0.64	0.32	0.71	0.21	0.59	0.58
Uniform Delay, d1	45.1	11.7	38.9	34.2	22.6	22.5
Progression Factor	1.00	1.00	1.43	3.08	1.00	1.00
Incremental Delay, d2	5.5	0.2	2.2	0.2	3.4	1.6
Delay (s)	50.6	11.9	57.9	105.6	26.1	24.2
Level of Service	D	B	E	F	C	C
Approach Delay (s)	23.7		70.2			24.8
Approach LOS	C		E			C
<b>Intersection Summary</b>						
HCM 2000 Control Delay			38.3		HCM 2000 Level of Service	D
HCM 2000 Volume to Capacity ratio			0.63			
Actuated Cycle Length (s)			110.0		Sum of lost time (s)	20.4
Intersection Capacity Utilization			65.3%		ICU Level of Service	C
Analysis Period (min)			15			
c Critical Lane Group						

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Total 2027 PM  
PM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	428	74	13	10	60	193	18	106	13	261	183	228
Future Volume (vph)	428	74	13	10	60	193	18	106	13	261	183	228
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (m)	20.0		0.0	15.0		15.0	20.0		0.0	20.0		0.0
Storage Lanes	1		0	1		1	1		0	1		1
Taper Length (m)	40.0			10.0			40.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.978				0.850		0.984				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1706	1879	0	1659	1921	1601	1825	1857	0	1807	1902	1570
Flt Permitted	0.548			0.696			0.634			0.675		
Satd. Flow (perm)	984	1879	0	1216	1921	1601	1218	1857	0	1284	1902	1570
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		12				208		6				245
Link Speed (k/h)		50			50			60				60
Link Distance (m)		78.3			208.1			259.8				200.0
Travel Time (s)		5.6			15.0			15.6				12.0
Peak Hour Factor	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93
Heavy Vehicles (%)	4%	0%	0%	10%	0%	2%	0%	2%	0%	1%	1%	4%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Adj. Flow (vph)	460	80	14	11	65	208	19	114	14	281	197	245
Shared Lane Traffic (%)												
Lane Group Flow (vph)	460	94	0	11	65	208	19	128	0	281	197	245
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			3.7				3.7
Link Offset(m)		0.0			0.0			0.0				0.0
Crosswalk Width(m)		1.6			1.6			1.6				1.6
Two way Left Turn Lane												
Headway Factor	1.02	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	6.1	30.5		6.1	30.5	6.1	6.1	30.5		6.1	30.5	6.1
Trailing Detector (m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	6.1	1.8		6.1	1.8	6.1	6.1	1.8		6.1	1.8	6.1
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		28.7			28.7			28.7				28.7
Detector 2 Size(m)		1.8			1.8			1.8				1.8
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex				Cl+Ex
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0				0.0
Turn Type	pm+pt	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Total 2027 PM  
PM Peak Hour




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Protected Phases	7	4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Detector Phase	7	4		8	8	8	2	2		6	6	6
Switch Phase												
Minimum Initial (s)	5.0	8.0		8.0	8.0	8.0	20.0	20.0		20.0	20.0	20.0
Minimum Split (s)	9.5	36.0		36.0	36.0	36.0	32.0	32.0		32.0	32.0	32.0
Total Split (s)	28.0	64.0		36.0	36.0	36.0	46.0	46.0		46.0	46.0	46.0
Total Split (%)	25.5%	58.2%		32.7%	32.7%	32.7%	41.8%	41.8%		41.8%	41.8%	41.8%
Maximum Green (s)	25.0	57.8		29.8	29.8	29.8	39.7	39.7		39.7	39.7	39.7
Yellow Time (s)	3.0	3.3		3.3	3.3	3.3	4.2	4.2		4.2	4.2	4.2
All-Red Time (s)	0.0	2.9		2.9	2.9	2.9	2.1	2.1		2.1	2.1	2.1
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lead/Lag	Lead			Lag			Lag					
Lead-Lag Optimize?	Yes			Yes			Yes					
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	None		None	None	None	C-Max	C-Max		C-Max	C-Max	C-Max
Walk Time (s)		7.0		7.0	7.0	7.0	7.0	7.0		7.0	7.0	7.0
Flash Dont Walk (s)		22.0		22.0	22.0	22.0	18.0	18.0		18.0	18.0	18.0
Pedestrian Calls (#/hr)		0		0	0	0	0	0		0	0	0
Act Effct Green (s)	41.1	37.9		9.9	9.9	9.9	59.6	59.6		59.6	59.6	59.6
Actuated g/C Ratio	0.37	0.34		0.09	0.09	0.09	0.54	0.54		0.54	0.54	0.54
v/c Ratio	0.87	0.14		0.10	0.38	0.63	0.03	0.13		0.40	0.19	0.25
Control Delay	47.7	21.7		46.6	52.9	15.2	12.8	12.7		7.3	4.8	2.2
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	47.7	21.7		46.6	52.9	15.2	12.8	12.7		7.3	4.8	2.2
LOS	D	C		D	D	B	B	B		A	A	A
Approach Delay		43.2			25.0			12.7			4.9	
Approach LOS		D			C			B			A	

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 40.7 (37%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green  
 Natural Cycle: 80  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.87  
 Intersection Signal Delay: 21.4      Intersection LOS: C  
 Intersection Capacity Utilization 66.1%      ICU Level of Service C  
 Analysis Period (min) 15

Splits and Phases: 2: Whites Road South & Oklahoma Drive



Queues  
2: Whites Road South & Oklahoma Drive

Future Total 2027 PM  
PM Peak Hour

























Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	SBL	SBT	SBR
Lane Group Flow (vph)	460	94	11	65	208	19	128	281	197	245
v/c Ratio	0.87	0.14	0.10	0.38	0.63	0.03	0.13	0.40	0.19	0.25
Control Delay	47.7	21.7	46.6	52.9	15.2	12.8	12.7	7.3	4.8	2.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	47.7	21.7	46.6	52.9	15.2	12.8	12.7	7.3	4.8	2.2
Queue Length 50th (m)	84.7	12.1	2.2	13.5	0.0	1.8	12.0	15.8	10.1	2.9
Queue Length 95th (m)	#124.2	22.2	7.5	26.0	20.9	5.8	23.4	20.1	14.6	6.6
Internal Link Dist (m)		54.3		184.1			235.8		176.0	
Turn Bay Length (m)	20.0		15.0		15.0	20.0		20.0		
Base Capacity (vph)	531	993	329	520	585	660	1009	696	1031	963
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.87	0.09	0.03	0.13	0.36	0.03	0.13	0.40	0.19	0.25

Intersection Summary

# 95th percentile volume exceeds capacity, queue may be longer.  
Queue shown is maximum after two cycles.

HCM Signalized Intersection Capacity Analysis  
2: Whites Road South & Oklahoma Drive

Future Total 2027 PM  
PM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	428	74	13	10	60	193	18	106	13	261	183	228
Future Volume (vph)	428	74	13	10	60	193	18	106	13	261	183	228
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lane Util. Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.00	1.00	1.00
Frt	1.00	0.98		1.00	1.00	0.85	1.00	0.98		1.00	1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00	1.00	0.95	1.00		0.95	1.00	1.00
Satd. Flow (prot)	1706	1878		1659	1921	1601	1825	1857		1807	1902	1570
Flt Permitted	0.55	1.00		0.70	1.00	1.00	0.63	1.00		0.67	1.00	1.00
Satd. Flow (perm)	985	1878		1216	1921	1601	1218	1857		1284	1902	1570
Peak-hour factor, PHF	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93
Adj. Flow (vph)	460	80	14	11	65	208	19	114	14	281	197	245
RTOR Reduction (vph)	0	8	0	0	0	189	0	3	0	0	0	112
Lane Group Flow (vph)	460	86	0	11	65	19	19	125	0	281	197	133
Heavy Vehicles (%)	4%	0%	0%	10%	0%	2%	0%	2%	0%	1%	1%	4%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Turn Type	pm+pt	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm
Protected Phases	7	4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Actuated Green, G (s)	37.9	37.9		9.9	9.9	9.9	59.6	59.6		59.6	59.6	59.6
Effective Green, g (s)	37.9	37.9		9.9	9.9	9.9	59.6	59.6		59.6	59.6	59.6
Actuated g/C Ratio	0.34	0.34		0.09	0.09	0.09	0.54	0.54		0.54	0.54	0.54
Clearance Time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Lane Grp Cap (vph)	503	647		109	172	144	659	1006		695	1030	850
v/s Ratio Prot	c0.21	0.05			0.03			0.07			0.10	
v/s Ratio Perm	c0.11			0.01		0.01	0.02			c0.22		0.08
v/c Ratio	0.91	0.13		0.10	0.38	0.13	0.03	0.12		0.40	0.19	0.16
Uniform Delay, d1	32.6	24.8		46.0	47.1	46.1	11.7	12.4		14.8	12.9	12.6
Progression Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		0.37	0.33	0.88
Incremental Delay, d2	21.1	0.1		0.4	1.4	0.4	0.1	0.3		1.5	0.4	0.3
Delay (s)	53.8	24.9		46.4	48.5	46.5	11.8	12.6		7.0	4.6	11.4
Level of Service	D	C		D	D	D	B	B		A	A	B
Approach Delay (s)		48.9			47.0			12.5			7.8	
Approach LOS		D			D			B			A	
<b>Intersection Summary</b>												
HCM 2000 Control Delay			28.1	HCM 2000 Level of Service				C				
HCM 2000 Volume to Capacity ratio			0.62									
Actuated Cycle Length (s)			110.0	Sum of lost time (s)				15.5				
Intersection Capacity Utilization			66.1%	ICU Level of Service				C				
Analysis Period (min)			15									

c Critical Lane Group



Lanes, Volumes, Timings  
3: Granite Court/Oaklahoma Drive

Future Total 2027 PM  
PM Peak Hour



Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (vph)	5	484	257	50	31	3
Future Volume (vph)	5	484	257	50	31	3
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00
Frt			0.978		0.989	
Flt Protected					0.956	
Satd. Flow (prot)	0	1883	1842	0	1781	0
Flt Permitted					0.956	
Satd. Flow (perm)	0	1883	1842	0	1781	0
Link Speed (k/h)		50	50		48	
Link Distance (m)		466.2	78.3		125.8	
Travel Time (s)		33.6	5.6		9.4	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	5	526	279	54	34	3
Shared Lane Traffic (%)						
Lane Group Flow (vph)	0	531	333	0	37	0
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Left	Left	Right	Left	Right
Median Width(m)		3.7	3.7		3.7	
Link Offset(m)		0.0	0.0		0.0	
Crosswalk Width(m)		1.6	1.6		1.6	
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24			14	24	14
Sign Control		Free	Free		Stop	

Intersection Summary

Area Type:	Other
Control Type:	Unsignalized
Intersection Capacity Utilization	39.5%
Analysis Period (min)	15
	ICU Level of Service A

HCM Unsignalized Intersection Capacity Analysis  
 3: Granite Court/Oaklahoma Drive

Future Total 2027 PM  
 PM Peak Hour



Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		↶	↷		↘	↙
Traffic Volume (veh/h)	5	484	257	50	31	3
Future Volume (Veh/h)	5	484	257	50	31	3
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	5	526	279	54	34	3
Pedestrians						
Lane Width (m)						
Walking Speed (m/s)						
Percent Blockage						
Right turn flare (veh)						
Median type		None	None			
Median storage veh						
Upstream signal (m)			78			
pX, platoon unblocked	0.97				0.97	0.97
vC, conflicting volume	333				842	306
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	301				824	273
tC, single (s)	4.1				6.4	6.2
tC, 2 stage (s)						
tF (s)	2.2				3.5	3.3
p0 queue free %	100				90	100
cM capacity (veh/h)	1226				332	745
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total	531	333	37			
Volume Left	5	0	34			
Volume Right	0	54	3			
cSH	1226	1700	348			
Volume to Capacity	0.00	0.20	0.11			
Queue Length 95th (m)	0.1	0.0	2.7			
Control Delay (s)	0.1	0.0	16.6			
Lane LOS	A		C			
Approach Delay (s)	0.1	0.0	16.6			
Approach LOS			C			
Intersection Summary						
Average Delay			0.8			
Intersection Capacity Utilization			39.5%		ICU Level of Service	A
Analysis Period (min)			15			

---













**Network Totals**

---

Number of Intersections	3
Total Delay (hr)	32
Stops (#)	2590
Average Speed (km/hr)	21
Total Travel Time (hr)	52
Distance Traveled (km)	1124
Fuel Consumed (l)	269
Fuel Economy (km/l)	4.2
Unserviced Vehicles (#)	0
Vehicles in dilemma zone (#)	49
Performance Index	39.7

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Future Total 2032 AM  
AM Peak Hour

						
Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Volume (vph)	108	279	590	76	384	543
Future Volume (vph)	108	279	590	76	384	543
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Storage Length (m)	0.0	0.0		30.0	70.0	
Storage Lanes	1	1		1	1	
Taper Length (m)	2.5				30.0	
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt		0.850		0.850		
Flt Protected	0.950				0.950	0.993
Satd. Flow (prot)	1722	1570	3510	1601	1612	3371
Flt Permitted	0.950				0.950	0.993
Satd. Flow (perm)	1722	1570	3510	1601	1612	3371
Right Turn on Red		Yes		Yes		
Satd. Flow (RTOR)		79		61		
Link Speed (k/h)	60		60			60
Link Distance (m)	376.4		200.0			221.2
Travel Time (s)	22.6		12.0			13.3
Peak Hour Factor	0.84	0.84	0.84	0.84	0.84	0.84
Heavy Vehicles (%)	6%	4%	4%	2%	3%	3%
Adj. Flow (vph)	129	332	702	90	457	646
Shared Lane Traffic (%)					22%	
Lane Group Flow (vph)	129	332	702	90	356	747
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Right	Left	Right	Left	Left
Median Width(m)	3.7		3.7			3.7
Link Offset(m)	0.0		0.0			0.0
Crosswalk Width(m)	1.6		1.6			1.6
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24	14		14	24	
Number of Detectors	1	1	2	1	1	2
Detector Template	Left	Right	Thru	Right	Left	Thru
Leading Detector (m)	6.1	6.1	30.5	6.1	6.1	30.5
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)	6.1	6.1	1.8	6.1	6.1	1.8
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel						
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)			28.7			28.7
Detector 2 Size(m)			1.8			1.8
Detector 2 Type			Cl+Ex			Cl+Ex
Detector 2 Channel						
Detector 2 Extend (s)			0.0			0.0
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2

Lanes, Volumes, Timings  
 1: Whites Road South & Bayly Street

Future Total 2032 AM  
 AM Peak Hour




Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Permitted Phases	8	8		5		
Detector Phase	8	2	5	5	2	2
Switch Phase						
Minimum Initial (s)	5.0	20.0	20.0	20.0	20.0	20.0
Minimum Split (s)	32.0	27.0	39.0	39.0	27.0	27.0
Total Split (s)	35.2	28.6	46.2	46.2	28.6	28.6
Total Split (%)	32.0%	26.0%	42.0%	42.0%	26.0%	26.0%
Maximum Green (s)	28.8	21.6	39.2	39.2	21.6	21.6
Yellow Time (s)	4.2	4.4	4.4	4.4	4.4	4.4
All-Red Time (s)	2.2	2.6	2.6	2.6	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lead/Lag						
Lead-Lag Optimize?						
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Recall Mode	None	C-Max	None	None	C-Max	C-Max
Walk Time (s)	7.0	5.0	7.0	7.0	5.0	5.0
Flash Dont Walk (s)	18.0	5.0	25.0	25.0	5.0	5.0
Pedestrian Calls (#/hr)	0	0	0	0	0	0
Act Effect Green (s)	13.6	66.9	29.1	29.1	46.9	46.9
Actuated g/C Ratio	0.12	0.61	0.26	0.26	0.43	0.43
v/c Ratio	0.61	0.34	0.76	0.19	0.52	0.52
Control Delay	57.3	9.8	35.5	8.2	29.1	26.7
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.3	9.8	35.5	8.2	29.1	26.7
LOS	E	A	D	A	C	C
Approach Delay	23.1		32.4			27.5
Approach LOS	C		C			C

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 24.2 (22%), Referenced to phase 2:SBTL and 6:, Start of Green  
 Natural Cycle: 100  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.76  
 Intersection Signal Delay: 28.3  
 Intersection LOS: C  
 Intersection Capacity Utilization 57.1%  
 ICU Level of Service B  
 Analysis Period (min) 15

Splits and Phases: 1: Whites Road South & Bayly Street



Queues  
1: Whites Road South & Bayly Street
















Future Total 2032 AM  
AM Peak Hour



Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Group Flow (vph)	129	332	702	90	356	747
v/c Ratio	0.61	0.34	0.76	0.19	0.52	0.52
Control Delay	57.3	9.8	35.5	8.2	29.1	26.7
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.3	9.8	35.5	8.2	29.1	26.7
Queue Length 50th (m)	26.6	23.9	74.5	1.5	60.5	63.5
Queue Length 95th (m)	40.2	42.6	73.7	5.7	100.2	90.4
Internal Link Dist (m)	352.4		176.0			197.2
Turn Bay Length (m)				30.0	70.0	
Base Capacity (vph)	450	985	1250	609	688	1438
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.29	0.34	0.56	0.15	0.52	0.52
<b>Intersection Summary</b>						























HCM Signalized Intersection Capacity Analysis  
 1: Whites Road South & Bayly Street

Future Total 2032 AM  
 AM Peak Hour

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			  
Traffic Volume (vph)	108	279	590	76	384	543
Future Volume (vph)	108	279	590	76	384	543
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt	1.00	0.85	1.00	0.85	1.00	1.00
Flt Protected	0.95	1.00	1.00	1.00	0.95	0.99
Satd. Flow (prot)	1722	1570	3510	1601	1612	3372
Flt Permitted	0.95	1.00	1.00	1.00	0.95	0.99
Satd. Flow (perm)	1722	1570	3510	1601	1612	3372
Peak-hour factor, PHF	0.84	0.84	0.84	0.84	0.84	0.84
Adj. Flow (vph)	129	332	702	90	457	646
RTOR Reduction (vph)	0	36	0	45	0	0
Lane Group Flow (vph)	129	296	702	45	356	747
Heavy Vehicles (%)	6%	4%	4%	2%	3%	3%
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2
Permitted Phases	8	8		5		
Actuated Green, G (s)	13.6	60.5	29.1	29.1	46.9	46.9
Effective Green, g (s)	13.6	60.5	29.1	29.1	46.9	46.9
Actuated g/C Ratio	0.12	0.55	0.26	0.26	0.43	0.43
Clearance Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	212	863	928	423	687	1437
v/s Ratio Prot		0.15	c0.20		0.22	c0.22
v/s Ratio Perm	c0.07	0.04		0.03		
v/c Ratio	0.61	0.34	0.76	0.11	0.52	0.52
Uniform Delay, d1	45.7	13.7	37.2	30.6	23.2	23.3
Progression Factor	1.00	1.00	0.82	0.65	1.00	1.00
Incremental Delay, d2	4.9	0.2	3.3	0.1	2.8	1.3
Delay (s)	50.6	14.0	33.9	19.9	26.0	24.6
Level of Service	D	B	C	B	C	C
Approach Delay (s)	24.2		32.3			25.1
Approach LOS	C		C			C
<b>Intersection Summary</b>						
HCM 2000 Control Delay			27.3		HCM 2000 Level of Service	C
HCM 2000 Volume to Capacity ratio			0.61			
Actuated Cycle Length (s)			110.0		Sum of lost time (s)	20.4
Intersection Capacity Utilization			57.1%		ICU Level of Service	B
Analysis Period (min)			15			
c	Critical Lane Group					

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive


Future Total 2032 AM  
AM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	213	45	11	7	56	305	18	135	25	189	88	367
Future Volume (vph)	213	45	11	7	56	305	18	135	25	189	88	367
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (m)	20.0		0.0	15.0		15.0	20.0		0.0	20.0		0.0
Storage Lanes	1		0	1		1	1		0	1		1
Taper Length (m)	40.0			10.0			40.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.970				0.850		0.977				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1658	1816	0	1825	1921	1601	1722	1861	0	1755	1762	1601
Flt Permitted	0.712			0.711			0.687			0.633		
Satd. Flow (perm)	1243	1816	0	1366	1921	1601	1245	1861	0	1169	1762	1601
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		13				377		12				453
Link Speed (k/h)		50			50			60				60
Link Distance (m)		78.3			208.1			259.8				200.0
Travel Time (s)		5.6			15.0			15.6				12.0
Peak Hour Factor	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81
Heavy Vehicles (%)	7%	0%	13%	0%	0%	2%	6%	1%	0%	4%	9%	2%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Adj. Flow (vph)	263	56	14	9	69	377	22	167	31	233	109	453
Shared Lane Traffic (%)												
Lane Group Flow (vph)	263	70	0	9	69	377	22	198	0	233	109	453
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			3.7				3.7
Link Offset(m)		0.0			0.0			0.0				0.0
Crosswalk Width(m)		1.6			1.6			1.6				1.6
Two way Left Turn Lane												
Headway Factor	1.02	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	6.1	30.5		6.1	30.5	6.1	6.1	30.5		6.1	30.5	6.1
Trailing Detector (m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	6.1	1.8		6.1	1.8	6.1	6.1	1.8		6.1	1.8	6.1
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		28.7			28.7			28.7				28.7
Detector 2 Size(m)		1.8			1.8			1.8				1.8
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex				Cl+Ex
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0				0.0
Turn Type	Perm	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm



Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Total 2032 AM  
AM Peak Hour



Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Protected Phases		4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Detector Phase	4	4		8	8	8	2	2		6	6	6
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0	5.0	5.0	5.0		5.0	5.0	5.0
Minimum Split (s)	36.0	36.0		36.0	36.0	36.0	32.0	32.0		32.0	32.0	32.0
Total Split (s)	48.4	48.4		48.4	48.4	48.4	61.6	61.6		61.6	61.6	61.6
Total Split (%)	44.0%	44.0%		44.0%	44.0%	44.0%	56.0%	56.0%		56.0%	56.0%	56.0%
Maximum Green (s)	42.2	42.2		42.2	42.2	42.2	55.3	55.3		55.3	55.3	55.3
Yellow Time (s)	3.3	3.3		3.3	3.3	3.3	4.2	4.2		4.2	4.2	4.2
All-Red Time (s)	2.9	2.9		2.9	2.9	2.9	2.1	2.1		2.1	2.1	2.1
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lead/Lag												
Lead-Lag Optimize?												
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	None		None	None	None	C-Max	C-Max		C-Max	C-Max	C-Max
Walk Time (s)	7.0	7.0		7.0	7.0	7.0	7.0	7.0		7.0	7.0	7.0
Flash Dont Walk (s)	22.0	22.0		22.0	22.0	22.0	18.0	18.0		18.0	18.0	18.0
Pedestrian Calls (#/hr)	0	0		0	0	0	0	0		0	0	0
Act Effct Green (s)	29.0	29.0		29.0	29.0	29.0	68.5	68.5		68.5	68.5	68.5
Actuated g/C Ratio	0.26	0.26		0.26	0.26	0.26	0.62	0.62		0.62	0.62	0.62
v/c Ratio	0.80	0.14		0.03	0.14	0.54	0.03	0.17		0.32	0.10	0.39
Control Delay	55.1	23.3		25.4	28.6	5.7	10.8	10.1		18.1	16.6	8.5
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	55.1	23.3		25.4	28.6	5.7	10.8	10.1		18.1	16.6	8.5
LOS	E	C		C	C	A	B	B		B	B	A
Approach Delay		48.5			9.6			10.2			12.4	
Approach LOS		D			A			B			B	

Intersection Summary

Area Type:	Other
Cycle Length:	110
Actuated Cycle Length:	110
Offset:	83.6 (76%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
Natural Cycle:	70
Control Type:	Actuated-Coordinated
Maximum v/c Ratio:	0.80
Intersection Signal Delay:	18.1
Intersection LOS:	B
Intersection Capacity Utilization	54.9%
ICU Level of Service	A
Analysis Period (min)	15

Splits and Phases: 2: Whites Road South & Oklahoma Drive



Queues  
2: Whites Road South & Oklahoma Drive

Future Total 2032 AM  
AM Peak Hour

























Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	SBL	SBT	SBR
Lane Group Flow (vph)	263	70	9	69	377	22	198	233	109	453
v/c Ratio	0.80	0.14	0.03	0.14	0.54	0.03	0.17	0.32	0.10	0.39
Control Delay	55.1	23.3	25.4	28.6	5.7	10.8	10.1	18.1	16.6	8.5
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	55.1	23.3	25.4	28.6	5.7	10.8	10.1	18.1	16.6	8.5
Queue Length 50th (m)	52.8	9.3	1.4	11.3	0.0	1.7	15.5	12.1	5.7	2.0
Queue Length 95th (m)	62.8	15.6	4.2	17.2	11.0	5.4	28.9	48.2	26.3	59.8
Internal Link Dist (m)		54.3		184.1			235.8		176.0	
Turn Bay Length (m)	20.0		15.0		15.0	20.0		20.0		
Base Capacity (vph)	476	704	524	736	846	774	1162	727	1096	1167
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.55	0.10	0.02	0.09	0.45	0.03	0.17	0.32	0.10	0.39

Intersection Summary

HCM Signalized Intersection Capacity Analysis  
2: Whites Road South & Oklahoma Drive

Future Total 2032 AM  
AM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	213	45	11	7	56	305	18	135	25	189	88	367
Future Volume (vph)	213	45	11	7	56	305	18	135	25	189	88	367
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lane Util. Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.00	1.00	1.00
Frt	1.00	0.97		1.00	1.00	0.85	1.00	0.98		1.00	1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00	1.00	0.95	1.00		0.95	1.00	1.00
Satd. Flow (prot)	1658	1816		1825	1921	1601	1722	1860		1755	1762	1601
Flt Permitted	0.71	1.00		0.71	1.00	1.00	0.69	1.00		0.63	1.00	1.00
Satd. Flow (perm)	1243	1816		1367	1921	1601	1245	1860		1170	1762	1601
Peak-hour factor, PHF	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81
Adj. Flow (vph)	263	56	14	9	69	377	22	167	31	233	109	453
RTOR Reduction (vph)	0	10	0	0	0	278	0	5	0	0	0	171
Lane Group Flow (vph)	263	60	0	9	69	99	22	193	0	233	109	282
Heavy Vehicles (%)	7%	0%	13%	0%	0%	2%	6%	1%	0%	4%	9%	2%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Turn Type	Perm	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm
Protected Phases		4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Actuated Green, G (s)	29.0	29.0		29.0	29.0	29.0	68.5	68.5		68.5	68.5	68.5
Effective Green, g (s)	29.0	29.0		29.0	29.0	29.0	68.5	68.5		68.5	68.5	68.5
Actuated g/C Ratio	0.26	0.26		0.26	0.26	0.26	0.62	0.62		0.62	0.62	0.62
Clearance Time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Lane Grp Cap (vph)	327	478		360	506	422	775	1158		728	1097	996
v/s Ratio Prot		0.03			0.04			0.10			0.06	
v/s Ratio Perm	c0.21			0.01		0.06	0.02			c0.20		0.18
v/c Ratio	0.80	0.13		0.03	0.14	0.24	0.03	0.17		0.32	0.10	0.28
Uniform Delay, d1	37.8	30.9		30.0	30.9	31.8	8.0	8.7		9.8	8.3	9.5
Progression Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.43	1.60	6.02
Incremental Delay, d2	13.4	0.1		0.0	0.1	0.3	0.1	0.3		1.0	0.2	0.6
Delay (s)	51.2	31.0		30.0	31.1	32.1	8.0	9.0		15.1	13.5	57.9
Level of Service	D	C		C	C	C	A	A		B	B	E
Approach Delay (s)		47.0			31.9			8.9			39.3	
Approach LOS		D			C			A			D	
<b>Intersection Summary</b>												
HCM 2000 Control Delay			35.1				HCM 2000 Level of Service				D	
HCM 2000 Volume to Capacity ratio			0.46									
Actuated Cycle Length (s)			110.0				Sum of lost time (s)			12.5		
Intersection Capacity Utilization			54.9%				ICU Level of Service			A		
Analysis Period (min)			15									

c Critical Lane Group

Lanes, Volumes, Timings  
3: Granite Court/Oaklahoma Drive

Future Total 2032 AM  
AM Peak Hour



Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		↔	↔		↔	
Traffic Volume (vph)	2	219	423	18	50	5
Future Volume (vph)	2	219	423	18	50	5
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00
Frt			0.994		0.989	
Flt Protected					0.956	
Satd. Flow (prot)	0	1883	1872	0	1781	0
Flt Permitted					0.956	
Satd. Flow (perm)	0	1883	1872	0	1781	0
Link Speed (k/h)		50	50		48	
Link Distance (m)		466.2	78.3		125.8	
Travel Time (s)		33.6	5.6		9.4	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	2	238	460	20	54	5
Shared Lane Traffic (%)						
Lane Group Flow (vph)	0	240	480	0	59	0
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Left	Left	Right	Left	Right
Median Width(m)		3.7	3.7		3.7	
Link Offset(m)		0.0	0.0		0.0	
Crosswalk Width(m)		1.6	1.6		1.6	
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24			14	24	14
Sign Control		Free	Free		Stop	

Intersection Summary

Area Type:	Other
Control Type:	Unsignalized
Intersection Capacity Utilization	33.4%
Analysis Period (min)	15
	ICU Level of Service A

# HCM Unsignalized Intersection Capacity Analysis

## 3: Granite Court/Oaklahoma Drive

Future Total 2032 AM  
AM Peak Hour



Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (veh/h)	2	219	423	18	50	5
Future Volume (Veh/h)	2	219	423	18	50	5
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	2	238	460	20	54	5
<b>Pedestrians</b>						
Lane Width (m)						
Walking Speed (m/s)						
Percent Blockage						
Right turn flare (veh)						
Median type		None	None			
Median storage veh						
Upstream signal (m)	78					
pX, platoon unblocked	0.98				0.98	0.98
vC, conflicting volume	480				712	470
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	463				699	453
tC, single (s)	4.1				6.4	6.2
tC, 2 stage (s)						
tF (s)	2.2				3.5	3.3
p0 queue free %	100				86	99
cM capacity (veh/h)	1080				399	597
<b>Direction, Lane #</b>	<b>EB 1</b>	<b>WB 1</b>	<b>SB 1</b>			
Volume Total	240	480	59			
Volume Left	2	0	54			
Volume Right	0	20	5			
cSH	1080	1700	410			
Volume to Capacity	0.00	0.28	0.14			
Queue Length 95th (m)	0.0	0.0	3.8			
Control Delay (s)	0.1	0.0	15.2			
Lane LOS	A		C			
Approach Delay (s)	0.1	0.0	15.2			
Approach LOS			C			
<b>Intersection Summary</b>						
Average Delay			1.2			
Intersection Capacity Utilization			33.4%	ICU Level of Service	A	
Analysis Period (min)			15			

---













**Network Totals**

---

Number of Intersections	3
Total Delay (hr)	23
Stops (#)	2067
Average Speed (km/hr)	23
Total Travel Time (hr)	39
Distance Traveled (km)	901
Fuel Consumed (l)	207
Fuel Economy (km/l)	4.3
Unserviced Vehicles (#)	0
Vehicles in dilemma zone (#)	70
Performance Index	28.9







Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Future Total 2032 PM  
PM Peak Hour

						
Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Volume (vph)	148	338	574	196	735	547
Future Volume (vph)	148	338	574	196	735	547
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Storage Length (m)	0.0	0.0		30.0	70.0	
Storage Lanes	1	1		1	1	
Taper Length (m)	2.5				30.0	
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt		0.850		0.850		
Flt Protected	0.950				0.950	0.982
Satd. Flow (prot)	1789	1617	3544	1585	1628	3366
Flt Permitted	0.950				0.950	0.982
Satd. Flow (perm)	1789	1617	3544	1585	1628	3366
Right Turn on Red		Yes		Yes		
Satd. Flow (RTOR)		101		158		
Link Speed (k/h)	60		60			60
Link Distance (m)	376.4		200.0			221.2
Travel Time (s)	22.6		12.0			13.3
Peak Hour Factor	0.95	0.95	0.95	0.95	0.95	0.95
Heavy Vehicles (%)	2%	1%	3%	3%	2%	2%
Adj. Flow (vph)	156	356	604	206	774	576
Shared Lane Traffic (%)					43%	
Lane Group Flow (vph)	156	356	604	206	441	909
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Right	Left	Right	Left	Left
Median Width(m)	3.7		3.7			3.7
Link Offset(m)	0.0		0.0			0.0
Crosswalk Width(m)	1.6		1.6			1.6
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24	14		14	24	
Number of Detectors	1	1	2	1	1	2
Detector Template	Left	Right	Thru	Right	Left	Thru
Leading Detector (m)	6.1	6.1	30.5	6.1	6.1	30.5
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)	6.1	6.1	1.8	6.1	6.1	1.8
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel						
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)			28.7			28.7
Detector 2 Size(m)			1.8			1.8
Detector 2 Type			Cl+Ex			Cl+Ex
Detector 2 Channel						
Detector 2 Extend (s)			0.0			0.0
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street


Future Total 2032 PM  
PM Peak Hour

						
Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Permitted Phases	8	8		5		
Detector Phase	8	2	5	5	2	2
Switch Phase						
Minimum Initial (s)	8.0	20.0	20.0	20.0	20.0	20.0
Minimum Split (s)	32.0	27.0	39.0	39.0	27.0	27.0
Total Split (s)	35.2	30.8	44.0	44.0	30.8	30.8
Total Split (%)	32.0%	28.0%	40.0%	40.0%	28.0%	28.0%
Maximum Green (s)	28.8	23.8	37.0	37.0	23.8	23.8
Yellow Time (s)	4.2	4.4	4.4	4.4	4.4	4.4
All-Red Time (s)	2.2	2.6	2.6	2.6	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lead/Lag						
Lead-Lag Optimize?						
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Recall Mode	None	C-Max	None	None	C-Max	C-Max
Walk Time (s)	7.0	5.0	7.0	7.0	5.0	5.0
Flash Dont Walk (s)	18.0	5.0	25.0	25.0	5.0	5.0
Pedestrian Calls (#/hr)	0	0	0	0	0	0
Act Effct Green (s)	14.9	70.0	26.0	26.0	48.7	48.7
Actuated g/C Ratio	0.14	0.64	0.24	0.24	0.44	0.44
v/c Ratio	0.64	0.33	0.72	0.42	0.61	0.61
Control Delay	56.8	8.0	59.1	28.4	30.5	27.5
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	56.8	8.0	59.1	28.4	30.5	27.5
LOS	E	A	E	C	C	C
Approach Delay	22.9		51.3			28.5
Approach LOS	C		D			C

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 33 (30%), Referenced to phase 2:SBTL and 6:, Start of Green  
 Natural Cycle: 100  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.72  
 Intersection Signal Delay: 34.3  
 Intersection Capacity Utilization 66.2%  
 Analysis Period (min) 15  
 Intersection LOS: C  
 ICU Level of Service C

Splits and Phases: 1: Whites Road South & Bayly Street





Queues

Future Total 2032 PM

1: Whites Road South & Bayly Street

PM Peak Hour



Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Group Flow (vph)	156	356	604	206	441	909
v/c Ratio	0.64	0.33	0.72	0.42	0.61	0.61
Control Delay	56.8	8.0	59.1	28.4	30.5	27.5
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	56.8	8.0	59.1	28.4	30.5	27.5
Queue Length 50th (m)	32.1	21.7	70.0	19.2	77.3	79.6
Queue Length 95th (m)	50.6	44.6	m83.5	m31.5	#150.0	123.5
Internal Link Dist (m)	352.4		176.0			197.2
Turn Bay Length (m)				30.0	70.0	
Base Capacity (vph)	468	1066	1192	637	721	1490
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.33	0.33	0.51	0.32	0.61	0.61

Intersection Summary
















# 95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

m Volume for 95th percentile queue is metered by upstream signal.























HCM Signalized Intersection Capacity Analysis  
 1: Whites Road South & Bayly Street

Future Total 2032 PM  
 PM Peak Hour

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			  
Traffic Volume (vph)	148	338	574	196	735	547
Future Volume (vph)	148	338	574	196	735	547
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt	1.00	0.85	1.00	0.85	1.00	1.00
Flt Protected	0.95	1.00	1.00	1.00	0.95	0.98
Satd. Flow (prot)	1789	1617	3544	1585	1628	3366
Flt Permitted	0.95	1.00	1.00	1.00	0.95	0.98
Satd. Flow (perm)	1789	1617	3544	1585	1628	3366
Peak-hour factor, PHF	0.95	0.95	0.95	0.95	0.95	0.95
Adj. Flow (vph)	156	356	604	206	774	576
RTOR Reduction (vph)	0	43	0	121	0	0
Lane Group Flow (vph)	156	313	604	85	441	909
Heavy Vehicles (%)	2%	1%	3%	3%	2%	2%
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2
Permitted Phases	8	8		5		
Actuated Green, G (s)	14.9	63.6	26.0	26.0	48.7	48.7
Effective Green, g (s)	14.9	63.6	26.0	26.0	48.7	48.7
Actuated g/C Ratio	0.14	0.58	0.24	0.24	0.44	0.44
Clearance Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	242	934	837	374	720	1490
v/s Ratio Prot		0.15	c0.17		c0.27	0.27
v/s Ratio Perm	c0.09	0.05		0.05		
v/c Ratio	0.64	0.34	0.72	0.23	0.61	0.61
Uniform Delay, d1	45.0	12.1	38.7	33.9	23.4	23.4
Progression Factor	1.00	1.00	1.44	2.91	1.00	1.00
Incremental Delay, d2	5.8	0.2	2.4	0.2	3.9	1.9
Delay (s)	50.8	12.4	58.1	98.8	27.3	25.3
Level of Service	D	B	E	F	C	C
Approach Delay (s)	24.1		68.4			25.9
Approach LOS	C		E			C
<b>Intersection Summary</b>						
HCM 2000 Control Delay			38.5		HCM 2000 Level of Service	D
HCM 2000 Volume to Capacity ratio			0.65			
Actuated Cycle Length (s)			110.0		Sum of lost time (s)	20.4
Intersection Capacity Utilization			66.2%		ICU Level of Service	C
Analysis Period (min)			15			
c	Critical Lane Group					

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Total 2032 PM  
PM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	439	76	13	10	61	198	18	108	13	267	193	233
Future Volume (vph)	439	76	13	10	61	198	18	108	13	267	193	233
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (m)	20.0		0.0	15.0		15.0	20.0		0.0	20.0		0.0
Storage Lanes	1		0	1		1	1		0	1		1
Taper Length (m)	40.0			10.0			40.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.978				0.850		0.984				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1706	1879	0	1659	1921	1601	1825	1857	0	1807	1902	1570
Flt Permitted	0.550			0.695			0.624			0.674		
Satd. Flow (perm)	988	1879	0	1214	1921	1601	1199	1857	0	1282	1902	1570
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		12				213		6				251
Link Speed (k/h)		50			50			60				60
Link Distance (m)		78.3			208.1			259.8				200.0
Travel Time (s)		5.6			15.0			15.6				12.0
Peak Hour Factor	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93
Heavy Vehicles (%)	4%	0%	0%	10%	0%	2%	0%	2%	0%	1%	1%	4%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Adj. Flow (vph)	472	82	14	11	66	213	19	116	14	287	208	251
Shared Lane Traffic (%)												
Lane Group Flow (vph)	472	96	0	11	66	213	19	130	0	287	208	251
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			3.7				3.7
Link Offset(m)		0.0			0.0			0.0				0.0
Crosswalk Width(m)		1.6			1.6			1.6				1.6
Two way Left Turn Lane												
Headway Factor	1.02	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	6.1	30.5		6.1	30.5	6.1	6.1	30.5		6.1	30.5	6.1
Trailing Detector (m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	6.1	1.8		6.1	1.8	6.1	6.1	1.8		6.1	1.8	6.1
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		28.7			28.7			28.7				28.7
Detector 2 Size(m)		1.8			1.8			1.8				1.8
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex				Cl+Ex
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0				0.0
Turn Type	pm+pt	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm

Lanes, Volumes, Timings  
 2: Whites Road South & Oklahoma Drive


Future Total 2032 PM  
 PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Protected Phases	7	4			8			2			6	
Permitted Phases	4			8	8	8	2			6		6
Detector Phase	7	4		8	8	8	2	2		6	6	6
Switch Phase												
Minimum Initial (s)	5.0	8.0		8.0	8.0	8.0	20.0	20.0		20.0	20.0	20.0
Minimum Split (s)	9.5	36.0		36.0	36.0	36.0	32.0	32.0		32.0	32.0	32.0
Total Split (s)	28.4	64.4		36.0	36.0	36.0	45.6	45.6		45.6	45.6	45.6
Total Split (%)	25.8%	58.5%		32.7%	32.7%	32.7%	41.5%	41.5%		41.5%	41.5%	41.5%
Maximum Green (s)	25.4	58.2		29.8	29.8	29.8	39.3	39.3		39.3	39.3	39.3
Yellow Time (s)	3.0	3.3		3.3	3.3	3.3	4.2	4.2		4.2	4.2	4.2
All-Red Time (s)	0.0	2.9		2.9	2.9	2.9	2.1	2.1		2.1	2.1	2.1
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lead/Lag	Lead			Lag	Lag	Lag						
Lead-Lag Optimize?	Yes			Yes	Yes	Yes						
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	None		None	None	None	C-Max	C-Max		C-Max	C-Max	C-Max
Walk Time (s)		7.0		7.0	7.0	7.0	7.0	7.0		7.0	7.0	7.0
Flash Dont Walk (s)		22.0		22.0	22.0	22.0	18.0	18.0		18.0	18.0	18.0
Pedestrian Calls (#/hr)		0		0	0	0	0	0		0	0	0
Act Effct Green (s)	41.7	38.5		10.1	10.1	10.1	59.0	59.0		59.0	59.0	59.0
Actuated g/C Ratio	0.38	0.35		0.09	0.09	0.09	0.54	0.54		0.54	0.54	0.54
v/c Ratio	0.87	0.14		0.10	0.38	0.63	0.03	0.13		0.42	0.20	0.26
Control Delay	47.9	21.3		46.0	52.3	14.9	13.3	13.1		7.1	4.7	2.1
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	47.9	21.3		46.0	52.3	14.9	13.3	13.1		7.1	4.7	2.1
LOS	D	C		D	D	B	B	B		A	A	A
Approach Delay		43.4			24.6			13.1			4.8	
Approach LOS		D			C			B			A	

Intersection Summary

Area Type:	Other
Cycle Length:	110
Actuated Cycle Length:	110
Offset:	40.7 (37%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
Natural Cycle:	80
Control Type:	Actuated-Coordinated
Maximum v/c Ratio:	0.87
Intersection Signal Delay:	21.3
Intersection LOS:	C
Intersection Capacity Utilization:	80.0%
ICU Level of Service:	D
Analysis Period (min):	15

Splits and Phases: 2: Whites Road South & Oklahoma Drive



Queues  
2: Whites Road South & Oklahoma Drive

Future Total 2032 PM  
PM Peak Hour



Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	SBL	SBT	SBR
Lane Group Flow (vph)	472	96	11	66	213	19	130	287	208	251
v/c Ratio	0.87	0.14	0.10	0.38	0.63	0.03	0.13	0.42	0.20	0.26
Control Delay	47.9	21.3	46.0	52.3	14.9	13.3	13.1	7.1	4.7	2.1
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	47.9	21.3	46.0	52.3	14.9	13.3	13.1	7.1	4.7	2.1
Queue Length 50th (m)	87.2	12.3	2.2	13.7	0.0	1.8	12.4	14.5	10.6	3.1
Queue Length 95th (m)	#123.8	22.0	7.4	25.9	20.6	5.9	24.4	20.6	15.4	6.7
Internal Link Dist (m)		54.3		184.1			235.8		176.0	
Turn Bay Length (m)	20.0		15.0		15.0	20.0		20.0		
Base Capacity (vph)	540	999	328	520	589	642	999	688	1020	958
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.87	0.10	0.03	0.13	0.36	0.03	0.13	0.42	0.20	0.26























Intersection Summary

# 95th percentile volume exceeds capacity, queue may be longer.  
Queue shown is maximum after two cycles.

# HCM Signalized Intersection Capacity Analysis

## 2: Whites Road South & Oklahoma Drive

Future Total 2032 PM  
PM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	439	76	13	10	61	198	18	108	13	267	193	233
Future Volume (vph)	439	76	13	10	61	198	18	108	13	267	193	233
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lane Util. Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.00	1.00	1.00
Frt	1.00	0.98		1.00	1.00	0.85	1.00	0.98		1.00	1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00	1.00	0.95	1.00		0.95	1.00	1.00
Satd. Flow (prot)	1706	1879		1659	1921	1601	1825	1857		1807	1902	1570
Flt Permitted	0.55	1.00		0.69	1.00	1.00	0.62	1.00		0.67	1.00	1.00
Satd. Flow (perm)	988	1879		1214	1921	1601	1198	1857		1282	1902	1570
Peak-hour factor, PHF	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93
Adj. Flow (vph)	472	82	14	11	66	213	19	116	14	287	208	251
RTOR Reduction (vph)	0	8	0	0	0	193	0	3	0	0	0	116
Lane Group Flow (vph)	472	88	0	11	66	20	19	127	0	287	208	135
Heavy Vehicles (%)	4%	0%	0%	10%	0%	2%	0%	2%	0%	1%	1%	4%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Turn Type	pm+pt	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm
Protected Phases	7	4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Actuated Green, G (s)	38.5	38.5		10.1	10.1	10.1	59.0	59.0		59.0	59.0	59.0
Effective Green, g (s)	38.5	38.5		10.1	10.1	10.1	59.0	59.0		59.0	59.0	59.0
Actuated g/C Ratio	0.35	0.35		0.09	0.09	0.09	0.54	0.54		0.54	0.54	0.54
Clearance Time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Lane Grp Cap (vph)	511	657		111	176	147	642	996		687	1020	842
v/s Ratio Prot	c0.21	0.05			0.03			0.07			0.11	
v/s Ratio Perm	c0.11			0.01		0.01	0.02			c0.22		0.09
v/c Ratio	0.92	0.13		0.10	0.38	0.13	0.03	0.13		0.42	0.20	0.16
Uniform Delay, d1	32.4	24.4		45.8	47.0	45.9	12.0	12.7		15.2	13.3	12.9
Progression Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		0.34	0.31	0.81
Incremental Delay, d2	22.5	0.1		0.4	1.3	0.4	0.1	0.3		1.6	0.4	0.3
Delay (s)	54.9	24.5		46.2	48.3	46.3	12.1	13.0		6.7	4.5	10.8
Level of Service	D	C		D	D	D	B	B		A	A	B
Approach Delay (s)		49.8			46.8			12.8			7.5	
Approach LOS		D			D			B			A	
<b>Intersection Summary</b>												
HCM 2000 Control Delay			28.1				HCM 2000 Level of Service				C	
HCM 2000 Volume to Capacity ratio			0.63									
Actuated Cycle Length (s)			110.0				Sum of lost time (s)				15.5	
Intersection Capacity Utilization			80.0%				ICU Level of Service				D	
Analysis Period (min)			15									

c Critical Lane Group

Lanes, Volumes, Timings  
3: Granite Court/Oaklahoma Drive

Future Total 2032 PM  
PM Peak Hour



Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (vph)	5	497	263	50	31	3
Future Volume (vph)	5	497	263	50	31	3
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00
Frt			0.979		0.989	
Flt Protected					0.956	
Satd. Flow (prot)	0	1883	1844	0	1781	0
Flt Permitted					0.956	
Satd. Flow (perm)	0	1883	1844	0	1781	0
Link Speed (k/h)		50	50		48	
Link Distance (m)		466.2	78.3		125.8	
Travel Time (s)		33.6	5.6		9.4	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	5	540	286	54	34	3
Shared Lane Traffic (%)						
Lane Group Flow (vph)	0	545	340	0	37	0
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Left	Left	Right	Left	Right
Median Width(m)		3.7	3.7		3.7	
Link Offset(m)		0.0	0.0		0.0	
Crosswalk Width(m)		1.6	1.6		1.6	
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24			14	24	14
Sign Control		Free	Free		Stop	

Intersection Summary

Area Type:	Other
Control Type:	Unsignalized
Intersection Capacity Utilization	40.1%
Analysis Period (min)	15
	ICU Level of Service A

HCM Unsignalized Intersection Capacity Analysis  
 3: Granite Court/Oaklahoma Drive

Future Total 2032 PM  
 PM Peak Hour



Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		↩	↩		↩	
Traffic Volume (veh/h)	5	497	263	50	31	3
Future Volume (Veh/h)	5	497	263	50	31	3
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	5	540	286	54	34	3
Pedestrians						
Lane Width (m)						
Walking Speed (m/s)						
Percent Blockage						
Right turn flare (veh)						
Median type		None	None			
Median storage veh						
Upstream signal (m)			78			
pX, platoon unblocked	0.97				0.97	0.97
vC, conflicting volume	340				863	313
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	307				845	279
tC, single (s)	4.1				6.4	6.2
tC, 2 stage (s)						
tF (s)	2.2				3.5	3.3
p0 queue free %	100				89	100
cM capacity (veh/h)	1219				323	739
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total	545	340	37			
Volume Left	5	0	34			
Volume Right	0	54	3			
cSH	1219	1700	338			
Volume to Capacity	0.00	0.20	0.11			
Queue Length 95th (m)	0.1	0.0	2.8			
Control Delay (s)	0.1	0.0	17.0			
Lane LOS	A		C			
Approach Delay (s)	0.1	0.0	17.0			
Approach LOS			C			
Intersection Summary						
Average Delay			0.8			
Intersection Capacity Utilization			40.1%		ICU Level of Service	A
Analysis Period (min)			15			



---













**Network Totals**

---

Number of Intersections	3
Total Delay (hr)	34
Stops (#)	2681
Average Speed (km/hr)	21
Total Travel Time (hr)	54
Distance Traveled (km)	1155
Fuel Consumed (l)	279
Fuel Economy (km/l)	4.1
Unserved Vehicles (#)	0
Vehicles in dilemma zone (#)	53
Performance Index	41.5

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Future Total 2037 AM  
AM Peak Hour

						
Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Volume (vph)	111	286	604	77	393	556
Future Volume (vph)	111	286	604	77	393	556
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Storage Length (m)	0.0	0.0		30.0	70.0	
Storage Lanes	1	1		1	1	
Taper Length (m)	2.5				30.0	
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt		0.850		0.850		
Flt Protected	0.950				0.950	0.993
Satd. Flow (prot)	1722	1570	3510	1601	1612	3371
Flt Permitted	0.950				0.950	0.993
Satd. Flow (perm)	1722	1570	3510	1601	1612	3371
Right Turn on Red		Yes		Yes		
Satd. Flow (RTOR)		74		61		
Link Speed (k/h)	60		60			60
Link Distance (m)	376.4		200.0			221.2
Travel Time (s)	22.6		12.0			13.3
Peak Hour Factor	0.84	0.84	0.84	0.84	0.84	0.84
Heavy Vehicles (%)	6%	4%	4%	2%	3%	3%
Adj. Flow (vph)	132	340	719	92	468	662
Shared Lane Traffic (%)					22%	
Lane Group Flow (vph)	132	340	719	92	365	765
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Right	Left	Right	Left	Left
Median Width(m)	3.7		3.7			3.7
Link Offset(m)	0.0		0.0			0.0
Crosswalk Width(m)	1.6		1.6			1.6
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24	14		14	24	
Number of Detectors	1	1	2	1	1	2
Detector Template	Left	Right	Thru	Right	Left	Thru
Leading Detector (m)	6.1	6.1	30.5	6.1	6.1	30.5
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)	6.1	6.1	1.8	6.1	6.1	1.8
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel						
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)			28.7			28.7
Detector 2 Size(m)			1.8			1.8
Detector 2 Type			Cl+Ex			Cl+Ex
Detector 2 Channel						
Detector 2 Extend (s)			0.0			0.0
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street


Future Total 2037 AM  
AM Peak Hour

Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Permitted Phases	8	8		5		
Detector Phase	8	2	5	5	2	2
Switch Phase						
Minimum Initial (s)	5.0	20.0	20.0	20.0	20.0	20.0
Minimum Split (s)	32.0	27.0	39.0	39.0	27.0	27.0
Total Split (s)	35.2	28.6	46.2	46.2	28.6	28.6
Total Split (%)	32.0%	26.0%	42.0%	42.0%	26.0%	26.0%
Maximum Green (s)	28.8	21.6	39.2	39.2	21.6	21.6
Yellow Time (s)	4.2	4.4	4.4	4.4	4.4	4.4
All-Red Time (s)	2.2	2.6	2.6	2.6	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lead/Lag						
Lead-Lag Optimize?						
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Recall Mode	None	C-Max	None	None	C-Max	C-Max
Walk Time (s)	7.0	5.0	7.0	7.0	5.0	5.0
Flash Dont Walk (s)	18.0	5.0	25.0	25.0	5.0	5.0
Pedestrian Calls (#/hr)	0	0	0	0	0	0
Act Effct Green (s)	13.8	66.4	29.6	29.6	46.2	46.2
Actuated g/C Ratio	0.13	0.60	0.27	0.27	0.42	0.42
v/c Ratio	0.61	0.35	0.76	0.19	0.54	0.54
Control Delay	57.2	10.4	35.4	8.4	30.3	27.7
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.2	10.4	35.4	8.4	30.3	27.7
LOS	E	B	D	A	C	C
Approach Delay	23.5		32.3			28.5
Approach LOS	C		C			C

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 24.2 (22%), Referenced to phase 2:SBTL and 6:, Start of Green  
 Natural Cycle: 100  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.76  
 Intersection Signal Delay: 28.8  
 Intersection Capacity Utilization 57.7%  
 Analysis Period (min) 15  
 Intersection LOS: C  
 ICU Level of Service B

Splits and Phases: 1: Whites Road South & Bayly Street



Queues

Future Total 2037 AM

1: Whites Road South & Bayly Street

AM Peak Hour


















Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Group Flow (vph)	132	340	719	92	365	765
v/c Ratio	0.61	0.35	0.76	0.19	0.54	0.54
Control Delay	57.2	10.4	35.4	8.4	30.3	27.7
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	57.2	10.4	35.4	8.4	30.3	27.7
Queue Length 50th (m)	27.2	25.9	76.2	1.7	63.5	66.4
Queue Length 95th (m)	41.0	45.3	75.6	6.1	104.1	94.2
Internal Link Dist (m)	352.4		176.0			197.2
Turn Bay Length (m)				30.0	70.0	
Base Capacity (vph)	450	976	1250	609	676	1415
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.29	0.35	0.58	0.15	0.54	0.54

Intersection Summary























HCM Signalized Intersection Capacity Analysis  
 1: Whites Road South & Bayly Street

Future Total 2037 AM  
 AM Peak Hour

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			  
Traffic Volume (vph)	111	286	604	77	393	556
Future Volume (vph)	111	286	604	77	393	556
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt	1.00	0.85	1.00	0.85	1.00	1.00
Flt Protected	0.95	1.00	1.00	1.00	0.95	0.99
Satd. Flow (prot)	1722	1570	3510	1601	1612	3372
Flt Permitted	0.95	1.00	1.00	1.00	0.95	0.99
Satd. Flow (perm)	1722	1570	3510	1601	1612	3372
Peak-hour factor, PHF	0.84	0.84	0.84	0.84	0.84	0.84
Adj. Flow (vph)	132	340	719	92	468	662
RTOR Reduction (vph)	0	34	0	45	0	0
Lane Group Flow (vph)	132	306	719	47	365	765
Heavy Vehicles (%)	6%	4%	4%	2%	3%	3%
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2
Permitted Phases	8	8		5		
Actuated Green, G (s)	13.8	60.0	29.6	29.6	46.2	46.2
Effective Green, g (s)	13.8	60.0	29.6	29.6	46.2	46.2
Actuated g/C Ratio	0.13	0.55	0.27	0.27	0.42	0.42
Clearance Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	216	856	944	430	677	1416
v/s Ratio Prot		0.15	c0.20		0.23	c0.23
v/s Ratio Perm	c0.08	0.04		0.03		
v/c Ratio	0.61	0.36	0.76	0.11	0.54	0.54
Uniform Delay, d1	45.6	14.1	37.0	30.3	23.9	23.9
Progression Factor	1.00	1.00	0.83	0.65	1.00	1.00
Incremental Delay, d2	5.0	0.3	3.4	0.1	3.1	1.5
Delay (s)	50.6	14.4	33.9	19.9	27.0	25.4
Level of Service	D	B	C	B	C	C
Approach Delay (s)	24.5		32.3			25.9
Approach LOS	C		C			C
<b>Intersection Summary</b>						
HCM 2000 Control Delay			27.8		HCM 2000 Level of Service	C
HCM 2000 Volume to Capacity ratio			0.62			
Actuated Cycle Length (s)			110.0		Sum of lost time (s)	20.4
Intersection Capacity Utilization			57.7%		ICU Level of Service	B
Analysis Period (min)			15			
c	Critical Lane Group					

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Total 2037 AM  
AM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	217	46	11	7	57	312	18	138	26	194	90	375
Future Volume (vph)	217	46	11	7	57	312	18	138	26	194	90	375
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (m)	20.0		0.0	15.0		15.0	20.0		0.0	20.0		0.0
Storage Lanes	1		0	1		1	1		0	1		1
Taper Length (m)	40.0			10.0			40.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.970				0.850		0.976				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1658	1817	0	1825	1921	1601	1722	1859	0	1755	1762	1601
Flt Permitted	0.711			0.711			0.685			0.631		
Satd. Flow (perm)	1241	1817	0	1366	1921	1601	1241	1859	0	1166	1762	1601
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		13				385		12				463
Link Speed (k/h)		50			50			60				60
Link Distance (m)		78.3			208.1			259.8				200.0
Travel Time (s)		5.6			15.0			15.6				12.0
Peak Hour Factor	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81
Heavy Vehicles (%)	7%	0%	13%	0%	0%	2%	6%	1%	0%	4%	9%	2%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Adj. Flow (vph)	268	57	14	9	70	385	22	170	32	240	111	463
Shared Lane Traffic (%)												
Lane Group Flow (vph)	268	71	0	9	70	385	22	202	0	240	111	463
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			3.7				3.7
Link Offset(m)		0.0			0.0			0.0				0.0
Crosswalk Width(m)		1.6			1.6			1.6				1.6
Two way Left Turn Lane												
Headway Factor	1.02	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	6.1	30.5		6.1	30.5	6.1	6.1	30.5		6.1	30.5	6.1
Trailing Detector (m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	6.1	1.8		6.1	1.8	6.1	6.1	1.8		6.1	1.8	6.1
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		28.7			28.7			28.7				28.7
Detector 2 Size(m)		1.8			1.8			1.8				1.8
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex				Cl+Ex
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0				0.0
Turn Type	Perm	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Total 2037 AM  
AM Peak Hour




Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Protected Phases		4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Detector Phase	4	4		8	8	8	2	2		6	6	6
Switch Phase												
Minimum Initial (s)	5.0	5.0		5.0	5.0	5.0	5.0	5.0		5.0	5.0	5.0
Minimum Split (s)	36.0	36.0		36.0	36.0	36.0	32.0	32.0		32.0	32.0	32.0
Total Split (s)	48.4	48.4		48.4	48.4	48.4	61.6	61.6		61.6	61.6	61.6
Total Split (%)	44.0%	44.0%		44.0%	44.0%	44.0%	56.0%	56.0%		56.0%	56.0%	56.0%
Maximum Green (s)	42.2	42.2		42.2	42.2	42.2	55.3	55.3		55.3	55.3	55.3
Yellow Time (s)	3.3	3.3		3.3	3.3	3.3	4.2	4.2		4.2	4.2	4.2
All-Red Time (s)	2.9	2.9		2.9	2.9	2.9	2.1	2.1		2.1	2.1	2.1
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lead/Lag												
Lead-Lag Optimize?												
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	None		None	None	None	C-Max	C-Max		C-Max	C-Max	C-Max
Walk Time (s)	7.0	7.0		7.0	7.0	7.0	7.0	7.0		7.0	7.0	7.0
Flash Dont Walk (s)	22.0	22.0		22.0	22.0	22.0	18.0	18.0		18.0	18.0	18.0
Pedestrian Calls (#/hr)	0	0		0	0	0	0	0		0	0	0
Act Effct Green (s)	29.5	29.5		29.5	29.5	29.5	68.0	68.0		68.0	68.0	68.0
Actuated g/C Ratio	0.27	0.27		0.27	0.27	0.27	0.62	0.62		0.62	0.62	0.62
v/c Ratio	0.81	0.14		0.02	0.14	0.54	0.03	0.18		0.33	0.10	0.40
Control Delay	55.0	23.1		25.1	28.3	5.7	11.0	10.4		19.5	17.7	9.3
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	55.0	23.1		25.1	28.3	5.7	11.0	10.4		19.5	17.7	9.3
LOS	D	C		C	C	A	B	B		B	B	A
Approach Delay		48.3			9.5			10.4			13.4	
Approach LOS		D			A			B			B	

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 83.6 (76%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green  
 Natural Cycle: 70  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.81  
 Intersection Signal Delay: 18.5  
 Intersection LOS: B  
 Intersection Capacity Utilization 55.8%  
 ICU Level of Service B  
 Analysis Period (min) 15

Splits and Phases: 2: Whites Road South & Oklahoma Drive



Queues  
2: Whites Road South & Oklahoma Drive

Future Total 2037 AM  
AM Peak Hour

























Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	SBL	SBT	SBR
Lane Group Flow (vph)	268	71	9	70	385	22	202	240	111	463
v/c Ratio	0.81	0.14	0.02	0.14	0.54	0.03	0.18	0.33	0.10	0.40
Control Delay	55.0	23.1	25.1	28.3	5.7	11.0	10.4	19.5	17.7	9.3
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	55.0	23.1	25.1	28.3	5.7	11.0	10.4	19.5	17.7	9.3
Queue Length 50th (m)	53.7	9.4	1.4	11.4	0.0	1.7	16.1	14.6	6.8	2.1
Queue Length 95th (m)	63.6	15.6	4.1	17.4	10.9	5.5	29.9	51.3	27.6	61.8
Internal Link Dist (m)		54.3		184.1			235.8		176.0	
Turn Bay Length (m)	20.0		15.0		15.0	20.0		20.0		
Base Capacity (vph)	476	705	524	736	851	767	1153	720	1088	1166
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.56	0.10	0.02	0.10	0.45	0.03	0.18	0.33	0.10	0.40

Intersection Summary



HCM Signalized Intersection Capacity Analysis  
2: Whites Road South & Oklahoma Drive

Future Total 2037 AM  
AM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	217	46	11	7	57	312	18	138	26	194	90	375
Future Volume (vph)	217	46	11	7	57	312	18	138	26	194	90	375
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lane Util. Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.00	1.00	1.00
Frt	1.00	0.97		1.00	1.00	0.85	1.00	0.98		1.00	1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00	1.00	0.95	1.00		0.95	1.00	1.00
Satd. Flow (prot)	1658	1818		1825	1921	1601	1722	1860		1755	1762	1601
Flt Permitted	0.71	1.00		0.71	1.00	1.00	0.69	1.00		0.63	1.00	1.00
Satd. Flow (perm)	1242	1818		1365	1921	1601	1242	1860		1166	1762	1601
Peak-hour factor, PHF	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81	0.81
Adj. Flow (vph)	268	57	14	9	70	385	22	170	32	240	111	463
RTOR Reduction (vph)	0	10	0	0	0	282	0	5	0	0	0	177
Lane Group Flow (vph)	268	61	0	9	70	103	22	197	0	240	111	286
Heavy Vehicles (%)	7%	0%	13%	0%	0%	2%	6%	1%	0%	4%	9%	2%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Turn Type	Perm	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm
Protected Phases		4			8			2			6	
Permitted Phases	4			8		8	2			6		6
Actuated Green, G (s)	29.5	29.5		29.5	29.5	29.5	68.0	68.0		68.0	68.0	68.0
Effective Green, g (s)	29.5	29.5		29.5	29.5	29.5	68.0	68.0		68.0	68.0	68.0
Actuated g/C Ratio	0.27	0.27		0.27	0.27	0.27	0.62	0.62		0.62	0.62	0.62
Clearance Time (s)	6.2	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Lane Grp Cap (vph)	333	487		366	515	429	767	1149		720	1089	989
v/s Ratio Prot		0.03			0.04			0.11			0.06	
v/s Ratio Perm	c0.22			0.01		0.06	0.02			c0.21		0.18
v/c Ratio	0.80	0.13		0.02	0.14	0.24	0.03	0.17		0.33	0.10	0.29
Uniform Delay, d1	37.6	30.5		29.7	30.6	31.5	8.2	9.0		10.1	8.6	9.8
Progression Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.50	1.67	6.47
Incremental Delay, d2	13.2	0.1		0.0	0.1	0.3	0.1	0.3		1.1	0.2	0.7
Delay (s)	50.7	30.6		29.7	30.7	31.8	8.2	9.3		16.3	14.5	63.9
Level of Service	D	C		C	C	C	A	A		B	B	E
Approach Delay (s)		46.5			31.6			9.2			43.1	
Approach LOS		D			C			A			D	

Intersection Summary		
HCM 2000 Control Delay	36.7	HCM 2000 Level of Service
HCM 2000 Volume to Capacity ratio	0.48	D
Actuated Cycle Length (s)	110.0	Sum of lost time (s)
Intersection Capacity Utilization	55.8%	12.5
Analysis Period (min)	15	ICU Level of Service
		B

c Critical Lane Group

Lanes, Volumes, Timings  
3: Granite Court/Oaklahoma Drive

Future Total 2037 AM  
AM Peak Hour



Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		↶	↶		↷	
Traffic Volume (vph)	2	225	434	18	50	5
Future Volume (vph)	2	225	434	18	50	5
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00
Frt			0.995		0.989	
Flt Protected					0.956	
Satd. Flow (prot)	0	1883	1874	0	1781	0
Flt Permitted					0.956	
Satd. Flow (perm)	0	1883	1874	0	1781	0
Link Speed (k/h)		50	50		48	
Link Distance (m)		466.2	78.3		125.8	
Travel Time (s)		33.6	5.6		9.4	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	2	245	472	20	54	5
Shared Lane Traffic (%)						
Lane Group Flow (vph)	0	247	492	0	59	0
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Left	Left	Right	Left	Right
Median Width(m)		3.7	3.7		3.7	
Link Offset(m)		0.0	0.0		0.0	
Crosswalk Width(m)		1.6	1.6		1.6	
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24			14	24	14
Sign Control		Free	Free		Stop	


Intersection Summary

Area Type:	Other
Control Type:	Unsignalized
Intersection Capacity Utilization	33.9%
Analysis Period (min)	15
	ICU Level of Service A

# HCM Unsignalized Intersection Capacity Analysis

## 3: Granite Court/Oaklahoma Drive

Future Total 2037 AM  
AM Peak Hour



Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (veh/h)	2	225	434	18	50	5
Future Volume (Veh/h)	2	225	434	18	50	5
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	2	245	472	20	54	5
<b>Pedestrians</b>						
Lane Width (m)						
Walking Speed (m/s)						
Percent Blockage						
Right turn flare (veh)						
Median type		None	None			
Median storage (veh)						
Upstream signal (m)	78					
pX, platoon unblocked	0.98				0.98	0.98
vC, conflicting volume	492				731	482
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	475				718	465
tC, single (s)	4.1				6.4	6.2
tC, 2 stage (s)						
tF (s)	2.2				3.5	3.3
p0 queue free %	100				86	99
cM capacity (veh/h)	1069				388	588
<b>Direction, Lane #</b>	<b>EB 1</b>	<b>WB 1</b>	<b>SB 1</b>			
Volume Total	247	492	59			
Volume Left	2	0	54			
Volume Right	0	20	5			
cSH	1069	1700	400			
Volume to Capacity	0.00	0.29	0.15			
Queue Length 95th (m)	0.0	0.0	3.9			
Control Delay (s)	0.1	0.0	15.6			
Lane LOS	A		C			
Approach Delay (s)	0.1	0.0	15.6			
Approach LOS			C			
<b>Intersection Summary</b>						
Average Delay			1.2			
Intersection Capacity Utilization			33.9%	ICU Level of Service	A	
Analysis Period (min)			15			

---













**Network Totals**

---

Number of Intersections	3
Total Delay (hr)	24
Stops (#)	2144
Average Speed (km/hr)	23
Total Travel Time (hr)	40
Distance Traveled (km)	923
Fuel Consumed (l)	215
Fuel Economy (km/l)	4.3
Unserved Vehicles (#)	0
Vehicles in dilemma zone (#)	71
Performance Index	30.1

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street

Future Total 2037 PM  
PM Peak Hour

						
Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations						
Traffic Volume (vph)	151	346	587	201	753	560
Future Volume (vph)	151	346	587	201	753	560
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Storage Length (m)	0.0	0.0		30.0	70.0	
Storage Lanes	1	1		1	1	
Taper Length (m)	2.5				30.0	
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt		0.850		0.850		
Flt Protected	0.950				0.950	0.982
Satd. Flow (prot)	1789	1617	3544	1585	1628	3366
Flt Permitted	0.950				0.950	0.982
Satd. Flow (perm)	1789	1617	3544	1585	1628	3366
Right Turn on Red		Yes		Yes		
Satd. Flow (RTOR)		95		159		
Link Speed (k/h)	60		60			60
Link Distance (m)	376.4		200.0			221.2
Travel Time (s)	22.6		12.0			13.3
Peak Hour Factor	0.95	0.95	0.95	0.95	0.95	0.95
Heavy Vehicles (%)	2%	1%	3%	3%	2%	2%
Adj. Flow (vph)	159	364	618	212	793	589
Shared Lane Traffic (%)					43%	
Lane Group Flow (vph)	159	364	618	212	452	930
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Right	Left	Right	Left	Left
Median Width(m)	3.7		3.7			3.7
Link Offset(m)	0.0		0.0			0.0
Crosswalk Width(m)	1.6		1.6			1.6
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24	14		14	24	
Number of Detectors	1	1	2	1	1	2
Detector Template	Left	Right	Thru	Right	Left	Thru
Leading Detector (m)	6.1	6.1	30.5	6.1	6.1	30.5
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)	6.1	6.1	1.8	6.1	6.1	1.8
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel						
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)			28.7			28.7
Detector 2 Size(m)			1.8			1.8
Detector 2 Type			Cl+Ex			Cl+Ex
Detector 2 Channel						
Detector 2 Extend (s)			0.0			0.0
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2

Lanes, Volumes, Timings  
1: Whites Road South & Bayly Street


Future Total 2037 PM  
PM Peak Hour

Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Permitted Phases	8	8		5		
Detector Phase	8	2	5	5	2	2
Switch Phase						
Minimum Initial (s)	8.0	20.0	20.0	20.0	20.0	20.0
Minimum Split (s)	32.0	27.0	39.0	39.0	27.0	27.0
Total Split (s)	35.2	30.8	44.0	44.0	30.8	30.8
Total Split (%)	32.0%	28.0%	40.0%	40.0%	28.0%	28.0%
Maximum Green (s)	28.8	23.8	37.0	37.0	23.8	23.8
Yellow Time (s)	4.2	4.4	4.4	4.4	4.4	4.4
All-Red Time (s)	2.2	2.6	2.6	2.6	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lead/Lag						
Lead-Lag Optimize?						
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Recall Mode	None	C-Max	None	None	C-Max	C-Max
Walk Time (s)	7.0	5.0	7.0	7.0	5.0	5.0
Flash Dont Walk (s)	18.0	5.0	25.0	25.0	5.0	5.0
Pedestrian Calls (#/hr)	0	0	0	0	0	0
Act Effct Green (s)	15.1	69.3	26.7	26.7	47.8	47.8
Actuated g/C Ratio	0.14	0.63	0.24	0.24	0.43	0.43
v/c Ratio	0.65	0.35	0.72	0.42	0.64	0.64
Control Delay	56.7	8.6	59.1	28.8	32.1	28.8
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	56.7	8.6	59.1	28.8	32.1	28.8
LOS	E	A	E	C	C	C
Approach Delay	23.3		51.3			29.9
Approach LOS	C		D			C

Intersection Summary

Area Type: Other  
 Cycle Length: 110  
 Actuated Cycle Length: 110  
 Offset: 33 (30%), Referenced to phase 2:SBTL and 6:, Start of Green  
 Natural Cycle: 100  
 Control Type: Actuated-Coordinated  
 Maximum v/c Ratio: 0.72  
 Intersection Signal Delay: 35.1  
 Intersection LOS: D  
 Intersection Capacity Utilization 66.9%  
 ICU Level of Service C  
 Analysis Period (min) 15

Splits and Phases: 1: Whites Road South & Bayly Street



Queues  
1: Whites Road South & Bayly Street

Future Total 2037 PM  
PM Peak Hour



Lane Group	WBL	WBR	NBT	NBR	SBL	SBT
Lane Group Flow (vph)	159	364	618	212	452	930
v/c Ratio	0.65	0.35	0.72	0.42	0.64	0.64
Control Delay	56.7	8.6	59.1	28.8	32.1	28.8
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	56.7	8.6	59.1	28.8	32.1	28.8
Queue Length 50th (m)	32.7	23.6	71.5	20.1	80.9	83.1
Queue Length 95th (m)	51.1	48.3	m85.2	m32.6	#160.9	#137.3
Internal Link Dist (m)	352.4		176.0			197.2
Turn Bay Length (m)				30.0	70.0	
Base Capacity (vph)	468	1054	1192	638	707	1463
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.34	0.35	0.52	0.33	0.64	0.64

Intersection Summary
















# 95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

m Volume for 95th percentile queue is metered by upstream signal.

HCM Signalized Intersection Capacity Analysis  
 1: Whites Road South & Bayly Street























Future Total 2037 PM  
 PM Peak Hour

						
Movement	WBL	WBR	NBT	NBR	SBL	SBT
Lane Configurations			 			  
Traffic Volume (vph)	151	346	587	201	753	560
Future Volume (vph)	151	346	587	201	753	560
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Lane Util. Factor	1.00	1.00	0.95	1.00	0.91	0.91
Frt	1.00	0.85	1.00	0.85	1.00	1.00
Flt Protected	0.95	1.00	1.00	1.00	0.95	0.98
Satd. Flow (prot)	1789	1617	3544	1585	1628	3366
Flt Permitted	0.95	1.00	1.00	1.00	0.95	0.98
Satd. Flow (perm)	1789	1617	3544	1585	1628	3366
Peak-hour factor, PHF	0.95	0.95	0.95	0.95	0.95	0.95
Adj. Flow (vph)	159	364	618	212	793	589
RTOR Reduction (vph)	0	41	0	120	0	0
Lane Group Flow (vph)	159	323	618	92	452	930
Heavy Vehicles (%)	2%	1%	3%	3%	2%	2%
Turn Type	Perm	pm+ov	NA	Perm	Split	NA
Protected Phases		2	5		2	2
Permitted Phases	8	8		5		
Actuated Green, G (s)	15.1	62.9	26.7	26.7	47.8	47.8
Effective Green, g (s)	15.1	62.9	26.7	26.7	47.8	47.8
Actuated g/C Ratio	0.14	0.57	0.24	0.24	0.43	0.43
Clearance Time (s)	6.4	7.0	7.0	7.0	7.0	7.0
Vehicle Extension (s)	3.0	3.0	3.0	3.0	3.0	3.0
Lane Grp Cap (vph)	245	924	860	384	707	1462
v/s Ratio Prot		0.15	c0.17		c0.28	0.28
v/s Ratio Perm	c0.09	0.05		0.06		
v/c Ratio	0.65	0.35	0.72	0.24	0.64	0.64
Uniform Delay, d1	44.9	12.6	38.2	33.5	24.4	24.3
Progression Factor	1.00	1.00	1.46	2.88	1.00	1.00
Incremental Delay, d2	5.8	0.2	2.3	0.3	4.4	2.1
Delay (s)	50.8	12.8	58.1	96.5	28.7	26.4
Level of Service	D	B	E	F	C	C
Approach Delay (s)	24.4		67.9			27.2
Approach LOS	C		E			C
<b>Intersection Summary</b>						
HCM 2000 Control Delay			39.0		HCM 2000 Level of Service	D
HCM 2000 Volume to Capacity ratio			0.66			
Actuated Cycle Length (s)			110.0		Sum of lost time (s)	20.4
Intersection Capacity Utilization			66.9%		ICU Level of Service	C
Analysis Period (min)			15			
c Critical Lane Group						



Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive

Future Total 2037 PM  
PM Peak Hour

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	449	77	13	10	62	203	19	111	14	274	198	238
Future Volume (vph)	449	77	13	10	62	203	19	111	14	274	198	238
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Storage Length (m)	20.0		0.0	15.0		15.0	20.0		0.0	20.0		0.0
Storage Lanes	1		0	1		1	1		0	1		1
Taper Length (m)	40.0			10.0			40.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt		0.978				0.850		0.983				0.850
Flt Protected	0.950			0.950			0.950			0.950		
Satd. Flow (prot)	1706	1879	0	1659	1921	1601	1825	1855	0	1807	1902	1570
Flt Permitted	0.550			0.694			0.618			0.671		
Satd. Flow (perm)	988	1879	0	1212	1921	1601	1187	1855	0	1276	1902	1570
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)		12				218		6				256
Link Speed (k/h)		50			50			60				60
Link Distance (m)		78.3			208.1			259.8				200.0
Travel Time (s)		5.6			15.0			15.6				12.0
Peak Hour Factor	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93
Heavy Vehicles (%)	4%	0%	0%	10%	0%	2%	0%	2%	0%	1%	1%	4%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Adj. Flow (vph)	483	83	14	11	67	218	20	119	15	295	213	256
Shared Lane Traffic (%)												
Lane Group Flow (vph)	483	97	0	11	67	218	20	134	0	295	213	256
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			3.7				3.7
Link Offset(m)		0.0			0.0			0.0				0.0
Crosswalk Width(m)		1.6			1.6			1.6				1.6
Two way Left Turn Lane												
Headway Factor	1.02	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2	1	1	2		1	2	1
Detector Template	Left	Thru		Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	6.1	30.5		6.1	30.5	6.1	6.1	30.5		6.1	30.5	6.1
Trailing Detector (m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	6.1	1.8		6.1	1.8	6.1	6.1	1.8		6.1	1.8	6.1
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		28.7			28.7			28.7				28.7
Detector 2 Size(m)		1.8			1.8			1.8				1.8
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex				Cl+Ex
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0				0.0
Turn Type	pm+pt	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm

Lanes, Volumes, Timings  
2: Whites Road South & Oklahoma Drive


Future Total 2037 PM  
PM Peak Hour

Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Protected Phases	7	4			8			2			6	
Permitted Phases	4			8	8	8	2			6		6
Detector Phase	7	4		8	8	8	2	2		6	6	6
Switch Phase												
Minimum Initial (s)	5.0	8.0		8.0	8.0	8.0	20.0	20.0		20.0	20.0	20.0
Minimum Split (s)	9.5	36.0		36.0	36.0	36.0	32.0	32.0		32.0	32.0	32.0
Total Split (s)	29.0	65.0		36.0	36.0	36.0	45.0	45.0		45.0	45.0	45.0
Total Split (%)	26.4%	59.1%		32.7%	32.7%	32.7%	40.9%	40.9%		40.9%	40.9%	40.9%
Maximum Green (s)	26.0	58.8		29.8	29.8	29.8	38.7	38.7		38.7	38.7	38.7
Yellow Time (s)	3.0	3.3		3.3	3.3	3.3	4.2	4.2		4.2	4.2	4.2
All-Red Time (s)	0.0	2.9		2.9	2.9	2.9	2.1	2.1		2.1	2.1	2.1
Lost Time Adjust (s)	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lead/Lag	Lead			Lag	Lag	Lag						
Lead-Lag Optimize?	Yes			Yes	Yes	Yes						
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Recall Mode	None	None		None	None	None	C-Max	C-Max		C-Max	C-Max	C-Max
Walk Time (s)		7.0		7.0	7.0	7.0	7.0	7.0		7.0	7.0	7.0
Flash Dont Walk (s)		22.0		22.0	22.0	22.0	18.0	18.0		18.0	18.0	18.0
Pedestrian Calls (#/hr)		0		0	0	0	0	0		0	0	0
Act Effct Green (s)	42.3	39.1		10.1	10.1	10.1	58.4	58.4		58.4	58.4	58.4
Actuated g/C Ratio	0.38	0.36		0.09	0.09	0.09	0.53	0.53		0.53	0.53	0.53
v/c Ratio	0.88	0.14		0.10	0.38	0.63	0.03	0.14		0.44	0.21	0.27
Control Delay	47.9	21.0		45.9	52.4	14.8	13.6	13.5		6.9	4.5	2.0
Queue Delay	0.0	0.0		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	47.9	21.0		45.9	52.4	14.8	13.6	13.5		6.9	4.5	2.0
LOS	D	C		D	D	B	B	B		A	A	A
Approach Delay		43.4			24.5			13.5			4.6	
Approach LOS		D			C			B			A	

Intersection Summary

Area Type:	Other
Cycle Length:	110
Actuated Cycle Length:	110
Offset:	40.7 (37%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green
Natural Cycle:	80
Control Type:	Actuated-Coordinated
Maximum v/c Ratio:	0.88
Intersection Signal Delay:	21.2
Intersection LOS:	C
Intersection Capacity Utilization:	80.5%
ICU Level of Service:	D
Analysis Period (min):	15

Splits and Phases: 2: Whites Road South & Oklahoma Drive



Queues  
2: Whites Road South & Oklahoma Drive

Future Total 2037 PM  
PM Peak Hour



Lane Group	EBL	EBT	WBL	WBT	WBR	NBL	NBT	SBL	SBT	SBR
Lane Group Flow (vph)	483	97	11	67	218	20	134	295	213	256
v/c Ratio	0.88	0.14	0.10	0.38	0.63	0.03	0.14	0.44	0.21	0.27
Control Delay	47.9	21.0	45.9	52.4	14.8	13.6	13.5	6.9	4.5	2.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	47.9	21.0	45.9	52.4	14.8	13.6	13.5	6.9	4.5	2.0
Queue Length 50th (m)	89.2	12.4	2.2	13.9	0.0	1.9	13.0	14.9	10.7	3.1
Queue Length 95th (m)	#127.2	22.1	7.4	26.3	20.8	6.3	25.6	21.1	15.6	6.7
Internal Link Dist (m)		54.3		184.1			235.8		176.0	
Turn Bay Length (m)	20.0		15.0		15.0	20.0		20.0		
Base Capacity (vph)	549	1009	328	520	592	629	987	676	1009	953
Starvation Cap Reductn	0	0	0	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0	0	0	0
Reduced v/c Ratio	0.88	0.10	0.03	0.13	0.37	0.03	0.14	0.44	0.21	0.27























Intersection Summary

# 95th percentile volume exceeds capacity, queue may be longer.  
Queue shown is maximum after two cycles.

# HCM Signalized Intersection Capacity Analysis

## 2: Whites Road South & Oklahoma Drive

Future Total 2037 PM  
PM Peak Hour

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	449	77	13	10	62	203	19	111	14	274	198	238
Future Volume (vph)	449	77	13	10	62	203	19	111	14	274	198	238
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Lane Util. Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		1.00	1.00	1.00
Frt	1.00	0.98		1.00	1.00	0.85	1.00	0.98		1.00	1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00	1.00	0.95	1.00		0.95	1.00	1.00
Satd. Flow (prot)	1706	1880		1659	1921	1601	1825	1856		1807	1902	1570
Flt Permitted	0.55	1.00		0.69	1.00	1.00	0.62	1.00		0.67	1.00	1.00
Satd. Flow (perm)	987	1880		1212	1921	1601	1187	1856		1277	1902	1570
Peak-hour factor, PHF	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93
Adj. Flow (vph)	483	83	14	11	67	218	20	119	15	295	213	256
RTOR Reduction (vph)	0	8	0	0	0	198	0	3	0	0	0	120
Lane Group Flow (vph)	483	89	0	11	67	20	20	131	0	295	213	136
Heavy Vehicles (%)	4%	0%	0%	10%	0%	2%	0%	2%	0%	1%	1%	4%
Bus Blockages (#/hr)	7	0	12	0	0	0	0	0	0	0	0	0
Turn Type	pm+pt	NA		Perm	NA	Perm	Perm	NA		Perm	NA	Perm
Protected Phases	7	4			8			2				6
Permitted Phases	4			8		8	2			6		6
Actuated Green, G (s)	39.1	39.1		10.1	10.1	10.1	58.4	58.4		58.4	58.4	58.4
Effective Green, g (s)	39.1	39.1		10.1	10.1	10.1	58.4	58.4		58.4	58.4	58.4
Actuated g/C Ratio	0.36	0.36		0.09	0.09	0.09	0.53	0.53		0.53	0.53	0.53
Clearance Time (s)	3.0	6.2		6.2	6.2	6.2	6.3	6.3		6.3	6.3	6.3
Vehicle Extension (s)	3.0	3.0		3.0	3.0	3.0	3.0	3.0		3.0	3.0	3.0
Lane Grp Cap (vph)	520	668		111	176	147	630	985		677	1009	833
v/s Ratio Prot	c0.22	0.05			0.03			0.07				0.11
v/s Ratio Perm	c0.11			0.01		0.01	0.02			c0.23		0.09
v/c Ratio	0.93	0.13		0.10	0.38	0.14	0.03	0.13		0.44	0.21	0.16
Uniform Delay, d1	32.2	24.0		45.8	47.0	45.9	12.3	13.0		15.7	13.6	13.3
Progression Factor	1.00	1.00		1.00	1.00	1.00	1.00	1.00		0.31	0.29	0.74
Incremental Delay, d2	23.0	0.1		0.4	1.4	0.4	0.1	0.3		1.7	0.4	0.4
Delay (s)	55.1	24.1		46.2	48.4	46.4	12.4	13.3		6.5	4.3	10.2
Level of Service	E	C		D	D	D	B	B		A	A	B
Approach Delay (s)		49.9			46.8			13.2			7.1	
Approach LOS		D			D			B			A	
<b>Intersection Summary</b>												
HCM 2000 Control Delay	28.0			HCM 2000 Level of Service				C				
HCM 2000 Volume to Capacity ratio	0.65											
Actuated Cycle Length (s)	110.0			Sum of lost time (s)				15.5				
Intersection Capacity Utilization	80.5%			ICU Level of Service				D				
Analysis Period (min)	15											

c Critical Lane Group

Lanes, Volumes, Timings  
3: Granite Court/Oaklahoma Drive

Future Total 2037 PM  
PM Peak Hour



Lane Group	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (vph)	5	509	270	50	31	3
Future Volume (vph)	5	509	270	50	31	3
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00
Frt			0.979		0.989	
Flt Protected					0.956	
Satd. Flow (prot)	0	1883	1844	0	1781	0
Flt Permitted					0.956	
Satd. Flow (perm)	0	1883	1844	0	1781	0
Link Speed (k/h)		50	50		48	
Link Distance (m)		466.2	78.3		125.8	
Travel Time (s)		33.6	5.6		9.4	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	5	553	293	54	34	3
Shared Lane Traffic (%)						
Lane Group Flow (vph)	0	558	347	0	37	0
Enter Blocked Intersection	No	No	No	No	No	No
Lane Alignment	Left	Left	Left	Right	Left	Right
Median Width(m)		3.7	3.7		3.7	
Link Offset(m)		0.0	0.0		0.0	
Crosswalk Width(m)		1.6	1.6		1.6	
Two way Left Turn Lane						
Headway Factor	0.99	0.99	0.99	0.99	0.99	0.99
Turning Speed (k/h)	24			14	24	14
Sign Control		Free	Free		Stop	


Intersection Summary

Area Type:	Other
Control Type:	Unsignalized
Intersection Capacity Utilization	40.8%
Analysis Period (min)	15
	ICU Level of Service A

# HCM Unsignalized Intersection Capacity Analysis

## 3: Granite Court/Oaklahoma Drive

Future Total 2037 PM  
PM Peak Hour



Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		↔	↔		↔	
Traffic Volume (veh/h)	5	509	270	50	31	3
Future Volume (Veh/h)	5	509	270	50	31	3
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	5	553	293	54	34	3
Pedestrians						
Lane Width (m)						
Walking Speed (m/s)						
Percent Blockage						
Right turn flare (veh)						
Median type		None	None			
Median storage veh						
Upstream signal (m)			78			
pX, platoon unblocked	0.97				0.97	0.97
vC, conflicting volume	347				883	320
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	314				865	286
tC, single (s)	4.1				6.4	6.2
tC, 2 stage (s)						
tF (s)	2.2				3.5	3.3
p0 queue free %	100				89	100
cM capacity (veh/h)	1212				314	732
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total	558	347	37			
Volume Left	5	0	34			
Volume Right	0	54	3			
cSH	1212	1700	329			
Volume to Capacity	0.00	0.20	0.11			
Queue Length 95th (m)	0.1	0.0	2.9			
Control Delay (s)	0.1	0.0	17.3			
Lane LOS	A		C			
Approach Delay (s)	0.1	0.0	17.3			
Approach LOS			C			
Intersection Summary						
Average Delay			0.8			
Intersection Capacity Utilization			40.8%		ICU Level of Service	A
Analysis Period (min)			15			

---

**Network Totals**

---

Number of Intersections	3
Total Delay (hr)	35
Stops (#)	2729
Average Speed (km/hr)	21
Total Travel Time (hr)	56
Distance Traveled (km)	1182
Fuel Consumed (l)	286
Fuel Economy (km/l)	4.1
Unserved Vehicles (#)	0
Vehicles in dilemma zone (#)	58
Performance Index	42.9

# **Appendix F**

**AutoTURN Circulation Review**






www.ghd.com

GHD Ltd.  
111 Brunel Road, Suite 200  
Mississauga, Ontario L4Z 1X3 Canada  
T 1 905 712 0510 F 1 905 712 0515

Conditions of Use  
This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD. This document may only be used by GHD's client (and any other person who GHD has agreed can use this document) for the purpose for which it was prepared and must not be used by any other person or for any other purpose.



Bar is 25mm on original size sheet  
0 25mm



Durham Front-end Garbage  
meters  
Width : 2.77  
Track : 2.60  
Lock to Lock Time 6.0  
Steering Angle : 28.5

No.	Issue	Checked	W.M	W.M	Approved	Date
1	First Submission					4/12/23

Author J.E Designer J.E

Drafting Check W.M Design Check W.M

Project Manager W.M Project Director W.M

Client -


Project  
720 Granite Court

Date April 12, 2023 Scale NTS

Project No. -

Title  
VEHICLE MANEUVERING  
DIAGRAM -  
GARBAGE TRUCK  
(INBOUND)

Sheet No.  
AT-101







www.ghd.com

GHD Ltd.  
111 Brunel Road, Suite 200  
Mississauga, Ontario L4Z 1X3 Canada  
T 1 905 712 0510 F 1 905 712 0515

Conditions of Use  
This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD. This document may only be used by GHD's client (and any other person who GHD has agreed can use this document) for the purpose for which it was prepared and must not be used by any other person or for any other purpose.



Bar is 25mm on original size sheet  
0 25mm



Durham Front-end Garbage  
meters  
Width : 2.77  
Track : 2.60  
Lock to Lock Time 6.0  
Steering Angle : 28.5

No.	Issue	Checked	W.M	W.M	4/12/23	Date
1	First Submission					

Author J.E Designer J.E

Drafting Check W.M Design Check W.M

Project Manager W.M Project Director W.M

Client -


Project  
720 Granite Court

Date April 12, 2023 Scale NTS

Project No. -

Title  
VEHICLE MANEUVERING  
DIAGRAM -  
GARBAGE TRUCK  
(OUTBOUND)

Sheet No.  
AT-102







www.ghd.com

GHD Ltd.  
111 Brunel Road, Suite 200  
Mississauga, Ontario L4Z 1X3 Canada  
T 1 905 712 0510 F 1 905 712 0515

Conditions of Use  
This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD. This document may only be used by GHD's client (and any other person who GHD has agreed can use this document) for the purpose for which it was prepared and must not be used by any other person or for any other purpose.



Bar is 25mm on original size sheet  
0 25mm



MSU meters  
Width : 2.60  
Track : 2.60  
Lock to Lock Time : 6.0  
Steering Angle : 40.2

No.	Issue	Checked	Approved	Date
1	First Submission	W.M	W.M	4/12/23

Author J.E Designer J.E

Drafting Check W.M Design Check W.M

Project Manager W.M Project Director W.M

Client -

Project 720 Granite Court


Date April 12, 2023 Scale NTS

Project No. -

Title VEHICLE MANEUVERING DIAGRAM - MSU TRUCK (INBOUND)

Size ANSI D

Sheet No. AT-103







www.ghd.com

GHD Ltd.  
111 Brunel Road, Suite 200  
Mississauga, Ontario L4Z 1X3 Canada  
T 1 905 712 0510 F 1 905 712 0515

Conditions of Use  
This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD. This document may only be used by GHD's client (and any other person who GHD has agreed can use this document) for the purpose for which it was prepared and must not be used by any other person or for any other purpose.



Bar is 25mm on original size sheet  
0 25mm



MSU meters  
Width : 2.60  
Track : 2.60  
Lock to Lock Time : 6.0  
Steering Angle : 40.2

No.	Issue	Checked	W.M	W.M	Approved	Date
1	First Submission					4/12/23

Author J.E Designer J.E

Drafting Check W.M Design Check W.M

Project Manager W.M Project Director W.M

Client -

Project 720 Granite Court


Date April 12, 2023 Scale NTS

Project No. -

Title VEHICLE MANEUVERING DIAGRAM - MSU TRUCK (OUTBOUND)

Size ANSI D

Sheet No. AT-104







www.ghd.com

GHD Ltd.  
111 Brunel Road, Suite 200  
Mississauga, Ontario L4Z 1X3 Canada  
T 1 905 712 0510 F 1 905 712 0515

Conditions of Use  
This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD. This document may only be used by GHD's client (and any other person who GHD has agreed can use this document) for the purpose for which it was prepared and must not be used by any other person or for any other purpose.



Bar is 25mm on original size sheet  
0 25mm



P  
Width : 2.00 meters  
Track : 2.00  
Lock to Lock Time : 6.0  
Steering Angle : 35.9

No.	Issue	Checked	W.M	W.M	4/12/23	Date
1	First Submission					

Author J.E Designer J.E

Drafting Check W.M Design Check W.M

Project Manager W.M Project Director W.M

Client -

Project  
720 Granite Court


Date April 12, 2023 Scale NTS

Project No. -

Title  
VEHICLE MANEUVERING  
DIAGRAM -  
PASSENGER CAR  
(INBOUND)

Size  
ANSI D

Sheet No.  
AT-105







www.ghd.com

GHD Ltd.  
111 Brunel Road, Suite 200  
Mississauga, Ontario L4Z 1X3 Canada  
T 1 905 712 0510 F 1 905 712 0515

Conditions of Use  
This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD. This document may only be used by GHD's client (and any other person who GHD has agreed can use this document) for the purpose for which it was prepared and must not be used by any other person or for any other purpose.



Bar is 25mm on original size sheet  
0 25mm



P  
Width : 2.00 meters  
Track : 2.00  
Lock to Lock Time: 6.0  
Steering Angle : 35.9

No.	Issue	Checked	W.M	W.M	Approved	Date
1	First Submission					4/12/23

Author J.E Designer J.E

Drafting Check W.M Design Check W.M

Project Manager W.M Project Director W.M

Client -

Project  
720 Granite Court


Date April 12, 2023 Scale NTS

Project No. -

Title  
VEHICLE MANEUVERING  
DIAGRAM -  
PASSENGER CAR  
(OUTBOUND)

Size  
ANSI D

Sheet No.  
AT-106







www.ghd.com

GHD Ltd.  
111 Brunel Road, Suite 200  
Mississauga, Ontario L4Z 1X3 Canada  
T 1 905 712 0510 F 1 905 712 0515

Conditions of Use  
This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD. This document may only be used by GHD's client (and any other person who GHD has agreed can use this document) for the purpose for which it was prepared and must not be used by any other person or for any other purpose.



Bar is 25mm on original size sheet  
0 25mm



P  
Width : 2.00 meters  
Track : 2.00  
Lock to Lock Time : 6.0  
Steering Angle : 35.9

No.	Issue	Checked	W.M	W.M	4/12/23	Date
1	First Submission					

Author J.E Designer J.E

Drafting Check W.M Design Check W.M

Project Manager W.M Project Director W.M

Client -


Project 720 Granite Court

Date April 12, 2023 Scale NTS

Project No. -

Title VEHICLE MANEUVERING DIAGRAM - PASSENGER CAR (P1 RAMP MOVEMENT)

Sheet No. AT-107






www.ghd.com

GHD Ltd.  
111 Brunel Road, Suite 200  
Mississauga, Ontario L4Z 1X3 Canada  
T 1 905 712 0510 F 1 905 712 0515

Conditions of Use  
This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD. This document may only be used by GHD's client (and any other person who GHD has agreed can use this document) for the purpose for which it was prepared and must not be used by any other person or for any other purpose.



Bar is 25mm on original size sheet  
0 25mm



P  
Width : 2.00 meters  
Track : 2.00  
Lock to Lock Time : 6.0  
Steering Angle : 35.9

No.	Issue	Checked	Approved	Date
1	First Submission	W.M	W.M	4/12/23

Author J.E Designer J.E  
 Drafting Check W.M Design Check W.M  
 Project Manager W.M Project Director W.M

Client -

Project 720 Granite Court

Date April 12, 2023 Scale NTS

Project No. -

Title VEHICLE MANEUVERING DIAGRAM - PASSENGER CAR (P2 RAMP MOVEMENT)

Sheet No. AT-108

